

BOQ OF INTERIOR FURNISHING WORK OF CANARA BANK BRANCH & ATM AT PUSAD, MAHARASHTRA.

ITEMS OF WORKS	UNIT	QUANTITY	RATE	AMOUNT
A) Branch Furnishing Work				
1) Full Height Both Side Laminated Partition with door: made out of Alluminium section (2"x2") network 2'x2' bothways horizontally & vertically with 6 mm th.MR grade ply with antitermite treatment & 1 mm th laminate on both sides as per approved shade with groovers with necessary hardware complete with provision to run electrical conduits, cutouts .complete as per design, details ,direction.for Record room,UPS Room including similler door handles, hinges, door closure complete with Vision Pannel(Partition shall be measured upto False ceiling Height Only)	Sq.Ft.	600.00		
2) Full Height Partly Glazed Partition With Doors (manager cabin,front partition) Providing & Fixing in Position Full Height Partly Glazed Partition made out of Alluminium section (2"x2") network 2'x2' bothways horizontally & vertically with 6 mm th.MR grade ply with antitermite treatment & 1 mm th laminate as per approved shade with grooves including Clear float glass 8/10 mm th with itching upto 7' height with provision to run electrical conduits, cutouts Etc.complete.forFront partition & Branch Manager's cabin including similler door with floor Spring (Dorma or Equivalent) , hinges,handles, lock complete(Partition shall be measured upto False ceiling Height Only)	Sq.Ft.	230.00		
3)Main Entrance Door : Providing and fixing of main entrance double Leaf door of size (6'0"x8'0") to be made out of .MR grade ply with antitermite treatment & 1 mm th laminate as per approved shade with grooves including Clear float glass 8/10 mm th with itching and Bank Logo, Cost include necessary hardwares like door handle CP Brass 600 mm -02 nos., locks, Stopper etc. complete. The rate also include providing and fixing of Frosted film upto a height of 3 feet on the door. The rate includes Providing and fixing of floor spring -Ozone / Dorma make with cutting floor etc. Complete	Sqft	60.00		
4) Low Height Partition .Provideing & Fixing in position low height Partition upto 5'0" "height made out of Alluminium section.(2" x 2") frame work max. 2' c/c both horizontally & vertically claddd with 6 mm th. MR grade ply (confirming to IS 303 of 1989) with anti termite treatment & 1 mm laminates fixed with adhesive of approved make design , colour, texture as per given pattern , grooves with provision to run electrical conduits, cutouts complete as per design, details ,direction.	Sq.Ft.	150.00		
5)Cash Cabin Enclosure: Providing & Fixing Cash cabin Enclosure 5' height with Alluminium sections(2"x2") 2' c/c apart both horizontally and vertically fitted with cleats & screws fastened with wall ,ceiling & flooring with 6 mm th. MR grade (confirming to IS 303 OF 1989) PLY finished with 1 mm laminates of approved make shade colour texture in directed pattern, fixed with standard Adhesive with 8 mm thick glass with itching & edge polishing with door including Lock , night latch, hinges complete as per Design/Instructions. The rate also includes providing of wooden trays for passing slips.	Sq.Ft.	85.00		

ITEMS OF WORKS	UNIT	QUANTITY	RATE	AMOUNT
6) Wicket Gate : Providing & Fixing in Position Wicket Gate made out of Alluminium section (2"x2") network 2'x2' bothways horizontally & vertically with 6 mm th.MR grade ply both side with antitermite treatment & 1 mm th laminate as per approved shade with groovers including hinges,lock,night latch, door stoper complete as per design, direction.	Sq.Ft.	20.00		
7)Clerical/Swo/Officer Counter: Providing and fitting in position clerical counter low height 2'-6" wide and 2'-6" high as per the instructions / directions made out of 19 mm th MR grade(confirming to IS code) ply finished with 1 mm laminate of approved make ,shade ,colour, texture in directed pattern with free edges covered with T.W. beading polished comprising of drawer and shelf unit out of 12 mm MR grade ply on 3 sides and bottom and the front out of 19 mm block board fitted with telescopic channels ,locks s.s. handles , cable manager ,hinges locks etc. with foot rest and plank for P.C. and ready made key board drawer of plastic/metal of approved make and all necessary accessories suitably suspended below table top and painting internally etc. complete.	R.Ft.	13.00		
8)Cash Counter: Providing and erecting in position Cash Counter (SWC) as per design working top 2'6"ht and customer end at 4' ht and 2'6" width as per drawings and instructions / directions made out of 18 mm th ply BWR grade(confirming to IS 303 of 1989) finished with 1 mm laminate of approved make ,shade ,colour, texture in directed pattern with free edges covered with T.W. beading polished , of drawer and shelf unit out of 19 mm MR grade ply for sides and bottom and the front , cable manager ,hinges locks etc. with foot rest and plank for P.C. and ready made key board drawer of approved make and all necessary accessories suitably suspended below table top painting internally etc complete.)(Provision of Currency Drawers shelves should be made). The counter to have another tier at a height of 3'10" from the floor level. The counter top to be finished with 18 mm plywood with laminate as per design	R.Ft.	6.00		
9)Cash/Swo Counter Frontage: Providing and fixing of 12 mm thick clear float glass to be fixed with clips / bidding in the cash cabin frontage , swo/officer counter frontage & on BM Table Top with edge polishing &making cutout in Cash cabin frontage complete	Sq.Ft.	65.00		
10)Tables: Providing & Fixing in position Tables made out of 19 mm th. MR gade (confirming to IS 303 OF 1989) PLY finished with 1 mm laminates of approved make shade colour texture in directed pattern with painting internally comprising 400x500x600 mm (WxDxH) drawers cum cabinates/shelf unit out of 12/6 mm th. MR grade (confirming to IS 303 OF 1989)ply and 1 mm laminate with locks, handles,sliding channels, Cable Manaers, foot rest, shelf for C.P.U. etc. with ready made key board drawer of approved make.including all necessary accessories & painting internally.complete as per design instruction & direction.				
a) Branch Manager's Table set size:6' x 3'0" x2'6" with side Credenza 3' x 1'4"x2'6" (Table top to be provided with 8 mm th clear float glass with edge polishing	No.	1.00		
b)Officer's / Clerical Table size:5'6" x 2'6" x2'6"	No.	2.00		
c)Cash Sorting Table size: 4'9"x 1'9" x 2'6"	No.	1.00		
d)Staff Table size:5' x 2'6" x2'6"	No.	2.00		
11) Electrical Pannel Main Board : Providing & Fixing in position Electrical Pannel Main Board with Louvered openable shutter with T.W. frame & 12 mm th ply & 1mm th. Laminate including hinges Locking arrangements complete as per design / direction.	Sq.Ft.	40.00		

ITEMS OF WORKS	UNIT	QUANTITY	RATE	AMOUNT
12)Drop Box : Providing & fixing in position Drop Box size 1'3" x 2' x 8" made out of 12mm th. Ply & 1 mm th. Laminate on external surface with openable door with clear glass with hinges , locking arrangements painting internally with enamel paint complete as per design & direction.	No.	1.00		
13)Suggestion Box :Providing & fixing in position Complaint Box size 1'3" x 2' x 8" made out of 12mm th. Ply & 1 mm th. Laminate on external surface with openable door with clear glass with hinges , locking arrangements painting internally with enamel paint complete as per design & direction.	No.	1.00		
14)Writing Ledge : Supplying & Erecting wall mounted Customer's writing Ledgeof size 3' x1' made out of 12 mm th. Glass with machine polished edges float glass supported withvacuum bush on 12 mm ply slots box for slips with laminates on external surface complete as per design/direction.	R.Ft.	3.00		
15)Notice Board :Providing & Fixing Notice Board of Size: 5' x 3' made out of 12 mm th. Soft board cladded with cloth on box made out of 19 mm th. MR ply complete.	No.	2.00		
16)Storage: a) Low Height Storage : Providing & Fixing Low Height Storage (1'4" deep) made out of 19 mm th. MR gade (confirming to IS 303 OF 1989) PLY finished with 1 mm laminates of approved make shade colour texture in directed pattern with internal shelves & internal finish in polish complete with locks, handles, hinges complete.	Sq.Ft.	40.00		
b)Full Height Storage(8'ht.) : Providing & Fixing full Height Storage (1'4" deep) made out of 19 mm th.BWR gade (confirming to IS 303 OF 1989) PLY finished with 1 mm laminates of approved make shade colour texture in directed pattern with internal shelves & internal finish in polish complete with locks, handles, hinges complete.	Sq.Ft.	200.00		
17) False Ceiling : a)Gypsum Board Ceiling :Providing & Fixing suspended false ceiling including G.I. Section 0.40 mm or .45 mm thick G.I. main runner bottom 760 mm center ceiling section 457 mm center & hanger supporting Nylon sleev 900 mm center to center with 12.5 mm Gypsum board as per design/direction complete.(using 800 gm, bottom member & 300 gm. Angle) including CFL/ LED light cutout and 2 coats of Plastic paint White colour	Sq.Ft.	430.00		
b) Grid False Ceiling : Providing & Fixing of saint Gobin make Grid False ceiling of size 600x600x15 mm th mineral fiber board suspended by using T 15 ceiling system including G.I. main, cross, wall angle member including all accessories , including CFL/ LED light cutout and 2 coats of Plastic paint White colour	Sq.Ft.	785.00		
18)Column/Wall Paneling : Providing and fixing wall / coloum panelling made out of 2"x 1" ALUMINIUM frame works at 2'-0" c/c in both ways, 6mm thick MR Grade ply and 1.0mm thick laminate finish of approved quality and as per the designs and details.	Sq.Ft.	385.00		
19)Rolling Shutter Boxing : Providing and fixing rolling shutter boxing by using 2" X 2" aluminium frame work to be cladded with 3 mm thick aluminium composite panel (silver gray colour) with provision for openable shutter for Rolling Shutter Greasing	Sq.Ft.	200		
20)Vertical Blinds :Providing & Fixing 4" wide Vertical Blinds of approved Shed & quality with necessary imported runners , fittings complete	Sq.Ft.	70.00		
21) Flush Door : Providing and fixing of flush door with laminate on external surface & edges to be provided with T.W. Lipping with Handles, Hinges, Lock complete	Sq.Ft.	90.00		
Total Cost (A) of Furnishing Work				0.00

ITEMS OF WORKS	UNIT	QUANTITY	RATE	AMOUNT
B) ATM Furnishing Work				
1)Main Entrance Partition With Door : Providing and fixing of main entrance partition with door of size(3'6"x7'0") to be made out of 12 mm th. toughened glass for partition/door including making cutout,holes for handle,including top patch, bottom patch, corner patch, lock with strike plate complete including floor spring (Dorma/Ozone) including Providing and fixing of 35x600 mm C.P. Brass Handles on both sides Complete (Glass SAINT GOBIN,MODIGUARD, Patch fittings Dorma/Ozone)	Sqft	60.00		
2) Double Skin Partition: Providing and fixing in position double skin partition with door fully panelled with aluminium frame work of size 2" x 1" at 2'-0" c./c vertically and horizontally with fixing frame in position to ceiling floor and wall etc. with metal clamps / bolt etc cladded with 3 mm aluminium composite panel on one exposed face and backside with 6 mm thick MR Grade plywood to be painted with 2 coats of synthetic enamel paint as directed. The rate includes door panel with necessary brass fixtures like hinges, tower bolt, handles, ISI door clousure, clamps etc. locking arrangements cable manager etc. complete	Sq.Ft.	65		
3) False Ceiling : a)Gypsum Board Ceiling :Providing & Fixing suspended false ceiling including G.I. Section 0.40 mm or .45 mm thick G.I. main runner bottom 760 mm center ceiling section 457 mm center & hanger supporting Nylon sleev 900 mm center to center with 12.5 mm Gypsum board as per design/direction complete.(using 800 gm, bottom member & 300 gm. Angle) including CFL/ LED light cutout and 2 coats of Plastic paint White colour	Sq.Ft.	75.00		
b)Grid Ceiling: Providing and fixing in position False ceiling in G.I. Powder coated grid system with fine fissured mineral fibre board 600 x 600 mm x 14 mm thick RH-80 butt edge "ARMSTRONG" with necessary fittings perimeter, cutting for lighting fixtures etc. complete(ceiling needs to be brought down by 4' from R.C.C. slab)	Sq.Ft.	30		
4)Writing Ledge: Providing and fixing Acp Cladded glass top writing Ledge at 4'-0" level.of 1'-0"x2'-0" size complete.	R.Ft.	3		
5)Notice board: Providing and fixing 3'-0" x 2'-0" size notice board made out of 12 mm thick soft board with flannel blue colour cloth incased in a border out aluminium complete	No.	1		
6)Air Louvers: Providing and fixing in position in Air louvers partition Linear 4'-0"x6" Powder coated white or ivory including cutting fitting with necessary hardware and clamps etc. complete	Sq.Ft.	2		
7)Wall Cladding : Providing and supply and installing 3 mm Aluminium Composite Panel on a hollow box grid of 50 X 50 mm box on wall of approved colour including silicon sealant , making necessary cutouts upto ceiling height inclusive of wastage, cleaning etc. complete	Sq.Ft.	235		
Total Cost (C) (ATM Work)				
Final Total SECTION I BRANCH WORK + ATM WORK (A) + (B)				
GST EXTRA AS APPLICABLE				