

**BOQ FOR INTERIOR WORKS FOR CANARA BANK REGIONAL OFFICE NIZAMBAD - 1st FLOOR**

S.No	Description	Unit	Qty	Rate	Amount
	<b>INTERIOR FURNITURE WORK FOR BRANCH</b>				
1.0	<b>GYPSUM BOARD FALSE CEILING</b>				
	Providing & fixing as per design with suspended false ceiling consisting of 12mm.thk.Gyp. board suspended on G.I. framework to consists of G.I. perimeter channels 0.55 mm thk. x 20mm .x 30mm. along perimeter of false ceiling; screw fixed to wall/partition with nylon sleeves & screws @ 600mm. dc. Suspending GI. Intermediate channels of size 0.9mm thk.x45mmx15mm. from the soffit at max. distance 1220mm. dc with ceiling angle 0.55mm. thk.x2n5mm.x10mm. Fixed to soffit using proprietary supplied GI. Cleats & steel expansion fasteners. Ceiling section 0.55mm thk. xweb size 51.5mm & flanges 26mm. Each & 10.5 mm. lips fixed perpendicular to intermediate channel at 457mm. c/c Gyp board is screw fixed to ceiling section with 25mm. drywall screws at 230mm. c/c. boards to be finished with proprietary supplied jointing tape & jointing compound & sand papered to achieve a smooth finish etc.complete or as directed by the Architec/Bank. Gyp ceiling where necessary as normal specification Rate should include all types of cut-outs, grooves ,moulding & plain troughs for tube lights / Down Lighter as directed by the designer. Note: Where RCC Slab is old and concrete is weal, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carrid out before fixing Gypsum board fixing.Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical no extra will be given for vertical and borders and rate include with luppum ,painting upto 3 coats till smooth finish.	Sft.	2,345.00		
2.0	<b>ARMSTRONG FALSE CEILING</b>				
	Providing and fixing of Armstrong make Mineral fibre Ceiling Boards in true horizontal level suspended on inter locking Grid system made of Hot Dip Galvanized steel sections powder coated XL -15 mm as per manufacturers specification including making opening for electrical and air conditioning fitting complete as directed. The tiles and grid system FRAMEWORK XL-15 mm Main Runner of 3000mm spaced at 1200mm centre fixed to soffit by approved hangers at 1200mm distance. First and last hanger should not be at a distance more than 450mm from the adjacent wall.XL-15 mm 1200mm cross Tee to be interlocked between Main Runner at 600mm centre to form 1200x600mm module 600mmx600mm module to be formed by fixing XL-15mm 600mm Cross Tee between centre of 1200mm Cross Tees.19X19 mm Wall Angle to be secured to wall at 450mm centers Suspension to be done by using 2mm pre-straightened GI wire using anchor fasteners. Make - Armstrong - ANS Micro & Supra fine XL frame work. Note: Where RCC Slab is old and concrete is weal, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carrid out before fixing Gypsum board fixing.Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical	Sft.	1,765.00		
2a	Supply and Fixing of Decorative Ceiling to be made as per the material selected and Suggested by the like wood ,acleric sheet ,gypsum projections banks deign logo ,theme based design and as per the site situation /discussion given by the Architect /Client As per the Site Conditions on Front Lobby Base (Rate includes with material ,labour ,fixing ,lifting ,transportation and design and cutting charges will not be paid extra )	sft	300.00		
3.0	<b>FULL HT SOLID PARTITION</b>				
	Full Height Solid Partitions : Providing and Fixing of Full height partitions all made with Sall/Kail/Marandi wood frame of 2"x2" section with 2'0"x2'0" c/c vertically and horizontally. Frame to be covered with 8 mm plywood of (Century/Green /nikon) from both sides. 1mm thick laminate/Veneer of (Century/Bravia/Greenply) to be covered from both the sides of the partition. Frame should be properly fixed to the Floor, Vertical members should be firmly to the Slab and side wall available. Laminate should be considered up to two or three colour combination. All as per the design suggested at site and instructions of Architects.(Frame work above false ceiling done for fixidity shall not be measured but contractor may factor it while quoting their rate as measurements up to false ceiling level only be taken). Plywood wherever mentioned Must be BWR GRADE , MARKED ISI.Rate includes with glossy or matte finish lam as per the selection by the client	Sft.	1,655.00		
4.0	<b>SEMI GLAZED PARTITION WITH DOOR</b>				
	Full Ht. Partitions : Same as Item no 3 but 8mm toughened Glass with Etching design or One way vision film approved design should be provided with 35mm x 12mm Steam beach Molding duly melamine polished. This glass will be starting from 3'-0" ht from ffl .All as per the design and instructions of Architects. Plywood wherever mentioned BWR GRADE .AS GIVE IN THE ITEM .(AGM CABIN TWO SIDES )	Sft.	846.00		
5.0	<b>PARTLY GLAZED LOW HT PARTITION</b>				
	Low Ht /Half Ht Solid Partitions: Same as Item no 3 but Low ht or Half height as per design. Edges of the partition to be covered with 3"x1.5" Steam beach wood duly male mine polished moulding. All as per the design and instructions of the design in charge.ply wood wherever mentioned BWR GRADE IS 303,(AT WORK STATION AND BETWEEN TABLES)(Between workstations , 2 sides for section heads & DM cubical 2 sides).	Sft	532.00		

6.0	<b>TABLE ( Size:- 5'-6" OR 4'-6" x 2'-6" ) ht. 2'-6" :-</b> Providing and fixing tables made out of 19 mm thick commercial ply over hard wood frame work finished with <b>1.0mm Lam</b> of approved shade. Top having steam beech wood edging of size 2" x 1 3/4". 10mm thick clear float glass with beveled edges shall be provided on the finished to 19mm thk Comm.ply wood of approved make cladded with <b>Lam</b> as per design in all visible areas. All the exposed edges to be covered with wooden steam beech lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk ply wood with <b>1.0Lam</b> finish in the front , and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint/LAM & Table back side will be 1mm laminate. A leg rest to be provided duly polished made out of 3"x2" Wooden Section. A shutter to be made by 19mm ply wood cladded with <b>1.0mm thick Lam</b> .The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. The necessary wire managers(SS) to be provided on the tables and provision for lights to be kept if required in the front of the table. All the exposed areas to be polished The work to be completed as per design and approval of the Bank. The table should have key board tray and CPU Trolley to be Modular. <u>All as per the design and instructions Bank .( for DM table)</u>	RFT	52.50		
7.0	<b>UTILITY COUNTER ( 2'-0" WIDE ) :-</b> Providing and fixing of Utility Counter 2'-0" wide top made up of 19mm board pasted on 1.0 thl lam. The Top of table will be finish with <b>1.0mm thick lam</b> .all hardware fittings fixtures etc. The drawers to be made out of 19mm thk board with <b>1.0mm thick lam</b> finish in the front ,sides to be made out of 12mm plywood and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint. All exposed edges to have wooden lipping stained to match the desk and melamine finished.Design and detail of the table shall be as per design. (As per Site, Designing of Table and specification may be Changed). The works to include a keyboard try and CPU trolley to be modular. <u>All as per the design and instructions Bank/Architect. (S.S. Finish Lock &amp; Handle to be included ) for counter no. 17</u>	R.FT.	43.00		
8.0	<b>Officer/Clerk counter</b> Providing & fixing officers counter of 2'-5" height, 4'-6" TO 5' length and 2'-6 " OR 2'-0" width , Counter to be made up of 18mm. thk. Plywood framework and open space for C.P.U. & small drawer above it on other side of Key Board drawer. The counter should have necessary holes of required sizes for wire managers. The counter should have necessary passages & ledges for data cables, electrical cables and telephone lines. The counter should be finished with 1.0mm. Thk. Laminate of approved color & shade from external side and polish from inside. All the exposed edges of plywood including lower edges should have lipping patti. Lipping patti should be finished in polish. The cost should include necessary hardware Moulding .handles & Godrej make drawer locks with common key for cash drawers, footrest etc. complete as per design. for running tables rate includes with glass seperater /partition of 12mm thk floated glass with fixing with studs and other hardware to be made as per the instruction given by the architect.	Rft	110.00		
9.0	<b>AGM TABLE (8'-0"x3'-0"):</b> Fabricating manger's Table made out of 18mm BWR Grade ply, having table top 2'-6" height from the ground level & 3'-0" clear top width. it will have a side table of size 1'-6" x 3'-0" Table shall be provided with a sliding keyboard tray 2'-3" wide with slider, 2nos drawers on either sides and cupboard below the drawer locking arrangements, aluminum handles, brass hinges etc all exposed surface shall be laminated with 1.0 mm thk rubber wood laminate. 12mm thk plain glass on table top as per shape with cutting for wire manager. The internal surfaces shall be painted with two coats of enamel paint over a coat of primer. Provision for c.p.u stand 1'-0" x 2'-0" & foot rest of size 75mm x 38mm shall be at bottom .wire manger shall be provided to the counter all exposed edges of the block board shall be provided with teak wood beading and polishing etc, complete. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing.	no	1.00		
10.0	<b>CONFERENCE TABLE</b> CONFERENCE TABLE (Size :- 22'-0" x 7'-0") ht. 2'-6" To be made up of 18mm commercial plywood by making top and bottum with required support on the surface to be laminate/veneer and 6MM Corean top to be fixed on the table .table to be made of design and instruction given by the Architect.	NO's	1.00		
10A	<b>DINING PLATFORM</b> Providing & Fixing Dining Platform 2'-0" wide made with 18mm ply finished with 1mm thick laminate on all surfaces including verticals. The platform should be supported on 18mm tk ply verticals placed at 2'0" intervals. All the edges of the plywood are covered with 12mm tk. steam beech beeding duly painted.	R.FT.	31.50		

11.0	<b>Side Units</b>				
	Providing & fixing side unit made up of 18mm. thk. plywood framework & 6mm. thk. plywood as backing. Side unit should have 2 no. of drawers above & shutters below. Drawers should be made up of 18 thk. Plywood fascia, 12 thk. Plywood sides & 6 thk. Plywood bottom. Drawers should be mounted on heavy duty drawer sliders. Side unit should be finished with 1.0 mm. thk. Laminate of approved shade & colour on external surface & oil paint to non laminated surface. All exposed edges of 18 thk. & 12 thk. Plywood should have lipping patti All lipping patti's should be finished with paint/french polish on it. The cost should include necessary hardware, handles, Godrej make locks with common handles, Godrej make locks with common key for set of drawers etc. complete as per design. Drawers to be made of 12 mm thick comm. plywood and finished with laminate on front and enamel painted inside	Sft	113.00		
12.0	<b>Storage Units</b>				
A	Providing & fixing storage units made up 18 mm. thk. plywood framework, 6 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design. LOW HEIGHT STORAGE	Sft	158.00		
B	Providing & fixing storage units made up 18 mm. thk. plywood framework, 6 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design. FULL HEIGHT STORAGE .	Sft	778.00		
13.0	<b>Main Entrance Door with Partition</b>				
	Providing & fixing main door & partition made up of 12 mm thk. Clear toughened glass shall be fixed in.Ozon / Enox make patch fitting with necessary hardware.With application of sealant from all sides. Edge polish for all exposed sides of glass. Complete as per design Door size 7'0" x 3'0" - Providing & fixing main door made up of 12 mm thk. Clear toughen glass shall be fixed in.Ozon / Enox make patch fitting with necessary hardware like floor spring, 12" S.S. finished decorative handle pair,& locking arrangement. Edge polish for all exposed sides of glass. Complete as per design and rate includes with all the mechanism and floor spring fixing Entrance	Sft	110.00		
13a	Supply and Fixing Of glass shelves come with flat polished edges with 3/8 inch or 10mm thick glass. With smooth surface and tough strength with displaying Front Glass . should be Durable enough to lift the weight of Memento and Glass shelf holders to be rust-proof and durable, The qualities to be more reliable and long-lasting , maximum weight capacity is 50 lbs.and Design given by the Architect.	Sft	100.00		
14.0	<b>PILLER /WALL PANELLING</b>				
	Fabricating and fixing wall/column paneling to consist of 37.5mm x 50mm treated kail/chir hardwood framework at spacing not exceeding 600mm bothways (horizontal and vertical). Paneling framework to be secured to wall surface/column surface.Paneling framework to be clad on one side with 8mm thick commercial ply finished with 1.0mm thk laminate including skirting of 100mm high & 12mm x 12mm groove at skirting level. Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI.(THIS ITEM IS AS PER SITE CONDITION AND AS PER THE REQUIRMENT )	Sft	1,960.00		
15.0	<b>SHUTTER BOXING</b>				
	OUT OF SHUTTER BOX Overhead outside shutter box: p/f sal/maranti wood frame fixing of 12mm plywood with 1mm thk. Laminate finish and openable shutter for out side area	Sft	125.00		
15.a	<b>WOODEN PODIUM</b>				
	Supply and Fixing of Wooden Movable podium with Size (Feet): 121 X 50 X 45 Cms provision for mic to be provided and it should be made up of standard plywood with surface approved make laminate and Design given by The Architect.	Nos	1.00		
	<b>SOLID DOORS:</b>				
16.0	Solid Doors : providing and fixing of solid door and Door Frame should of best quality non-teak wood of 4.5"x2.5" section without Glass. Instead of glass, matching laminate on plywood to be used for maintaining uniform appearance. Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI. rate includes with laminate panal, nails adhesive , hardware ,labour ,transportation,lifting, etc for pantry ,ups,passage and other rooms	Nos	16.00		
17.0	<b>VERTICAL BLINDS:-</b> Providing and fixing vertical blinds of 100mm lenth of vista Lavour of approved shade and pattern. The rate shall include necessary scoch gurd treatment on both sides. The overlapping should be uniform and adequate.Necessary oparative arrangements,frames to be provided. The work to be completed as per specification and approval of the architect.MAKE(vista) at banking hall and cabins windows.	Sft	551.00		

18.0	<b>SOFT BOARD:-</b> Providing and fixing soft board with necessary framework with 12mm plywood on top 12 jolly board to be fixed finished with fabric @Rs120 , with necessary mouldings duly polished along the periferi.	Sft	80.00		
19.0	<b>TEXTURED PAINT:-</b> Providing , spraying and applying Texture paint as per approved shade as per approval of the architect. Bi colour texture paint will be used. On POP finish wall to give a smooth surface as per approval of the Architect.( optional for pillar)	SFT	80.00		
20.0	<b>WALL DISPLAY BEHIND VISITOR AREA</b>				
	Structure made by 18mm plywood and gypsum board 6" depth boxing ,finish with1mm thk. laminate, splot light,flower vase, abstrac paintings as per drawings.	SFT	30.00		
21.0	<b>BACK DROP BEHIND RECEPTION AREA</b>				
	Structure made by 19mm plywood and gypsum board finish with laminate/veneer, and 10mm frosted glass panelling with splot light,flower vase, abstrac paintings as per drawings.	SFT	60.00		
22.0	<b>CONSOLE FOR BOARD ROOM</b>				
	Providing and fixing console with 12mm ply with 1mm thk. Laminate finish, and back portion texture paint finish with glass shelves four nos both side as shown in the architect drawing. The depth of console is 12" including lighting arrangement for display. Center portion of the console will be 6" thk. lacquerd glass fixed with S.S Stud for projector, lacquerd glass will be 3" away from wall.Design and detail of the console shall be as per Architects design,	No's	1.00		
23.0	<b>WHITE BOARD</b>				
	P/F in position magnetic white board (make Alkor, Whitemark) to walls complete as per detailed drawings.	SFT	140.00		
24.0	Providing & fixing 6 mm thk Lacquerd glass for projector fixed with S.S stud.	SFT	160.00		
25.0	<b>PEST ANTI TERMITE</b>				
	Providing Pest control and Anti-termite treatment by appointing specialized agency as per specifications mentioned by Bureau of Indian Standards and agencies specifications whichever is higher for General Civil, Plumbing,/ Drainage and timber/ Carpentry works. Complete as directed. ( Mode of measurement shall be carpet area of floor and not area of surface treated.)	SFT	4,638.00		
26.0	<b>TOILETS, UPS &amp; RECORDS, etc., (INCLU. CEILING) PAINT</b>				
	Cleaning the old surface of the wall and then applying & painting walls with OBD White paint matt finish with two coats of approved make shade and colour over a base coat of appropriate paint of approved make (total 3 coats) including cost and conveyance of materials like paint to site including lift and labour charges such as preparing the wall,applying luppum,applying primary coat, curing for primary coat, applying paint with matt finish two coats etc., complete for the finished item of work.	SFT	450.00		
27.0	<b>SYNTHETIC ENAMEL PAINT FOR WINDOW GRILL, ROLLING SHUTTER &amp; COLLAPSEABLE GATE</b>				
	Providing and applying 2 coats synthetic enamel paint on window grill,rolling shutter and collapsible gate.Before putting final paint scrapping, leveling, preparing the surface and 2 coats primer to be done.The wall to be completed as per the direction of architect.	SFT	781.00		
28.0	<b>cnc cut jall:-</b>				
	Providing and fabricating MDF Sheet jalli cut with CNC CANARA BANK LOGO with Paint Finishas per approved	SFT	40.00		
	<b>TOTAL AMOUNT</b>				
	<b>DISCOUNT IF ANY</b>				
	<b>GRAND TOTAL</b>				