

BOQ FOR FURNISHING WORKS FOR CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA						
A	FURNISHING WORKS					
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount	
1	FALSE CEILING (Including ATM Ceiling)					
a.	Providing and fixing GYPSUM BOARD FALSE CEILING in levels as per the detailed drawing - made up of G.I frames as specified by Gypsum India/Saint -Gobain Gyproc and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel of size 20X27X30 mm and 0.55 mm thick for light fittings, AC Grills, diffusers, suspenders etc. shall be standard sections supplied by Gypsum India/ Saint Gobain. Spacing of intermediate channels shall be at 1200 mm c/c and ceiling section at 457 mm c/c. The work includes taping and jointing, applying primer, two or more coats of plastic emulsion paint of approved shade ICI/ ASHIAN PAINTS make, making cut-out for light fixtures /fittings, etc. The Final coat shall be done with FOAM ROLLER and no brush marks should be visible. Providing of perimeter channels / beading etc. as per drawing complete in all respects.(All measurement in sqft only and finished surface area shall be measured)	4820	sqft			
b.	GRID FALSE CEILING(24" x 24") 24"x24" Grid False Ceiling Providing and fixing in the true horizontal level false ceiling system of Armstrong world industries. The suspension system shall be the Armstrong Trulock Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color black or white revealed Silhouette main runners and cross tees to have mitered ends with birds mouth notches to provide mitered cruciform junctions. Main runners to be spaced at 12mm c/c fixed by using 2mm pre straightened GI Wire.Main tee, rotary stitched of size 15mm x44mmx3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mmx44mm x1200mm at every 600 mm c/c maximum and 600 mm c/c cross tee of size 15 mm x 44 mm x 600 mm at every 1200mm c/c maximum and 19mmx19mmx3000 wall angle. All as per the design and instructions Architects (make- Armstrong & thickness of tile- 16 mm)	1390	sqft			
c.	Providing & Fixing of Ceiling tiles shall be of high acoustic performance of Decosonic CNBM make and micro edge glass fiber in size 600x600x15 mm of color white/Black. It comprises a high-density glass wool panel covered with painted glass wool tissue for decorative ceiling effect and glass wool tissue on the backside and having sealed edges. It shall have a noise reduction co-efficient of greater than 0.90, light reflection of over 85%, density of 100kg/m ³ , humidity resistance. To lay the field panel of size 600x1200mm, flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre. Thus a grid system of 600mm X 1200mm is formed. Installation shall not begin until all wet work is completed and dry. Building shall be properly enclosed and under standard occupancy conditions (temperature of 20-40°C and not more than 70% relative humidity) before installation begins (make- Armstrong & thickness of tile- 16 mm)	20	sqft			
2	PARTITIONS WITH WOODEN PRESERVATIVE					
a	Low height Partition Providing & fixing of LOW HEIGHT PARTITION (HT. 4'-6") made of 2"x2" aluminium tubular section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of approved make on both faces finished with 1mm thick laminate of approved shade. Till the height of 3'-3" and 1'-3"(10mm thk.) toughened glass on (side & front) top complete with teak beading, The PU polishing teak sections of approved shade as per drawing and fixing of soft board covering with similar fabric. Complete in all respects to the complete satisfaction of the Architect.	1630	sqft			
b	Full height Partition (Both Side Laminate) Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" aluminium tubular section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of approved make on both faces finished with 1mm thick laminate of approved Make and shade. minimum 8 mm thick toughened glass of approved make with etching/taping as required) on the glazed portion. The work includes PU polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. Including doors but excluding cost of door closers, mortise locks.	1100	sqft			
f	Providing & Fixing 50mm Glasswool in between the solid partition complete as directed by the Engineer-in Charge	1480	sqft			
h	SEMI GLAZED PARTITION Providing & fixing of partly glazed (12mm toughened glass of approved make as per design), made of 2"x2" aluminium tubular section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of Approved Make on both faces finished with 1mm thick laminate of approved make & shade The work includes providing PU polishing of shade on woodwork and steam beach beading etc. Including doors but excluding cost of door closers mortise locks. Complete in all respects to the complete satisfaction of the Architect /Engineer	665	sqft			
i	Single skin partition above ceiling Providing and fixing single skin partition above false ceiling(where false ceiling is provided only on one side) for a height of up to 600mm or near about soffit of roof using aluminium frame as specified above along with 9mm thick ply board wood lined on only one side and lining with 1mm thk laminate of approved shade and amke along with grooves.	390	sqft			

BOQ FOR FURNISHING WORKS FOR CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

A	FURNISHING WORKS				
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount
j	<p>SOLID PARTITION (FULL HEIGHT)- CEMENT FIBRE BOARD FOR UPS ROOM AND ELECTRIC PANEL</p> <p>Providing and fixing solid partition using framing as per details mentioned above, The inner side of the partition shall be made out of 10mm thick cement fiber board and finished with required putty to make it even surface finished with 2 coats of ivory white enamel paint on the internal side (not visible from the customer lobby). Other side the partition towards customer having 12mm thk Ply shall be finished with 1mm thick laminate of approved shade and scheme on the customer side (visible to customers) .The rate quoted must be inclusive of the providing one panel door for UPS room (Size - 7'-0" x 2'-9") & 2 panes door (Size-7'-0" x 2'-0" for electrical panel) or door sizes as per site requirements in combination of 10mm thk cement fibre board and 19mm thick approved block board pasted / screwed together to form a single entity and finished as per matching scheme. The block board shall be on the outer side and shall be pasted with 1.0 mm thick laminate along with matching skirting & top bands as per bank's scheme and the cement fiber side of the door shall be on the inside with 2 coats ivory white enamel paint over a coat of primer. Exposed edge of door thickness shall be finished with Steam beechwood lipping & melamine/PU polish.</p> <p>Item shall include installing / affixing 12" X 6" aluminium louvers at the horizontal centre of the door panes at suitable height along with all other necessary hardwares & fittings such as 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, mortice lock / brass tower bolt, SS Handles on both sides, magnetic ball catchers etc of approved makes.</p> <p>Note - For the purpose of contractor's payment in case of Electrical panel cabinet, only front elevation area shall be measured. BUT the partition shall be erected till soffit of the actual ceiling along with the board concealing the entire area and not just till the false ceiling.</p>	255	sqft		
I	Providing and fixing of following items/ accessories completeed in all including				
i	Mortise locks with handles.(Make Godrej)	12.00	no.		
ii	Hydraulic Door closer.(Make Godrej/ Universal)	12.00	no.		
ii	Floor springs.for Glass door.(Make Godrej/ Universal)	9.00	no.		
3	GLASS DOORS				
A	Providing and fixing of (3'-0"/ 3'-6" X8'-0")12mm toughened glass door with18" long SS handles, floor spring (Ozone-FS- 9400) etc, locking arrangement of brass make at top of standard make(patch fitting), including fixing of Frosted strip vision film & bank logo as directed by the Bank/ Architects.	255	sqft		
B	FIXED GLAZING Providing and fixing external FIXED GLAZING comprising of 12 mm thick toughened glass of approved Make with top, bottom and vertical U Channel frames comprising of powder coated (shade as approved) 16 gauge Aluminium members of approved shade 1.5mm avg. thick top, bottom & vertical member with clip sections as per specifications and drawings to complete satisfaction of the Architect.	330	sqft		
C	BLOCK DOORS Providing and fixing solid core 38 mm solid core flush door finished with lippings in all side with necessary door hinges , cylindrical locks(golden, Godrej) , door clouser, door stoppers, etc with a frame work of T.W./Beech wood size 75mm x 62.5mm with necessary hold fast fixed to the wall/partition. 1 mm laminate to be fixed on both sides duly finished,edges to be finished with wooden lippings.A wooden moulding size 1.5"x2/8" to be provided all along the periferi of the frame work in the both sides . All the wooden area to be duly polished as per specification of the Architect. In case of Partly glazed door 8 mm thk etched toughened glass with granular blasting/sand blasting as per design of the Architect to be fixed with necessary mouldings.	25	sqft		
4	COUNTERS AND TABLES				
a	Providing and fixing Tables with 10mm beveled toughened glass of approved make to be fitted on top obtain the total height of 2'-6" as per detailed drawing, made up of 19mm board of approved Make and finished with 1 mm thick laminate of approved make, and shade. Table(with one side drawer unit and another side drawer unit) shall be provided with drawers sliding on telescopic channels and one cabinet with proper locking arrangements and keyboard with telescopic channels . The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, PU polishing of steam beach/ white cedar beading etc. and The inner exposed surfaces to be finished with 0.8 mm thk laminate of approved shade. complete in all respects to the entire satisfaction of the Architect/Bank.				
i	DGM Table size: 8'-0"x 3'-0 x 2'-6"	1.00	nos.		
ii	AGM Table size: 6'-6"x 3'-0 x 2'-6"	2.00	nos.		
iii	Officer Table Size: 5'-0" x 2'-6" x 2'-6"	35.00	nos.		
iv	Staff Counters (Width of working top: 2'6"; Height: 2'6")	45.00	Rft		

BOQ FOR FURNISHING WORKS FOR CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA						
A	FURNISHING WORKS					
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount	
b	<p>CONFERENCE TABLE</p> <p>Providing and erecting in position CONFERENCE TABLE of approx size 65'-0" X 3'-0" U-Shape shaped as per layout to be made out of 19mm thk Commercial ply top with 60 X 60mm thk t.w.moulding all round the top to be finished with approved 4.0 mm thk veneer with approved polycoat polish, and to be erected on a framing of t.w 75 X 75 mm thk moulded frame including bracings at a regular interval of 900 mm centres finished with ply on both sides & 4.0mm thk veneer (Basic Price Rs 150/- per Sqft) with melamine polish. The exposed middle verticals (aprons) shall be finished with approved 4.0 mm thk natural veneer with melamine polish. The table shall have 3 nos of cut outs for placing planters with internal surfaces to be finished with the same 4.0mm thk veneer with polycoat polish.</p> <p>The rate shall include the cost of planters & white pebbles filling the cut out area including 12mm thk toughened glass for the cut out area supported on t.w moulding with melamine polish on sides etc complete. The rate shall be inclusive of necessary cut outs & provisions for video/tele conferencing, wire managers, necessary hardware, cable cubby, cabling arrangements for video / tele conferencing, Poppup box and openings for speakers etc complete in all respects to the complete satisfaction of the Architect</p>	1.00	no.			
c	<p>VC TABLE</p> <p>Providing and erecting in position VC TABLE of approx size 10'-0" X 4'-0" oval shaped (10 seater) as per layout to be made out of 19mm thk Commercial ply top with 60 X 60mm thk t.w.moulding all round the top to be finished with approved 4.0 mm thk veneer with approved polycoat polish, and to be erected on a framing of t.w 75 X 75 mm thk moulded frame including bracings at a regular interval of 900 mm centres finished with ply on both sides & 4.0mm thk veneer (Basic Price Rs 150/- per Sqft) with melamine polish. The exposed middle verticals (aprons) shall be finished with approved 4.0 mm thk natural veneer with melamine polish. The table shall have 3 nos of cut outs for placing planters with internal surfaces to be finished with the same 4.0mm thk veneer with polycoat polish.</p> <p>The rate shall include the cost of planters & white pebbles filling the cut out area including 12mm thk toughened glass for the cut out area supported on t.w moulding with melamine polish on sides etc complete. The rate shall be inclusive of necessary cut outs & provisions for video/tele conferencing, wire managers, necessary hardware, cable cubby, cabling arrangements for video / tele conferencing, Poppup box and openings for speakers etc complete in all respects to the complete satisfaction of the Architect</p>	1.00	no.			
f	<p>RECEPTION TABLE WITH BACK UNIT</p> <p>Table top: Table top of 2'-6" wide to be formed out of 19mm thick commercial ply clad with 6mm thick approved Corian, complete as per detail dwg. & Architect's instruction (size- 8'-6" x 2'-6" x 3'-6")</p>	1.00	no.			
	Modesty panel: Modesty shall be formed out of 19mm thick commercial ply boxing finished in 6mm thk approved Veneer with PU polish Finish from outside and all inner surface should be finished with 0.8 mm tk laminate from inside. Provision for Cove lighting to be done as per dwg Complete as per detail dwg. & Architects instruction. Cost to include providing & fixing 6mm thk SS inlays as shown in the drawing.					
	Back Unit : Providing and fixing of 9'-0" X 1'-6" X 2'-6" ht. made out of 19mm thk Commercial Ply finished with 4mm thk approved veneer . Drawer unit to have 2 drawers and 1 shutter made out of 19mm thk commercial ply finished with approved 1mm thk laminate , mounted on approved drawer channel, central locking, approved handle. Complete as per the detailed dwg and instructions of the Architect.					
g	SIDE CREDENZAS					
	Providing and fixing SIDE CREDENZAS size 3'-0" to 4'-0" x 1'-3" x 2'-6" made of 19mm board of approved make finished with 1 mm thick laminate of approved Make and shade on top, back, sides and front having two drawers and cabinet below complete with all accessories like locks, handles, magnetic catcher etc. Teak wood beading on all exposed edges with PU polish. (Should not be attached with partitions)	315	sqft			
5	MISCELLANEOUS FURNITURE					
	Providing & fixing STORAGE CABINETS independent units (movable) 12 feet long (maximum) 4'-6" ht and 1'-6" deep as per layout plan made up of 19mm board/ply of approved make and finished with 1mm thick laminate of approved make, shade and as per detailed drawing. one shelves made up of 19mm thick board, each drawer(with lock) & cabinet(with lock) 19mm thickness portion every place must be finished with proper liping/ margin teak wood finish. In side and back shall be finished with 0.8mm thick laminate of approved Make and color The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak liping etc as specified. complete in all respects.					
a	Full height STORAGE CABINATES upto 8'-6" false ceiling high specification as per (a)	180	Sqft			
b	Half height STORAGE CABINATES upto 4'-0"/ 2'-6" high specification as per (a)	650	Sqft			
d	<p>COLUMN / WALL PANNELING</p> <p>Providing and fixing of COLUMN PANNELING as per design, consisting of 10 mm thick MDF BOARD of approved Make fixed on wall with made of 2"x2" aluminium tubular section framework (16 gauge) 2'0" c/c both ways. The above shall be laminated with 1mm thick mica of approved Make, The work includes PU polishing of wood beading, complete in all respects as per detailed drawings to the complete satisfaction of the Architect.</p>	3300	sqft			
e	Providing & fixing in position wall panelling as design (Location : GM Cabin & DGM Cabin) consisting of 9 mm plywood of approved make finished with 4 mm thick Veneer of approved make and shade with aluminium hat furring channel 22-25 @ 500 mm. both direction. The item is to be completed in all respects as per design & approval of the architect.	0	sqft			
6	NOTICE BOARD					

BOQ FOR FURNISHING WORKS FOR CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA						
A	FURNISHING WORKS					
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount	
	Providing and fixing soft board with glass White board necessary framework and 12mm bwp plywood on top 12MM jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly polished along the periferi.The work to be completed as per approval and satisfaction of the Architect.	60.00	Sft			
7	CENTER TABLES (3'-0" X 2'-0" X 1'-6"HT) Providing and making center tables of above mentioned size as per drg. Table top shall consist of 12 mm. Thk.float glass with chamfered edge with approved quality etching. The base shall be made up of CP Teak wood frame as directed by the Architect. All exposed faces finished with natural PU polish (if wood frmes are used) or with 1.0mm Thk laminate for ply. All inner surfaces will be finished with natural french polish.	4.00	no.			
8	ROLLER BLINDS Supplying & Fixing of Seclusion Blockout fabric made up of 100% Polyester with Acrylic coated of 0.32mm(PVC free) of thickness 0.50mm ±5% and wieghing 270-295gsm with openness factor of 0% .Shrinkage % Warp5-6. GREENGUARD certified fabric.The Roller blind system consists of 38mm OD extruded out of Aluminium alloy 6063 T6 with silver anodized to provide an everlasting finish and luster, the rotary unit shall be 36mm in OD incorporating a clutch mechanism composed of low – flexing braided polyster cord with nylon core, Control Ball chain shall be composed of braided nylon cord (2mm dia) with high engineering grade plastic beads of 4.5mm diameter mounted co-axially on the cord with a pitch of 6.2mm (C-T-C) Bottom rail should be powder coated Aluminium flat bottom rail of 290 gm to finish it from the ends it should have rail end caps. The clutch will be at the tube. The return end cap bracket shall incorporate snap spring design to facilitate easy installation and removal for maintenance activities. The bracket shall be finished with a flush mounting cover on each side providing an aesthetic finish. It should handle up to 5 Kgs of material. The clutch should mount flush to the face of the bracket which minimize the light gap between the shade and the window frame. Material & Color shade will be as per sample approved by Architect. (Make- Graber/ walltact/ hunter Douglas)	480.00	Sft			
9	Providing and fixing at Wooden work for ceiling made by 6 mm thk marine grade ply (IS-710) to be finished in 4.0 mm thk. polished veneer of approved shade, fixed to suspended Gypsteel chanel of appoprete size to hold the ceiling ply. The item is to be completed in all respects as per design & approval of the architect. The rate to be included for making necessary cut outs for light fittings, ac unit or other equipments	350.00	Sft			
10	Providing and fixing of wall paper of approve shade and pattarten of Marshall /Excell/ WK make to wall/partition as per instruction with adhesive including all labour and material. This is to be pasted over POP / Putty surface with primer finish (cost of primer to be included in the rate). The item is to be completed in all respects as per design & approval of the architect. (basic cost of wall paper : Rs. 50.00/ s.ft.) (Location : DGM rm & Conference rm)	100.00	Sft			
11	MDF JALI: Providing, fabricating & fixing of Jali work Partition made of 25 mm MDF finished in Mettalic Duco paint to be fixed to the floor and ceiling, complete as per the detailed dwg or the instructions. Cost also to include Design and Lazer Cutting on theMDF , and MS supports above False ceiling up to true ceiling . Mode of measurement : Length & height upto Height of the Jali Work Partition shall be measured for payment. Providing and fixing 50x50mm thick teak wood in frame @ 600mm c/c horizontally and vertically for paneling frame work with coat of anti-termite treatment including hardware and adhesive as required complete as directed. Complete as per the detailed design dwg and instructions.	75.00	Sft			
12	Frosted Film- Providing & pasting frosted film (3M, Garware make) on glass work partition and glass door as required as directed by the consultant/Architect.	585.00	Sft			
13	i Logo- Providing & pasting frosted film (3M, Garware make) coloured logo on entrance door as directed by the Consultant.	9.00	no.			
	ii S.S logo of Canara Bank in SS plate of 18 inch dia and Poster Frame - one set poster frame consisting 2 sheets of imporetred acrylic of 5 mm thickness front sheet with half inch moulding and edge polished;back sheet with polished edge and Alumunuum stud for fixing the frame on wall,One Pin Board for fixing Notices and other communication made of 24"x18" soft board,with hardwood and aluminium frame covered with satin of appropriate colour.	35.00	no.			
14	Painting of walls with textured paint, double spary coat or eq. of approved shade & colour complete as per manufacturers specs .Finishing walls with textured exterior paint of required shadeNew work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/ 10 sqm- textured paint Finalize by architect only.	75.00	Sft			
15	Providing and fixing designer Wall Paneling with 3D engraving in 18mm thick acrylic solid surface sheet of approved make or as approved by Architect basic white/ coloured. Design & fixing arrangement as per direction of Engineer. The material should be CNC 3D cut to achieve the desired design. The CNC cut Acrylic solid surface sheet to be fixed in a box frame or on a frame or on a flat surface as per the drawing and design and as per the instructions of the Architect. The material used shall be very translucent and the light shall pass through the acrylic solid surface enhancing the design and the lights passing should be very visible. The cost shall include the framing and Boxing of wood / plywood and the frame should be of stainless steel or wood as per requirement of stability and weight carrying capacity and its requirement for support. The 3D shall be done as per the requirement of light translucency and reflection of lights required as per the design and instructions of Architect. The backlit ceiling shall have the light passing and shall have translucency. Acrylic solid surface shall have Antibacterial certificate and TUV (Austria) FR grade certified. All design and drawings will be finalized by architect complete all the work as per satisfaction only.	50.00	Sft			

BOQ FOR FURNISHING WORKS FOR CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA							
A	FURNISHING WORKS						
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount		
16	"Providing 15mm thick Mikasa Make Engineered Wooden Flooring with plank width of 185mm / 135mm and length of 1800mm / 2100mm and top layer up to 3mm Oak natural Veneer. Surface of Top layer is pre finished with several layer of UV hardened Acrylic lacquer. Strictly Free from Formaldehyde and solvents. Flooring plank shall be interlocked using Plank Loc locking system in a glue less floating manner. Engineered wood planks shall be a composition of 3 layer of Pine wood with direction of each layer oriented at right angle to the adjacent layer of natural strain in Lacquer and Non Beveled /Beveled in length and width as specified by the manufacturer-in-charge. Product should be MAKE IN INDIA, to maintain a consistent and long term supply of all required quantities. Manufacturing Plant / Product should have FSC certificate and adhere to stringent emission standards. Design and shades are finalized by Architect.	0	Sft				
	Solid Wood Skirting of Matching shade to Engineered wood floor color						
	Installation of Engineered wood flooring in Linear Pattern						
17	Providing and fixing 4.5" wide seamless panel on the existing wooden surface i/c cutting the same and fixing with the help of suitable adhesive / nailing etc in approved design and pattern etc complete as reqd.	220.00	Sft				
18	Providing and fixing of wooden rafter of approx size 7"x2" made out of wooden member and duly clad with 1 mm thick laminate i/c fixing the same on the existing ceiling / floor etc complete as reqd.	260.00	Rft				
19	Providing and fixing of indoor artificial plant to create decorative vertical garden in the existing surface byfixing of base frame and artificial plants in the approved pattern and design etc complete as reqd	75.00	Sft				
20	Supplying and fixing of 6' x 6'x 3' deep conical shaped inverted dome like structure , fabricated out of double layers of 9mm ply / 12 mm MDF duly fixed on the ceiling with the help of frame work made out of aluminium frame and G.I.section and duly laminated from inside in step formation with 12 mm wide grooves & finishing the same by filling of grooves in matching colours of paint / polish etc complete as reqd.	0.00	Sft				
21	Providing and fixing 18 mm thick, 150 mm wide pelmet of flat pressed 3 layer or graded wood particle board medium density grade I, IS : 3087 marked, including top cover of 6 mm commercial ply wood conforming to IS: 303 BWR grade, nickel plated M.S. pipe 20 mm dia (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. flat 10 cm long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all complete. PELMETS with Laminate Finish	100.00	Rft				
22	PANELLING ON WALL IN LACQUERED GLASS-Providing and Fixing of wooden Panelling of wall on hall and column made of 2 MM thick Aluminium tube frame The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminium angles and fastened with steel screws. Frame size 25 x 50 MM with 9 MM thick BWR Ply with 6mm thk colour lacquered glass in approved colour, design, shape and size, including Anti Termite Treatment. Complete in all respect and satisfaction of Architect/Engg.	50.00	Sft				
23	PANELLING ON WALL/PARTITION IN ACOUSTICAL PANELS-Providing & fixing Acoustical Panelling channelled Wood works spaced at perforated panels of width 128mm, thickness of 16mm and length 2440mm or as required on site & approved by EIC, made of a high density particle board substrate with a laminated facing as per the approved shade/species & finish and melamine balancing layer on the reverse side. The boards shall have a special perforation pattern where the visible surface has a ("Helmholtz" fluted perforation of 2mm width and 14mm of visible panel/4mm width and 28mm visible panel) each. The panels shall provide a minimum sag resistance of RH90 and a fire rating class of 1 as per Part 7 of BS 476. The edges of the panels shall be "tongue-and-grooved" to receive special clips for installation. The back of the perforated panel shall have sound absorbing non-woven acoustical fleece. The panels shall be mounted on special aluminium spines using clips provided by Armstrong or equivalent and approved.	50.00	Sft				
24	Providing & Fixing Panelling as same as above, having top layer as duco paint of approved make, quality & shade as per the architects direction on wooden or metal surfaces. The rate shall include scrapping, levelling & preparing the surface, primer coat, chock putty, all surface development as per satisfaction of Architect.	250.00	Sft				
25	WOODEN FLOORING - Providing and fixing of 8-9mm thick Laminated wooden flooring with a surface abrasion resistance of class AC4, with 0.2mm thick wear layer on top of a High Density Fibre substrate core of plank having uniline locking arrangement with an made of Armstrong natural colour foam, with accessories like Skirting, end profile, door profile, transition profile, reducer etc. Complete. Make ARMSTRONG/ AMBIENCE PLUS/ PERGO/vista. Length and breadth of superficial areas of the finished work shall be measured for payment. Make - Carbolink, / Apex / Junkers / Parquet.	0.00	Sft				
26	Providing and fixing of nylon carpet tiles of tufted textured loop in required design, colour, shades and made with 100% nylon BCF solution dyed, total pile height 6.5 mm +/- 0.3 mm, pile weight 700 gms/m2 +/-5%, gauge 1/10"/1/8" ,backing with PVC Glass lined and size of tile 60.9x60.9 cm. fixing of tile with synthesis adhesive as per manufacturer guidelines etc. complete all as per the direction of Engineer-in-charge.	235.00	Sft				

BOQ FOR FURNISHING WORKS FOR CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA							
A	FURNISHING WORKS						
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount		
27	SUN FILMS - Supplying and fixing Suncontrol window film for glazing in different locations and at different heights, to be fixed as per any of the approved type including removing old faded sun film by scrapping and thoroughly cleaning the glass surface with the help of suitable cleaning solution etc. and providing and installing of Sun Control film from inside, Complete job. Rates quoted shall be all inclusive for complete work. Nothing extra will be paid for scaffolding, breakage during execution of the work or for any other item necessary to complete the work satisfactorily. Measurement will be for the finished surface excluding Aluminium frames. Make - 3M / Avery.	580.00	Sft				
28	SOFA SETS - (FABRIC COST B.R. Rs. 300/MTS. TEAL GREEN COLOUR SAMPLE TO BE GOT APPROVED)						
	i SINGLE SEATER	0.0	Nos.				
	ii DOUBLE SEATER	0.0	Nos.				
	iii THREE SEATER	0.0	Nos.				
	Providing and fixing sofa set to detail as shown in drawing about 60cm wide and about 68cm high comprising second class SAL WOOD framework using 50 x 40 with 8mm thick com plywood covering on all sides. Seats finished with spring hooked to MS plate 25mm width fixed to the seat frame. Both seat frame and back covered with layer of jute cloth and 75mm latex rubber (2 layer for seat alone) finished with 12mm foam lining and upholstered to shape with fabric (basic price Rs.300/m) for the rear of the back also and the under surface of the seat finished with Gada cloth 8mm ply below seat. Note: (For sofas materials like foam, latex rubber, gada cloth, spring ,fabric etc., to be approved by the Architects / Bank).						
29	GLASS SHELVES	50.0	Rft.				
	Providing and fixing glass panes / shelves of required sizes with all edges neatly grinded, polished and fixed to the wall surfaces using SS D-brackets. The glass shall be 10mm thk plain glass of approved make. Item shall include all required arrangement / hardwares/ accessories to complete the job upto the satisfaction of bank / Architect. Note - For the purpose of contractor's payment, running length of shelf shall be measured.						
30	ACP WALL PANNELLING (For outside front walls, outer pillars of ATM & ATM internal walls)	0.0	Sft				
	Providing & fixing in position ACP (Aluminium Composite Panel) wall panelling having minimum ACP thickness of 3mm and minimum foil thickness of 0.25 mm on both sides with Aluminium framing tube sections of min 1.5" X 1" (20 gauge or down) @ 2'-0" C/C both ways. Panels shall be neatly fixed to the frame with 3M or equivalent adhesive and joints shall be finished with silicon based sealant. ACP shall be of approved make and in Ivory & Canara Bank Blue shade as per bank's approval. Item shall include proving & fixing additional sections as required for fixing Indoor AC units, proper access panel for ATM power point, proper locking arrangement for plug point by providing additional framing etc complete. Note - For the purpose of payment, the measurements shall be taken up to the visible height / false ceiling level only.						
31	BOXING FOR ROLLING SHUTTER	630.0	Sft				
	Providing and fixing rolling shutter panelling / enclosure of required size as per description of ACP panelling above. The rate shall inclusive of necessary hardware fittings like hinges, screws, tower bolts sealant, trap door, locking arrangement etc complete.						
32	DOOR MATS FOR BRANCH ENTRANCE & ATM ENTRANCE GATE	75.0	Sft				
	Supply and laying of outdoor type Waterproof and weather resistant, rubber doormats (<u>preferably Blue Color</u>) in entrance of the Branch Main entrance Gate & ATM entrance gate.						
33	MISC ITEMS						
	a P&F High Quality PVC/Acrylic/Texture Laminate as per design given by Architect.	45.00	Sft				
	b P&F G-Profile as per Architect	55.00	Rft				
	c P&F SS Patti Gold 1.5"	75.00	Rft				
	d P&F T Patti Gold 3/4"	75.00	Rft				
	e P&F SS Patti Gold 3/4"	75.00	Rft				
	f P&F SS Patti Gold 3/4"	75.00	Rft				
	GST extra as applicable	Total					