

**CARPENTRY WORKS FOR INTERIOR FURNISHING WORKS OF PANJABARI
CURRENCY CHEST OF CANARA BANK AT ASSAM**

SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMT
	CARPENTRY IN LAMINATE				
	GENERAL NOTES FOR CARPENTRY WORKS				
	1. All Plwood and Block board to be used in Carpentry works should strictly be of Century/ Green/ Duro ply/ Kitply/ Archid ply only				
	2. All Plywood/ Block Board used to be of commercial grade but of above make only				
	3. All laminates should strictly be 1.0mm thk of Century/Greenlam or Merino make				
A	TABLE , DESKS , DRAWERS AND STORAGEES				
	ALL TABLES / WORK STATIONS SHOULD HAVE KEYBOARD TRAY, CPU TROLLEY(METAL), FOOT REST AND RATES SHOULD BE QUOTED ACCORDINGLY WITHOUT ANY EXTRA CLAIM				
i	BACK OFFICE RUNNING COUNTER WITH PEDESTAL	RFT	52.50		
	Fabricating, erecting and fixing of running counter 3' wide with top with vertical support at every 3'-6' length and supported additionally from the partition/ walls as per design.. The counter should be made up of 25mm thk ply with laminate of 1mm thk on top and wooden beading/ moulding all round melamine polished. The table to include a fixed type pedestal with a set of 3 drawer unit with a central locking arrangement, and keyboard tray for every 4 ft length. The works to include all hardware fittings fixtures etc along with propoer supporting verticals. All exposed edges to have wooden lipping stained to match the rest of the interiors. The iten to include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc., of approved make. All exposed edges to have wooden lipping stained to match the desk and melamine finished.Cost to inlcude Borer/antitermite treatment for wood/plywood. The lock to be of single control type.				
v	Manager's Table of size 6'-0"(L) x 3'-0"(W) x 2'-6"(H) with 8mm thk clear Glass (all edges mirror polished) on Top	NOS	1.00		
	Providing and fixing Manager Table in laminate finish of size 6'-0" X 2'-6" .Providing and making a table of overall size of top as mentioned above. It shall consist of 3/4" thk plywood top as per design(double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES) supported on 3/4" thk plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
vi	Officer's Table 5'-0"(L) x 2'-6"(W) x 2'-6"(H)	NOS	3.00		

	<p>Providing and fixing Officer'sr Table Post formed laminate finish of size 4'-6" X 2'-3" .Providing and making a table of overall size of top as mentioned above. It shall consist of 3/4" thk plywood top as per design, with 1/2" PVC beading in matching shade, supported on 3/4" thk plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement.</p>				
	SECURITY GUARD'S TABLE	NOS	2.00		
	<p>Providing and laying 450 MM wide Plain Table for Security Gurd of overall top size 900mm x 450-500 mm with a Pencil Drawers for over all size of top as mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make.</p>				
vii	Side Cadenza of size 1'-6"(W) x 3'-6"(L) x 2'-6" (H) (FOR MANAGER)	NOS	1.00		
	<p>Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit (C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make</p>				
	Side Cadenza of size 1'-6"(W) x 3'(L) x 2'-6" (H) (FOR OFFICER)	NOS	3.00		
	<p>Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit (C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make</p>				
viii	LOW HT RUNNING STORAGE(1'-6"DX2'-6"HT) (BACK CADENZA)	SFT	68.00		

	<p>Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make . Note- The Height of the running stoarge should be 2'-6" and should comprise of a 6" high drawe and shutters below. No shelves should be provided inside the shutters</p>				
ix	OVER HEAD STORAGE IN PANTRY ONLY	SFT			
	<p>Providng and fixing over-head storages which consists of 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & t.w lipping matching with approved laminate on all the edges. They shall consist of 3/4" thk plywood top , sides and bottom and 1/4" thk marine plywood back. A 3/4" thk ply wood palmet shall be provided below the storage to house the tube light. All the external surfaces shall be finished with 1.0mm thk laminate of approved shade. Divisions of shutter shall be made equally in accordance to the length of the storage. All internal surfaces shall be finished with french polish including the shutter. Rate shall be inclusive of all necessary hardware fittings of approved make like- hinges, locks, towerbolts, handles etc.Note- the pelmet for tubelights will not be considered as seperate item on in the measurement</p>				
x	FULL HT. STORAGE	SFT	212.00		
	<p>Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.comm. ply top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type higes of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages (as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval (approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.</p>				
	1500 MM HIGH AND 300MM DEEP LOCKERS FOR CURRENCY CHEST, FINISHED WITH 1.0mm thk laminate of approved shade	SFT	28.00		

	Providing and laying Locker unit of sizes as mentioned above having 300mm depth, with individual locker size of 300mm x 300mm, and having separate lock and key arrangement. They shall consist of 3/4" thk plywood for top, intermediates, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full oval open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be made equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with melamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
	LOOKING MIRROR ON 4 CORNERS OF PATROLLING CORRIDOR	SFT	44.00		
	Providing and fixing 6mm thk. of approved make clear mirror (First QUALITY) fixed over 12mm thk. Marine ply. fixed on all four corners of Patrolling corridor above 6" high skirting till 5'-6" level from FFL or as directed by the architect/ EIC. It should be fixed to the two sides of the wall with wooden frame of 50mm x 38mm size. The rate shall be inclusive all necessary fixtures and fittings. All exposed surface including skirting, side and top boarders should be finished with approved shade of laminate				
B	PANELLING				
1	PANELLING ON WALLS/ COLUMNS IN LAMINATE FINISH				
	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consist of aluminium sections 50mm x 38mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 18/19mm thk commercial grade plywood and finished with 1.0mm thk laminate or left naked as per the direction of the EIC/architect. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required.				
a	In 12 mm plywood finish in laminate for sealing of window	SFT			
b	In Laminate Finish over Ply	SFT	196		
C	PARTITIONS				
	(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca/ rcc ceiling/slab but the area of partition payable will be below the false ceiling only).				
1	Full Height Solid Partition B/S Laminate	SFT	580.00		
	Providing & fixing in position solid Full Height Partition in frame work in 2'x 2' grid (horizontally and vertically) comprising of 2"x 2" T.W. Section with 8 mm thick plywood on both sides finished with 1 mm thick laminates of approved make and colour as shown in drawing. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
2	FULL HEIGHT PARTLY GLAZED PARTITION	SFT	238		

	Providing and fixing partition framing which shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures.The framing shall be fixed with 8/9 mm thk. commercial grade plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine Polish.				
4	FULLY GLAZED PARTITION WITH TOUGHENED GLASS	SFT	44.00		
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.Rate shall be inclusive of frosted film and bank logo to be fixed over the glass surface as per deign and as directed by the architect				
	ALUMINIUM HEAVY DUTY FRONT GLAZING WITH ANODISED SECTIONS (As per Colour Specified by Bank) :-	SFT	22		
	Providing and fixing fully glazed heavy duty alluminium sections (14 Guage) at the main entrance as shown in the drwng. Glazing shall consist of approved make heavy duty 6" x 2" sections for the top & bottom rails and 2" x 2" sections for the vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the framing. Rate shall include necessary etching film / LOGO, and any necessary hardware items. (Heavy Duty 6" & 2" thick frames(14 Guage) - approved make)				
	<u>SEMI HEIGHT SOLID/ SEMI GLAZED PARTITION FOR CASH CABIN , SINGLE WINDOW COUNTER AND OTHER AREAS</u>	SFT	54.00		
	Providing and fixing in position Semi Height Semi Glazed/ solid Partition at places as indicated in the drawing in Aluminium frame work in 2'x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 1.8mm thk Aluminium Section , fixed with 8/9 mm thk plywood on both sides and then finished with 1.0 mm thick laminate of approved shade and make in approved pattern. Item to include 8/10 mm thick itched glass or clear glass with frosted film of approved pattern. All edges should be fixed with T.W beading and should be finished in melamine polish of matching laminate colour as directed including wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
D	DOORS				
a	SOLID DOORS- IN LAMINATE FINISH (BOTH SIDE LAMINATE)				
	Providing and fixing solid doors of sizes as shown in the drawing.The door shutter shall consist of 3 nos 2" x1" C.P teak wood styles and 3 nos 3" x 1" C.P teak wood bottom, middle and top rails. The wooden framing will be covered with 1/4" thk plywood on both sides. A door frame of size 3"x1 1/2" t.w section finished with mellamine polish shall be provided. Rates shall be inclusive of approved locking system(Godrejmake- Ultra mortise dead lock), door stopper, a pair of handles, tower bolts etc and misc. hardware items of approved make				
i	2'-6'-0"X7'-0"-IN LAMINATE FINISH (WITH 1 1/2X4" WOODEN FRAME)	NOS	6.00		
b	PARTLY GLAZED DOOR				

	Specification same as above except for 8mm thk Modi Guard clear float glass shall be provided at 4'-0" from floor lvl The door shall be finished in 1.0 mm thk laminate on both sides				
I	DOUBLE LEAF PARTLY GLAZED DOOR AT SORTING AREA (4'-0" X 7'-0")	NOS	1.00		
II	DOUBLE LEAF DOOR IN ENTRANCE TO CHEST FRONT CORRIDOR(6'-0" X 7'-0") WITH ALDROBE , TOWER BOLT, AND ALL OTHER HARDWARE FITTINGS ALL COMPLETE	NOS	1.00		
IV	4'-0" high Wicked Door as per design	NOS			
c	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)- AT ENTRANCE & BM'S CABIN	SFT	21.00		
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate grade fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)				
	ENTRANCE DOORS - IN ALLUMINIUM POWDER COATED SECTIONS (HEAVY DUTY-14 GAUGE) , BANKING HALL - FULLY GLAZED (12MM THK GLASS	SFT	35		
	Providing and fixing fully glazed alluminium (heavy duty-14 gauge) doors at the main entrance as shown in the drg. Door shall consist of approved make heavy duty-14 gauge sections 6" x 2" for top & bottom rails, 2" X 2" for vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the framing. Rate shall include necessary etching film / Logo, Pad Lock (GODREJ MAKE), 1 pair of 12" long S. S. Handles (Curved shape , C Shape in Elevation), floor springs (MAKE EVERITE / GOLDEN /HARDWIN /EVEREST MAKE), gaskets & any other necessary hardware items.				
E	FALSE CEILING AND POP WORKS				
1	GYPSUM BOARD CEILING	SFT	500.00		
	Providing and fixing 1/2" thk Gypsum India Board false ceiling at levels as shown in the drg. From the FFL. Rate shall be inclusive of all Gypsum India Components contained G.I perimeter channels of size 0.55 thk having one flange of 20mm and another flange of 30mm and a web of 27mm along the perimeter of the ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centres. The suspending G.I intermediate channels of size 45mm, 0.9mm thk with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angles of width 25mm x 10mm x 0.55mm thk fixed to soffit with G.I cleat and steel expansion fastener at every 610mm c/c. Ceiling sections of 0.55mm thk having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in directions perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gyboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment. The board are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & jointing paper tape. Rate shall be inclusive of any vertical ceiling part, cutouts for spot and tube lights, a.c grills, fire and security system cutouts. All Sections should adhere to the manufacturer's guidelines .				

	Note- Rates shall be inclusive of The drop/band of 6"-12" between the Gypsum-Gypsum (Higher-Lower levels) and Armstrong-Gypsum (Higher-Lower levels). No extra can be claimed for the same. Amount will be paid as per the measurement of the horizontal surfaces of Gypsum and Armstrong and nothing will be paid for vertical surface / band/ drop as it is all inclusive in the Rate				
2	MODULAR FALSE CEILING- ARMSTRONG make	SFT	572.00		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm grid sections) false ceiling of size 24" X24" AT LEVELS AS SHOWN IN THE DRG. FROM THE FFL. Rates shall be inclusive of providing the total system with installation etc. The contractor has to maintain all ceiling tiles in good order and replace the defective tiles (at his own cost) before the handing over of the site.				
	Note- Rates shall be inclusive of The drop/band of 6"-12" between the gypsum(at lower level) and Armstrong(at heigher level). No extra can be claimed for the same. Amount will be paid as per the measurement of the horizontal surfaces of Gypsum and Armstrong and nothing will be paid for vertical surface / band/ drop as it is all inclusive. Rate				
F	PAINTING				
1	LUSTRE PAINT WITH POP PUNNING ON GYPSUM FALSE CEILING	SFT	530.00		
	Providing & applying Luster Paint on walls, columns & ceilings over pop punning. The rate shall include scrapping, levelling & preparing the surface. with pop , jointing compound and Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.				
2	DISTEMPER PAINTS FOR WALLS (TOILETS, STORE, UPS AND STRONG ROOM)	SFT			
	Providing and applying Distemper paint on walls , columns & ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 3 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided.Note- Rates shall also include - filling up the cracks in the wall & ceilings, making good surface .				
G	MISC. ITEMS				
2	PIN UP BOARD	SFT	24.00		
	Providing and fixing Pin-Up board of sizes as mentioned in the drawing in 1/2" thk soft board of good density to be mounted over 12mm thk ply and fixed to partition/ walls or at places as directed by the architect. The soft board shall be covered with valver cloth of approved shade and make (BASIC RATE RS. 200 /R.MTS.) .				
3	SHUTTER BOXING	SFT	96.00		
	Providing and Fixing Shutter Boxing with 19mm thk Marine Ply and Finished with Approved Shade of laminate> The boxing of shutter should be made opennable type for periodic maintainance. Note the mode of measurement would be the multiplication of the length and the height of the boxing				
4	NOTICE BOARD	SFT	24.00		
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
6	WRITING LEDGE	NOS			

	Providing and fixing Wall Mounted Writing Ledge Of Size 4'-0" x 1'-3" x 1"(H), made out of 19mm thk Plywood of approved make and finished with 1mm Thk approved shade of laminate. This ledge should have 4 nos of Pockets made along 4' length with the Supporting wall as base with 3" clear space to house withdraws/deposit etc slips. All inner surfaces of the Ledge should also be laminated. A 12mm thk Clear Glass, Mirror polished on all sides of size 4'-0" x 1'-3" shall be fixed with 4 nos 1-1/2" dia and 4" High S. S Studs should be fixed on the Top portion of the ledge. The Top and sides are to be panelled with CORIAN OF Approved make and shade.Please Refer Drawing for Writing Ledge.				
7	COMPLAIN BOX & SUGGESTION BOX	NOS			
	Supplying and erecting free-standing complain box of overall size 300 mm long x 200 mm deep x 450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete with hardware fittings and fixtures of approved make and quality.Top and all exposed surfaces of block board are to be finished with 1.00 mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.				
8	CHEQUE DROP BOX	NOS			
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.P teak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved designand quality.				
9	10MM GLASS SHELVES- 250-300MM WIDE	RFT	18		
	Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass selves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ pannelling, at an interval of 24-30" as per design and as directed by the achitect				
10	DRY PLANTER BOX WITH POT & PLANTS (WITH FLOWER POT)	NOS	6		
	Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18 mm thk. sandwiched plywood - sides finished in both inner and outer surfaces with 1.0mm thk laminate of approved shade and all exposed side edges of Ply/ board shall be covered with teak wood beading finished with matching Deco paint to give it similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with artificial/ natural plants as per architect's choice.				
11	COLOURED ACRYLIC SHEET LOGO FO THE BANK, BACK LIT (600 X 600)	NOS	1.00		
	Supplying , fabricating and installation of Canara Bank's Logo of 2 Nos of Triangle (Blue and Yellow Colour) made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Coloured Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect.				
	BUNK BED IN SECURITY GUARD'S ROOM	SET	3		

	<p>Providing and Supplying S.S Bunk Bed. The Legs shall be made of MSERW pipe Dia. 50.8 X 1.6mm thick which continues from top to bottom of the frame. Side supporting pipe of the frame is made of MSERW pipe Size 40x20x1.6mm thick and seven no. of pipe horizontally for Supporting mattress size 20x20x1.6mm thick (14 no. for up and Down). the ladder is made of 25x25x1.6mm thick MSERW pipe to go up for upper bed. Head side and leg side dia. 19.01x1.6mm pipe are welded with the legs as a supporting members and for safety of upper person at one side pipe shall be provided which help person not to fall down while Sleeping and it should be made of MSERW pipe Size 19.01x1.6mm thick. The entire frame goes under the Seven tank pretreatment process and should be duly powder coated with minimum thickness of 40-50 Microns (DFT). At bottom there shall be PPCP shoe to avoid Scratches on the Floor. The overall size of the bed shall be 2000mm (L) X 907mm (W) X 450mm (lower sleeping height) and 1770mm upper sleeping height. All the size shall have the tolerance of upper and lower deviation of ± 10mm for overall size & ± 0.2mm for metal. The manufacturer shall have quality and safety assurance like ISO-9001:2015, ISO-14001:2015 and ISO-18001:2007, BIFMA membership and AIOTA certification. The rate shall be inclusive of supplying of 2 Nos Pillow with cover, 2 Nos 4" High coired Mattress, 2 Nos bed cover per Bunk Bed. (Two bed- one below and the other on top shall consist of one Set of Bunk Bed)</p>				
	GRAND TOTAL				