

THE SPACE MATRIX

architects,planners,interior designers valuers

BOQ FOR FURNISHING WORK IN PALI MAIN BRANCH

BOQ FOR FURNISHING WORK IN PALI MAIN BRANCH					
Note:-					
i	The work to include all demolishen and diposal, shifting etc. as required, no extra payment will be given for this item.				
ii	The work to include shifting / reshifting etc. (including wiring arrangements) as required to be done , on day to day basis, for branch functioning, no extra payment will be given for this item.				
iii	The plywood must be treated with Anti-termite Solution before application.				
S.No.	Details of works. (Particulars)	Quantity	Unit	Rate (in ₹)	Amount (in ₹)
1	Gypsum Ceiling : P&F false ceiling with Gypsum Board 12.5mm thick fixed to a metal frame comprised of ceiling channel of size 80mm X 26mm X 0.5mm @ every 450 cms centres, inter channel 45mm X 15mm X 0.9mm @ every 1220mm centres, peri-meter channel 20mm X 26mm all along the wall, strap hanger suspendeds 25mm X 0 5mm with nuts and bolts 6.4mm x 12.7mm, connecting clip 2.64mm thick, dry walls screw 25mm long , soffit cleat. 27mm X 37mm X 25mm X 1.6mm thich and dash fasterner/ rawl plug 12.5mm dia X 35mm long with 6mm dia bolt. The joint of gypsum board to be taped 3 times and sealed with jointed compound with three coat plastic emulsion paint finished. Cut-out are provided to accommodate luminaries, air conditioning grills and fire warming dectors if any. The rate to include two or more coats of approved paint after preparing the surface. All fitting to be separately hung from the ceiling and should not rest on the false ceiling. (plan area shall be measured for payment)	510.00	sq.ft.		
2	Grid Ceiling : The grid false ceiling shall be provided in the Banking Hall, Manager's etc. The ceiling height and level shall be determined at the perimeter. The minimum height of the ceiling cavity should be 100 mm. All service fittings integrated within the suspended ceiling must be independently supported from the ceiling grid by a structure designed for the purpose. □ Ceiling tiles : Shall be Armstrong Fine fissured Classic lite RH99 of 16 mm thickness. Suspension system Shall be of Armstrong Trulok Silhouette reveal profile grid system with 15mm flanges incorporating 3mm central recess in global white with black reveal. Silhouette main runners and cross tees to have mitred ends and "birdsmouth" notches to provide mitred cruciform junctions.□ Installation : Main runners will be placed at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200 mm maximum centers and not more than 150mm from spliced joints. The last runner at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200 mm long cross tees to be interlock between main runners at 600 mm centers to form 1200x600mm modules. Cross tees longer than 600 mm require independent support. 600x600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200mm cross tees. The 1200mm cross tees to have central "birdsmouth" notches to facilitate fitting of 600mm cross tees. The perimeter trim to be Armstrong Trulok equal wall	712.00	sq.ft.		
3	Entry Glass door : Supplying and fixing of main door made of 12mm thick clear toughened glass in single piece with computerized diamond cut & diamond edge polish pencil edges all around including making required cutout holes for lock , handles , pivot patch fitting , corner fitting hinges etc. The rate is inclusive of providing of 3M film as per approved pattern/ Design on the door glass, cost of materials and labour charges etc. complete as per design and door to be fixed with heavy duty floor spring and SS finished patch fittings on top, bottom. The door also have a lock on bottoms and 450 to 600mm length SS brush finished handles with necessary hardware complete.	49.00	sq.ft.		
4	Fixed Glass partition : Providing & fixing 12mm thick clear toughened glass fixed partitions. The rate is inclusive of providing of 3M film as per approved pattern/ Design on the glass, cost of materials and labour charges etc. complete as per design and partitions to be fixed with SS finished patch fittings on top, bottom with necessary hardware complete.	63.00	sq.ft.		

THE SPACE MATRIX

architects,planners,interior designers valuers

5	<p>Incumbent Incharge Table: All Tables / counters/ work stations to have 19mm commercial ply board and 1.0 mm Pseude finish laminate finish on exposed surfaces as per approved colour scheme. The inside of the table to be provided with 0.8 mm thick laminate of White shade instead of painting the surfaces / area. All drawer units are to be laminated inside with 0.8 mm laminate. The drawers units to run on telescopic drawer channels. Drawer units to have two smaller and one bigger drawer with locking arrangement. Footrest made with T.W member of size 4"x2" finished with paint complete to be fixed for each table. The rate includes all necessary hardware such as drawer channels, SS handles locks with wire manager etc. The item also includes a tray for key board running on telescopic channel, finished with laminate on top with CPU tray etc. complete as per drawing and details and as instructed by the Architect. As per the above specifications with side table storage unit with shutters of sliding type. Table size 6'-0" x 3'-0" x 2'-6" & storage unit 3'-0" x 1'-3"</p>	1.00	Nos.		
6	<p>Officer Table : As per the above specifications with side table storage unit with shutters of sliding type. Table size 5'-0" x 2'-6" x 2'-6" & storage unit 3'-0" x 1'-3"</p>	1.00	Nos.		
7	<p>SWO Work station : As per the above specifications with Table size upto 5'-0"x2'-6" x 2'-6" & including 10mm thick clear glass in front of counter with teak wood beading of approved size and specifications in front of counter.</p>	6.00	Nos.		
8	<p>Cash Counter : As per the above specifications Cash Counter with table top should be in two levels, the top level shall be 1'-6" as customer top at 3'-10" level. The front shall be 10mm thick toughened glass upto 7'-0" level. All exposed glass face to be machine polished. The counter shall be made of 19mm ply board, with 01mm laminate as per drawings, storage unit with drawers, keyboard and pencil drawer on channels, cable manager, and laminated apron to match decor. Drawer unit and verticals made out of 19mm commercial ply board with key board drawers and 3 cash drawers (18"Wx24"Dx8"H) with note separator made out of 12mm ply board with lipped edges. PC stands for PC below work top and 19mm ply board for footrest finished. All drawers to be provided with Godrej lock & SS handles of approved make. The exposed side of front facade, drawer front shall be finished with 01mm Pseude finish laminate as per drawing encised. The inside of the table to be provided with 0.8 mm thick laminate of White shade instead of painting the surfaces / area. All drawer units are to be laminated inside with 0.8 mm laminate. The item includes supply & fixing of flush door shutter with necessary hardwares, door stopper, tower bolt, Night Latch & mortise lock of approved matke. All exposed surface covered with teak lipping 6mm thk as required with polish finished.Cash Counter size up to be (5'-0" x 2'-6" x 3'-8").</p>	1.00	Nos.		
9	<p>Wooden Partition Full Height : Providing and Fixing of full height wooden glazed partition made of 2 MM thick Aluminium tube frame size 50x50mm. The sections are placed @ 600 x 600 mm C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminium angles and fastened with steel screws. The alternative corner vertical members of the partitions shall be taken up to the ceiling level (Payment shall be made for the partition measured below the false ceiling level) Frame work shall be fixed with 9 MM thick BWR Ply on both side finished with 1mm thk.Pseude finish Laminate in approved colour,design, Patern and size. The glazing will be of 8mm thick clear glass panel fixed within 900-2100mm ht. There will be designed glass film over the glazing area with required design complete as directed by Architect. The item includes supply & fixing of flush door shutter with necessary hardwares, door stopper, tower bolt & mortise lock of approved matke. All exposed surface covered with teak lipping 6mm thk as required with polish finished. the work should be completed in all respect as perspecification & satisfacation of Architect.</p>	668.00	sq.ft.		

THE SPACE MATRIX

architects,planners,interior designers valuers

10	<p>Wooden Partition Full Height (Dry Wall) : Providing and Fixing of full height wooden glazed partition made of 2 MM thick Aluminum tube frame size 50x50mm. The sections are placed @ 600 x 600 mm C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminum angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminum angles and fastened with steel screws. The alternative corner vertical members of the partitions shall be taken up to the ceiling level (Payment shall be made for the partition measured below the false ceiling level) Frame work shall be fixed with 9 MM thick cement sheet (BISON PANEL) both side finished with plastic paint with bands and combination with grooves etc. as per details. The item includes supply & fixing of flush door shutter with necessary hardware, door stopper, tower bolt & mortise lock of approved make. All exposed surface covered with teak lipping 6mm thk as required with polish finished. the work should be completed in all respect as per specification & satisfaction of Architect.</p>	223.00	sq.ft.		
11	<p>Wooden Partition Low Height : Providing fabricating & fixing of partition up to the level of 4'-6" ht. with frame work made of 2 mm thick Aluminium tube frame size 50x50mm. The sections are placed @ 600 x 600 mm c/c both ways & additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor with suitable aluminium angles and fastened with steel screws.(as per site requirement) Frame work shall be fixed with 9 MM thick Ply on both side finished with 1mm thk.Pseude finish Laminate in approved colour, Patern and size with bands & combination with grooves etc. as per details. The sides/top shall be finished with teak wood beading with Pseude finish finish . This partition will be 3' ht. with up to 18" ht.10mm thick toughened etched glass. Partition including chowkhats for flap doors, door & to be fixed with all hardware, tower bolts, stoppers in brass etc complete fine finish.</p>	149.00	sq.ft.		
12	<p>Cash Cabin Partition: Providing fabricating & fixing of partition from floor level to 7' height with frame work made of 2 MM thick Aluminium tube frame size 50x50mm. The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor with suitable aluminium angles and fastened with steel screws.(as per site requirement) Frame work shall be fixed with 9 MM thick BWR Ply on both side finished with 1mm thk. Pseude finish Laminate in approved colour,design, Patern and size with bands and combination with grooves etc. as per details.. The sides /top shall be finished with teak wood beading with Pseude finish finish This partition will have 3" x 1" chowkhats for doors, including provision of windows as per size with 10 mm thick etched as design glass and beading for fixing the window glass and covering the joints between partition and chowkhats etc. .Same pattern door to be fixed in the partition with polishing & with all hardware, tower bolts, stoppers in brass etc complete fine finish as per design and to the satisfaction of Architect/ Bank.</p>	56.00	sq.ft.		
13	<p>Wall Panelling: Providing and Fixing of wooden Panelling of wall on hall and column made of 2 MM thick Aluminium tube frame size 50x25mm. The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminium angles and fastened with steel screws. Frame work shall be fixed with 9 MM thick BWR Ply finished with 1mm thk. Pseude finish Laminate in approved colour,design, Patern and size with bands and combination with grooves etc. as per details. All exposed surface covered with teak lipping 6mm thk as required with polish finished. the work should be completed in all respect as per specification & satisfaction of Architect.</p>	650.00	sq.ft.		
14	<p>Storage : Providing and fixing wooden storage 450 mm wide and 750/1200/2400 mm high having sides, partitions shelves and shutter made of 19 mm th. BWR Ply with 6mm BWR ply to be fixed at the back finished with 1 mm Pseude finish laminate with all other exposed external surface. The inside of the storage to be provided with 0.8 mm thick laminate of White shade instead of painting the surfaces / area. All drawer units are to be laminated inside with 0.8 mm laminate and with side hinged sutter complete with horizontal & vertical division for stacking of files as per design including of handles, SS hardwares, locks etc. (for the purpose of contractor's payment only front elevation area of a cabinete will be</p>	110.00	Sq.ft.		

THE SPACE MATRIX

architects,planners,interior designers valuers

15	Notice Board : Providing & fixing on partition/ walls soft pin-up board as per following specification:- Core material of 10mm thick soft board finished with approved fabric. Framed with teak wood of section size 4"x2'-6"	1.00	nos.		
16	Solid flush doors: Providing & fixing 35mm thk water proof ready made solid flush doors for Toilets, cabins, ancillary areas specified to match the solid partitions including 2nd class BTC frame of 100 X 50mm finished with 1.0mm thk Pseude finish laminate on both sides including heavy duty door closers, locks, handles, hinges etc. complete as per the directions of Architect.	25.00	Sq.Ft.		
17	Providing & fixing of Hydraulic Door Closers as per approved make.	4.00	Nos.		
18	Slips counter / Writing ledge, Suggestion box, Cheque dropping box: 10 mm bevelled clear glass to SLIP counter 3'0" x 1'3" x 3'6" height with shelf and Pigeon holes to keep slips with suggestion box made out of solid ply and finished with 1 mm thk Pseude finish laminate and inside 0.8 mm thick laminate of White shade instead of painting the surfaces / area and 1" high slit is to be made in the front for letter etc. and 1" thk slit to be made in the front for letter / cheque etc. of 19mm block board fabrication approved pattern laminated as per design in drawing with divisions below and shutter in front to create to boxes for mail, clearing etc.	1.00	nos.		
19	Aluminum Composite Panel Sheet (external 4mm): Proving and fixing in position Aluminum composite panel Boxing with PVDF Coating & LDPE core laminated of approved make Exterior Grade 4 mm thick with composite of (0.5mm - 3mm- 0.5mm) including fabrication for the same with aluminum sections, required hardware, silicon sealant (Dow Corning 789) masking tape, necessary scaffolding etc. complete in all respects.	300.00	Sft		
20	Vertical Blinds :Providing and fixing fabric slats of 4" wide of Vista/Mac make. It will have bottom pockets for housing bottom weights coupled together by means of endless bead chain pivotally attached as per manufacturer's specifications. The slats overlap should not be less than 12mm. The slats movement will be on travelers assembled and should include head channel, spline, shaft, slat traveler, slat spacer links, tilt control, slat carriers, bottom weights, linkage chains, channel mounting brackets, traversing cord and fabric slats with all the necessary hardware's as per schedule.	33.00	Sq.ft.		
21	Aircon Louvers : Providing & fixing 6" wide Powder coated Aluminum Aircon Louvers.	4.00	Sq.Ft.		
22	Panel Box : Providing and fixing wooden Panel Boxing 450 mm wide having sides, partitions, shelves and shutter made of 19 mm th. BWR ply finished with 1 mm laminate with all other exposed external surface & inside cement sheet (BISON PANEL) finished with enamel paint internal surface complete and with side hinged shutters complete with horizontal & vertical division as per design including of handles, SS hardwares, locks etc. (for the purpose of contractor's payment only front elevation area of the cabinete will be measured) .	52.00	sq.ft.		
23	Supply and application of washable interior grade Dulux 3-in-1 pastic emulsion paint on walls with 1 coat of wall primer and 2 or more coats of plastic emulsion paint as per manufacturer's specifications etc. all complete. All painting final coats to be done after removal of face plates of switch boards in coordination with the electrical contractor and face plates to be fixed only after satisfactory completion of painting.	200.00	Sq.Ft.		
24	Providing & applying with approved shade 2 or more coats of Synthetic Enamel paint of approved make including preparation of necessary base & under layer.	200.00	Sq.Ft.		
		TOTAL (₹.)			