

BOQ OF INTERIOR & FURNISHING WORKS OF Vivekanandanagar BRANCH & ATM					
S.No	Particulars with Description	Qty	Rate	Unit	Amount
	<b>PARTITIONS:</b>				
1	Full Height Solid Partitions : Providing and Fixing of Full height partitions all made with Sall/Kail/Marandi wood frame of 2"x2" section with 2'0"x2'0" c/c vertically and horizontally. Frame to be covered with 8 mm plywood from both sides. 1mm thick GLOSSY laminate to be covered from both the sides of the partition. Frame should be properly fixed to the Floor, Vertical members should be firmly to the Slab and side wall available. GLOSSY laminate should be considered up to two or three colour combination. All as per the design suggested at site and instructions of engineer.(Frame work above false ceiling done for fixidity shall not be measured but contractor may factor it while quoting their rate as measurements up to false ceiling level only be taken). Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI. Each panel of glass/ply to be fixed with film of bank logo in true colours of size 6" dia to look elegant.	355.00		sft	
2	<b>Low Ht /Half Ht Solid Partitions:</b> Same as Item no 1 but Low ht or Half height as per design. Edges of the partition to be covered with 3"x1.5" Steam beach wood duly male mine polished moulding. All as per the design and instructions of the design in charge. Plywood wherever mentioned Must be ISI MARKED IS 303 AND BWR GRADE.	175.00		sft	
3	<b>Full Ht. Glazed Partitions :</b> Same as Item no 2 but 8mm Plain Glass with Etching & Acid texture DESIGN or One way vision film of banks approved design should be provided with 35mm x 12mm Steam beach Molding duly melamine polished. This glass will be starting from 3'-0" ht from ffl .All as per the design and instructions of Architects. Plywood wherever mentioned BWR GRADE IS 303.	260.00		sft	
4	<b>MAIN ENTRANCE DOOR:</b> 12mm toughened glass partition with Dorma patch fittings or equivalent, including cost of doors. The quoted rate should include for fixing frosted film / one way vision film work, with banks approved design, CANARA logo, write up in the top two bands of film (frosted /one way vision film) as directed by the Architects. SS handles of size up to 450mm long best make, brass locking arrangement (at top) to be fixed to the door. Glass may be fixed in a ss channel on the floor and wood work at lintle level for fixidity.	180.00		sft	
5	<b>Cash Cabin:</b> Providing and fixing partition with 2"x2" salwood section without saps and joints treated with anti-termite oil and fire retardent paint to be placed 2'.0"x2'.0"c/c horizontally and vertical frame work upto trueceiling and to be covered with 6mm thk plywood on wooden section finished with 1mm thk GLOSSY laminate as follows as per scheme.The partition to be blocked upto 3'.0" and from 7' 0" height will have 8mm thk clear glass with glass etching to be embedded into partition with the beach etching to be embedded into partition with the beach as per design	250.00		sft	
6	Float Glass partition for cash counter:with 2" x 1 1/2" salwood section covered with 6mm thk ply wood finished with 1mm thk GLOSSY laminate and 12mm thk to float glass to be fixed embedded into partition above3'6"ht.	60.00		sft	
7	Deco Grill partitions for cash cage:with2" x 1 1/2" salwood section covered with 6mm thk ply wood finished with 1mm GLOSSY laminate and Almn powdercoated decogrill to be fixed embedded into partition above 3'6" ht Including roof grill. The item is to be completed in all respects as per design, approval, instructions of the bank. The item is to be completed in all respects as per design approval, instructions of the bank.	70.00		RFT	
8	Doors: Providing and Fixing standard wooden section bottom rails fixed with lintel and floor, with 12mm Modi Guard/Saint Gibain clear float glass with sand Blasting etching as per design and in wooden rail and wooden section to finished with duco superior metallic of to finished with approved shade and make as per scheme.				
	a. Glazed with 35mm thk solid core flush door finish with 5mm thkModiguard/Saint Gobain clear etched glass. The rate shall include the door frame(3" x 1 1/2") salwood, door lock, handle door closer etc.,with 1mm thick lamination on both sides & teak lipping of 35 x 2mm on all sides only lamination to be exposed.(21 sft each approx.) The item to be completed in all respects as per design, approval, instructions of the bank	5.00		no	

	<b>CLERICAL COUNTER.</b>			
9	Supply and fixing of running counter 600 wide with top made up of 19mm thk ply with GLOSSY laminate of 1.0mm thk on top as approved by the bank and wooden beading/ moulding all round melamine polished. The table to include a pedestal unit with a drawer and shutter. The works to include key board tray and all hardware fittings fixtures etc. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per Engineer design. Plywood wherever mentioned Must be BWP GRADE AND IS 303, MARKED ISI.	45.00		RFT
10	Providing and fixing <b>glass railing</b> in clerical counter by fixing of Teak wood around shape pillar and 12mm thick modi float clar glass with etching and all edges finished in machine polish "C" shape including fixing charges.	80.00		RFT
11	<b>Table for BRANCH MANAGER WITH SIDE RACK</b>			
	Providing and fixing tables made out of 19mm thk BWR block board of approved make clad with 1mm GLOSSY laminate( color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk block board with GLOSSY laminate finish in the front ,sides to be made out of 12mm BWR plywood and bottom to be made out of 6mm BWR plywood and it should play in drawer sliding telescopic channels. The inside of the drawer and the table to be duly paint . A leg rest to be provided duly polished made out of 3"x2" Wooden Section. A shutter to be made by 19mm BWR Block board clad with 1.0mm GLOSSY laminate .The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. On top of the table 8mm thk glass to be placed with duly edge polished .The table should have key board tray and tea tray duly finished with 1.0mm GLOSSY laminate. The necessary wire managers to be provided on the tables and provision for lights to be kept if required in the front of the table. All the exposed areas to be duly malamine polished The work to be completed as per design and approval of the Architect. Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI.	1.00		no
12	<b>Cash counting/stitching table</b> made with 18 mm ply for top and supports and complete with Lamination. (5'X1'6"x2'6")	1.00		nos
13	<b>Cash counter 2'-6" depth Ht. 3'-8"</b> with 18mm solid plywood for counter top at 3'-8" ht and for the table top at 2'-6" he, the same for the front, sides etc., Finished with 1mm thk GLOSSY laminate for drawer, front, table top front counter. Which will have provision for modular key board tray including mouse tray and the drawer with set lock system. The table will have a provision for horizontal CPU unit/trolley. The inside exposed surfaces will be enamel painted with approved shade.	5.60		rft
14	<b>Writing ledge:</b> Made out of 18mm solid ply the sides of which will be polished of approved shade and the top provided with 18mm ply with GLOSSY laminate	2.00		nos
15	<b>DISPLAY BOARD/POSTER FRAME:</b> Providing and fixing poster frame fabricated using 2 sheets of 24" x 18" clear acrylic. Outer sheet should be 5 mm thk and bevelled crystal edge polished for 3/4" at 8-10 degrees on all sides in the front, Rear sheet should be 5mm and flat.	2.00		nos
16	<b>SOFT BOARD / NOTICE BOARD:</b> Providing and fixing soft board with necessary framework with 12mm BWR plywood on top 12 jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly polished along the periferi.	2.00		no
17	<b>SUGGESTION BOX/DROP BOX</b> Providing and fixing of 18mm thk BWP ply for top sides front shutters finished with 1mm thk GLOSSY laminate. For all exposed external surfaces with necessary lipping at front. Inside of the storage to be enamel painted. The rates includes godrej multipurpose lock. S.S.handles, hinges etc.,	2.00		nos
18	<b>Vertical Blinds:</b> 100mm wide vertical blinds having top rail 39mm x 34mm 91.2mm thk)The lower fabric shall be of polyster viscose/polyster/yam as per approval.	100.00		sft

19	<b>FALSE CEILING-</b> The item is to be completed in all respects as per design, approval, instructions of the bank.			
	Providing and fixing ½" thk. V board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.	660.00		sft
	Providing, fabricating, erecting lay-in type tegular/ drop type Mineral fibre board false Ceiling of 600mm x 600mm grid as per the following specifications.The approved brands are ARMSTRONG/ NITTOBO / SAINT GOBAIN. The grid system having 600mm x 600 mm or part thereof wherever necessary, shall be made using hot dipped galvanized steel section, exposed surface chemically cleaned capping prefinished in backed polyester paint, main Tee of size 14 x 38 x 0.33mm at every 1200mm c/c max and rotary stitched cross tee of size 14 x 38 x 0.33mm at every 600mm c/c and cross Tee of size 14x 38 x 0.33mm at every 1200 c/c max and 14 x 22 x 0.457mm wall angle alround the wall to form grid size of 600 x 600mm. The suspension system shall have 4mm dia prestraigthened GI rods which are in-turn supported from real ceiling using 6mm size anchor bolts, connected with adjustable Hanger clips/ J bolts and other accessories as per the manufacturers specifications. The T Sections have a Galvanizing of 120 grams per M2 & passed through for 500 hrs of Salt test. TThhee item shall include the cost of additional Tee or L supports & other accessories near the ends/ odd size edges/corners, making necessary openings for electrical light fittings, fire alarm detectors and any other fixtures. No extra payment shall be made for making openings in the panels/ grid for the purpose of light fittings. Item rate shall include all the taxes, transporation, erection, loading & unloading and any other incidental expenditure that may be required to be spent in completing the work in totality as per above specifications.The tiles removed to place light fittings shall be handed over to bank's custody and there may not be any deduction for light fittings area.	880.00		sft
20	<b>WALL AND PILLAR PANELLING:</b>	1100.00		SFT
21	<b>DRESSING UNIT FOR LOCKER ROOM</b>	1.00		Nos
22	<b>DINING PLANK:</b> 3' x 11' Made out of 18mm solid ply the sides of which will be polished of approved shade and the top provided with 18mm ply with GLOSSY laminate	1.00		Nos
25	<b>Storage Units:</b> Providing and fixing Full height storage 400mm deep made out of 19mm BWR block board finished with 1.0mm GLOSSY laminate in all exposed areas . The drawers to be made out of 19mm BWR block board in the front cladded with 1.0mm GLOSSY laminate( color, vertical grain) .sides to be made out of 12mm plywood and bottom made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels . The shutters to be made out of 19mm block board and should play on drawer sliding castors on powder coated channels. The necessary locks , handles, etc to be provided . 3" x1/2 wooden skiritng to be provided duly polished as per matching tone all along the visible areas . Inside of the unit to be enamel painted in matching tone . All the exposed edeges of the boards/plywoods to be coverd with wooden lippings/mouldings duly polished all complete.The work to be completed as per approval and specificaion of the Engineer. Plywood wherever mentioned Must be BWP GRADE AND IS 303, MARKED ISI.	250.00		sft
<b>Total Amount (Excluding GST)</b>				