

ESTIMATE OF CIVIL WORK FOR CANARA BANK AT DTC PATPARGANJ DELHI BRANCH					
S.No.	Particulars	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1.0	BRICK & CONCRETE WORK				
1.1	Providing Brick Work 230 mm thick with bricks of class designation 75 laid in cement mortar 1:5 (1 part cement : 5 parts coarse sand). The item includes cleaning base floor finishing and reaching upto base floor concrete slab and then laying brick work over base mortar layer of 12mm thickness, including necessary curing, scaffolding etc. complete as per instructions of Architect/ Bank's Engineer. (FOR SAFE ROOM)	Cu.Ft.	180.00		
1.2	Providing Brick Work 115 mm thick with bricks of class designation 75 laid in cement mortar 1:3 (1 part cement : 3 parts coarse sand). The item includes cleaning base floor finishing and reaching upto base floor concrete slab and then laying brick work over base mortar layer of 12mm thickness, including necessary curing, scaffolding etc. complete as per instructions of Architect/ Bank's Engineer. (For UPS ROOM)	Sq.Ft.	115.00		
1.3	Providing Cement Plaster 15mm thick on new brickwork and wherever required. The plaster is to be done in cement mortar 1:6 (one part cement : 6 parts fine sand) with water proofing compound (CICO/ Dr. Fixit/ Pidilite). Item includes removing existing plaster, cleaning of the surfaces with wire brush as required, necessary curing, scaffolding etc. & also removal of all malba from the site and Bank's premises on day to day basis etc. complete as per instructions of Architect/ Bank's Engineer.	Sq.Ft.	820.00		
2.0	M.S. WORK				
2.1	Supplying and fixing Rolling Shutter made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters including applying two coats of synthetic enamel paint on all surfaces of the shutter over a coat of primer as per manufacturer's specifications etc complete to the satisfaction of the Architect /Bank's Engineer.	Sq. Ft.	85.00		
2.2	Providing and fixing in position Collapsible Steel Shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles,including applying a priming coat of approved steel primer as per manufacturer's specifications etc complete to the satisfaction of the Architect /Bank's Engineer.	Sq. Ft.	75.00		
2.3	Providing and fixing MS Grills in SAFE ROOM of 16mm MS solid square bars spaced at 100mm (3") centre to centre in MS angle frame fabricated out of 65mmx 65mmx 6 mm angle section with welding having suitable angle iron holdfasts for fixing the grill in the openings in the walls including applying two coats of synthetic enamel paint on all surfaces of the over a coat of primer as per manufacturer's specifications etc complete to the satisfaction of the Architect /Bank's Engineer.	Sq. Ft.	330.00		

2.4	MS GRILL FOR CEILING OF SAFE ROOM :- Providing and fixing MS grills for ceiling of Strong room using 20mm MS Square Bars @ 75mm c/c as per design given via welding. The edges to be supported on IS angle 65mmx65mmx6mm on all sides with welding. The side angles to be fixed to the walls/ Steel firmly with anchor bolts. The rate is inclusive of 2 coats of Antirust paint. Complete to the satisfaction of the Architect /Bank's Engineer.	Sq. Ft.	85		
3.0	MISCLLEANOUS WORKS				
3.1	BLOCKED DOOR (3'-0"x7'-0") :- Providing and fixing made in 35mm thick Flush door with 1mm lamination form both sides , Acid texture border fixed with Steam beach molding duly melamine polished. 35mmX 12mm steam beach Lipping to be provided to all the edges of the door . Rate also to include the cost of Door Frame/Chowkhat made Steam beach wood fixed in partition or wall.. Door Frame should be fixed properly to the wall / Partitions, All Hardware should be of Brass / SS Brush finish with ISI mark. Hardware includes Concealed Door closer, Cylindrical Lock, Door stopper and other standard needs. All as per the design and instructions Architect /Bank's Engineer.	Sq. Ft.	42		
3.2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new/existing work.	Sqft.	450		
3.3	P/Applying two or more coats of Acrylic Emulsion Paint over Walls & ceiling after preparing the surface with a coat of primer.& 6 mm th. POP.finish.	Sqft.	1100		
A	TOTAL FOR CIVIL WORKS (EXCLUDING GST)				
	Discount If any (Only on Excluding GST amount only)				
	Net Amount (After Discount if any - Excluding GST) (Discount if any shall be given on Amount in Sub part (A -Excluding GST).				
	GST as extra as applicable (For Civil works)-By Bank				