

केनरा बैंक Canara Bank 

भारत सरकार का उपक्रम

A Government of India Undertaking

 सिंडिकेट Syndicate

Premises & Estate Section, Circle Office Karnal, PIN - 132001.

BOQ FOR FURNISHING WORKS AT: SUNCITY BRANCH, GURUGRAM

S.N O.	DESCRIPTION OF ITEM	QTY	UNIT	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
1	PARTITIONS				
	Frame Work: Providing and fixing in position Full Height partition in framework of 600 X 600 mm grid (horizontally and vertically) comprising of 50mm X 50mm heavy duty GI Box Sections (0.5 mm) with 8 mm thick ply on both sides finished with 1 mm thick laminate as mentioned below.				
	Note: a) In case of false ceiling, the vertical GI members to be fixed to RCC ceiling but the area of partition payable will be below the false ceiling only. b) Measurement of height shall be taken from finished floor only, in case of varying heights on either side of partition, average height shall be considered. c) Openings/ door/ glass shall not be measured for payment and shall to measured and paid under seprate relevant item.				
	Laminate: 1.0 mm thick matt laminate (shade and design as per Bank's Scheme) pasted over MDF with approved adhesive. Laminates shall be combination of 3 colours - White, Blue and Yellow to be approved from the bank prior to application. Partition shall have 100mm high skirting from the finished floor in Canara Bank Blue shade and a 100mm high top band from the soffit/ceiling/visible top of the partition in Canara Bank Yellow shade. Remaining Area to be covered with White laminate.				
	The necessary openings and provisions in the frame work for Electrical Conduits, modular electrical boxes, AC Grills & pipes, AC Ducts / louvers, doors / glazing etc. should be provided as per site requirements while keeping the structural integrity and strength of the framing intact. The GI frame members shall be fixed rigidly to the floor, columns, RCC Ceiling and beams. Note: In case of false ceiling, the vertical GI members of the frame should be fixed / screwed / grouted rigidly on the Roof / RCC ceiling but the area of partition payable will be measured from the finished floor up till the false ceiling only. In case of varying heights on either side of partition, average height shall be considered.				
1a.	Cash Cabin Partition (Height 7'-6")	60.00	Sq. Ft.		
	Proving and fixing both side laminated Solid partition for cash cabin using framing, MDF and laminate as per details mentioned in Sl. No.1. The partition shall be solid till 4'-0" height and thereafter an opening of 2'-6" Height & 2'-6" width (or of appropriate size as per site requirement) for Aluminium Decorative Grill (12mm thick having hexagonal openings) which shall be provided with double sided 2 coat melamine polished teakwood beading. Rest of the height shall be solid partition till the height of 7'-6" from the finished floor. All exposed edges of MDF shall be fixed with teakwood lipping of appropriate thickness (75mmx75mm thick sections or as per site) enough to cover the entire exposed edges and frame opening for aluminium grill / doors chowkhat / windows etc.) with 2 coat melamine polish.				
	The rate quoted must be inclusive of the 32-35mm thick door (Size - 7'-0"x3'-0") made with commercial plywood / board of approved make with 1.0 mm thick matt finish laminate pasted over plywood along with skirting and top band on both sides of the door as per bank's colour scheme along with making 6mm thk glass opening of size 18"(W) X 48"(H) positioned at the horizontal centre & 5'-0" height for visibility with proper teakwood framing and polishing. The exposed edges of the door must be finished with teakwood lipping with 2 coats of melamine polish. Item shall also include supply and installation of frosting film of aproved make with approved artwork. Film shall be self-adhesive with bubblefree installation to be done on clean glass.				

<p>A 2" deep slip tray made of 11mm/12mm MDF covered with 1.0 mm thick white matt laminate with edges finished with teakwood beading and 2 coats of melamine polish to be affixed at a height of 4'0" from the finished floor on the side partition adjacent to the passing Officer's counter at an appropriate slot to ensure convenient usage by both staff members. The slip tray must be 6" wide 10" long and must be positioned such that it must be emanating 4" on either side of the partition. The front edges of the partitions i.e., the edges visible to the customers, shall be finished with 1.0mm thick laminate of Canara Bank Blue shade. The rate quoted must also include installing / affixing all necessary fittings like 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, Hydraulic Door Closer, Night latch, SS Handles on both sides & Brass Door Stopper etc as per approved makes.</p>				
<p>1b. Low Height Partition (Height 4'-0") - Between working Counters, cubicles & support for Flap door)</p>	50.00	Sq. Ft.		
<p>Proving and fixing both side laminated solid partition using framing, MDF and laminate as per details mentioned in Sl. No.1. The partition shall be solid till 3'-0" then glazing with 8-10mm thick clear float glass of 1'-0" Height & supported on 4" wide solid partition pillars on both sides of the glass. The exposed edges of the glass shall be bevelled, grinded and machine finished to render smooth edges. The glass in the partitions shall be fixed with beading / moulding on both sides. All exposed edges of partition shall be fixed with teakwood lipping of appropriate thickness (75mmx75mm thick sections or as per site) enough to cover the entire exposed edges and frame opening for fixed glazing / doors / windows) with 2 coat melamine polish. Item shall also include supply and installation of frosting film of aproved make with approved artwork. Film shall be self-adhesive with bubblefree installation to be done on clean glass.</p>				
<p>The length of the partitions between the counters shall be 3'0"</p>				
<p>1c. Solid Partition (Full Ht.) - Both Side Laminated</p>	152.00	Sq. Ft.		
<p>Proving and fixing both side laminated solid partition using framing, MDF and laminate as per details mentioned in Sr. No.1. All exposed edges of partition shall be fixed with teakwood lipping of appropriate thickness enough to cover the entire exposed edges and frame opening for doors chowkhat (75mmx75mm thick sections or as per site) with 2 coats of melamine polish. The rate quoted must be inclusive of the 32-35mm thick door (Size - 7'-0"x3'-0") made with approved plywood / board of approved make with 1.0 mm thick matte finish laminate pasted over plywood along with skirting and top band on both sides of the door as per bank's colour scheme. The rate quoted must also include installing / affixing all necessary fittings like 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, Hydraulic Door Closer, Mortise Lock Assembly, SS Handles on both sides & Brass Door Stopper etc as per approved makes. The exposed edges of the door must be finished with teakwood lipping with 2 coats of melamine polish.</p>				
<p>1d. Solid Partition (Full Ht.) - Cement Fiber Board for UPS Room</p>	195.00	Sq. Ft.		
<p>Proving and fixing both side solid partition using framing and laminate as per details mentioned in Sl. No.1. The skin of the partition shall be made out of 10mm thick cement fiber board and finished with 1mm thick laminate of approved shade and scheme on the customer side (visible to customers) and 2 coats of ivory white enamel paint on the internal side (not visible from the customer lobby). The rate quoted must be inclusive of the providing one pane door for UPS room (Size - 7'-0" x 2'-9") & 2 panes door (Size-7'-0" x 2'-0" for electrical panel) or door sizes as per site requirements in combination of 6mm thk cement fibre board and 19mm thick approved block board pasted / screwed together to form a single entity and finished as per matching scheme. The block board shall be on the outer side and shall be pasted with 1.0 mm thick matt laminate along with matching skirting & top bands as per bank's scheme and the cement fiber side of the door shall be on the inside with 2 coats ivory white enamel paint over a coat of primer. Exposed edge of door thickness shall be finished with teakwood lipping & melamine polish.</p>				

<p>Item shall include installing / affixing 12" X 6" aluminium louvers at the horizontal centre of the door panes at suitable height along with all other necessary hardwares & fittings such as 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, mortice lock / brass tower bolt, SS Handles on both sides, magnetic ball catchers etc of approved makes.</p> <p>Note - For the purpose of contractor's payment in case of Electrical panel cabinet, only front elevation area shall be measured. BUT the partition shall be erected till soffit of the actual ceiling along with the board concealing the entire area and not just till the false ceiling.</p>				
<p>1e. Flap Door (4'0" High)</p>	<p>25.00</p>	<p>Sq. Ft.</p>		
<p>Providing and fixing of flap door using 19mm thick block board of approved make laminated on both sides with 1mm thick laminate of approved shade as mentioned above. The exposed edges of the board shall be finished with teakwood beading of appropriate thickness (enough to cover the entire exposed edges). The rate quoted must also include a vertical brass tower bolt assembly, 2 Nos. SS Butt Hinges (100mmx5.5mm size), screws & magnetic ball catchers etc of approved makes. There shall be 100mm high skirting at the bottom of the door with 1mm lamination in Canara Bank Blue shade & a 100mm high top band of Canara Bank Yellow colour at the vertical top of the door so as to match the surrounding scheme.</p>				
<p>2 COUNTERS & TABLES</p>				
<p>Providing & Fixing Box type Tables and counters of size mentioned below as per branch drawing and layout. The tables / counters are made out of 19mm thick approved ply / block board frame work for top, verticals, apron, sides, drawer unit with shelves, shutters, customer top, foot rest. The sides, sliding shutters, front apron of drawer unit shall be made out of 12.0mm thick approved ply while backs & bottom of drawer unit shall be made with 6mm thick approved ply. The drawer unit of 450mm width x 750mm height x 500mm depth or size approved by the bank shall be placed on a suitable side of the table / counter as per layout. The drawer unit shall consist of 3 nos. drawers of equal height to cover the entire height of the unit & each must be 450mm deep OR of size & number as approved by the bank. Each drawer shall have SS handles with multipurpose concealed lock. The drawers shall be fixed with telescopic SS sliding channels of approved make with easy push-pull mechanism.</p>				
<p>A uniform 100mm high skirting shall be provided at the visible bottom of the side unit with 1.0mm thick laminate of Canara Bank Blue shade. A fixed footrest made with T.W. member of size 4"X1.5" finished with french polish shall also be provided at the bottom of the inside of the tables / counters at a comfortable height. <u>The working top of ALL counters / tables shall be provided with 10mm thick clear glass on top with edges bevelled and machine finished to render smooth edges.</u> Grooves / openings for cable managers shall also be provisioned in the table and glass along with supply & fixing of cable manager. The shape of the top glass shall be prepared / cut in such a manner that the entire surface of the working top of the table / counters should be covered by the top glass.</p>				
<p>All the open surfaces of the tables / counters / drawer units shall be completely covered with 1mm thick laminates. The front apron and visible side apron(s) of the counters / tables shall be provided with 100mm top band of 1.0mm thk laminate of Canara Bank Yellow shade & 100mm skirting of of 1.0mm thk laminate of Canara Bank Blue shade. The remaining area shall be provided with 1.0mm thick white laminate. The counter / table top shall be provided with 1.0mm thick laminate of Canara Bank Blue shade. The other exposed edges shall be finished with teakwood lipping & 2 coats of melamine polish. All inner surfaces shall be finished with approved 0.8 mm thick laminate of ivory / white shade of approved make.</p>				
<p>All table / counters shall be provided with sliding key board unit of size 12"x20" made of 19mm thick approved board finished with 1.0mm white laminate and mounted with telescopic channels of approved make on the sides made out from 12mm thk approved board with 1.0mm thick white laminate. All exposed edges to be finished with teakwood beadings of appropriate size and 2 coats of melamine polish along with all other finishes / hardware / fittings etc required to complete the job.</p>				

<p>For <u>CASH COUNTER</u>- Same as above but the cash counter shall have two working tops viz. one working top at height of 2'-6" for staff & other, the customer top, at height of 4'-10" for customer use. The customer top shall be 450mm wide of length as mentioned below and shall be fabricated such that it is projected 150mm outwards i.e. towards the customer. The rate quoted must include full front portion and customer top of mentioned height and style made out of 19mm approved ply and 1.0mm thick laminate of design as approved by the Bank, along with 10-12mm plain float front glass which should be 3'-0" high over and above the customer top and of required length as mentioned below. A support partition shall also be provided on top of the glass till a height of 7'-6" from the finished floor. The partition over the glass shall be made out of 19mm thk approved board finished with 1.0mm thick laminate of Canara Bank Blue shade. The front glass shall be fixed rigidly over the customer top with teakwood beadings on both sides finished with 2 coats of melamine polish. Two openings / slits shall be provided in the front glass - one opening of 300mmx150mm on the horizontal centre at the bottom of the glass and another 3" wide horizontal slit at the vertical centre of the front glass for convenient cash and voice transaction. The glass edges shall be bevelled on all exposed edges on both faces to ensure safe & smooth edges.</p>				
<p>2a. Branch In-charge Table (Size: 6'0"x3'0"x2'6"(H))</p>	1.00	No.		
<p>2b. Staff Counters (Width of working top: 2'6"; Height: 2'6")</p>	15.00	R. Ft.		
<p>2c. Cash Counters (Width of working top: 3'0" & width of customer top: 1'6"; Heights as per description above)</p>	5.00	R. Ft.		
<p>3 STORAGE CABINETS / CREDENZAS</p>				
<p>Providing & placing in position box type storage cabinets / Credenzas 18" deep & height as given below made out of 19mm approved board with 1mm laminate with shade as per bank's approved scheme. The top of the low height storages / credenzas shall be finished with 1.0mm thk Canara Bank Blue laminate. The sides, partition, top, shelves & bottom shall be made out of 19mm thk. approved board and back made out of 6mm thk. approved ply. Item shall have one 6" high drawers on top made out of 19mm thick approved ply / board complete with handles, locks etc of approved makes. The shutters made out of 19mm commercial ply wood finished with 1.0mm thk laminates of approved scheme on the outer surface shall cover the remaining space available below the drawers. All inner surface shall be finished with 0.8mm thick white laminate with matching edge tapes for all exposed edges. A 100mm high top band shall be provided on top front face of the storage cabinets / credenzas finished with 1mm thk canara bank yellow laminate & 100mm high skirting finished with canara bank blue laminate shall be provided as per approved make.</p>				
<p>The drawer must be finished with 1.0mm thk laminate of shade as per Bank's scheme on outer surface and 0.8mm thick white laminate on the inner surfaces. The drawers shall be supported with SS telescopic sliding channels of approved make with smooth push-pull mechanism along with SS handles and individual locks. The shutters below the drawer shall be supported with soft close clip-on SS Hinges of approved make of required number depending upon the size of the shutter. Each shutter shall be supplied with necessary accessories and hardware such as individual locks, SS handles, magnetic ball catchers, SS tower bolts, individual locks etc. of approved makes screwed and fixed rigidly. Horizontal shelves & vertical planks made out of 19mm thick commercial board shall be provided inside the shutters in such a manner to create optimum number of storage chambers each of equal storage space depending upon the size of the cabinets / credenzas. These partitions shall be finished with 1mm thick white laminate on all faces and exposed side (thickness) edges of the partition members shall be finished with teakwood lipping and 2 coats of melamine polish. <u>Note</u> - For the purpose of contractors bill payment, only front elevation area shall be measured</p>				
<p>3a. Side credenza adjacent to the tables and counters (2'-6" High & 3'-0" Wide OR as mentioned in layout) Same as Sr. No.3 but with 1 no. 6" high drawers at top & shutters below drawer.</p>	8.00	Sq. Ft.		
<p>3b. Low Ht. Storage (2'-6" High) (FOR B.M. Cabin and Cash Cabin only) Same as Sr. No.3 but with 1 no. 6" high drawers at top & shutters below drawer.</p>	25.00	Sq. Ft.		

3c.	Low Ht. Storage (4'-0" High) (FOR space behind staff counters in Branch Hall only) Same as Sr. No.3 but without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights.	60.00	Sq. Ft.		
4 Toughened glass Partitions & doors					
Providing and fixing glazed door and fixed glazing (full/ low height glass partition) with 12 mm thick toughened glass of approved make with all SS patch fittings (Hettich/ Haffele/ Dorma). Item to include floor springs, lock, 300 mm long D- handles and other necessary hardware of Stainless Steel of make Hettich/ Haffele/ Dorma all complete as per the directions of Architect/ Engineer-in-charge.					
4a	Fixed Glazing	165.00	SqFt		
4b	Openable door .	68.00	SqFt		
5 CUSTOMER WRITING DESK.					
Supply and fixing of free standing box type customer writing desk of required length, 42" height and 18" deep. The desk shall be made out of 19mm thick approved block / ply upto the height of 36" and glass bins above (open towards the front for keeping challans) of size 6" X 6" each made up of 10 mm thick plain glass on back & side partitions of the bins affixed firmly to the base and the writing top over the bins shall be made of 12mm thk clear glass, finished with smooth edges and sealed with silicon sealant. The bottom of the desk shall consist of 2 nos. box type cabinets of size - 12" (w) x 24" (h) x 18" (d) made out of 19mm thick approved ply with shutters with a viewing glass pane of appropriate size using 6 8mm plain glass and 20mm horizontal slit at the top of the shutter. The shutter shall be complete with all accessories like lock, SS handles, SS Hinges etc. All the exposed surfaces of the board shall be covered with 1mm thk laminate of approved shades and exposed edges to be finished with teakwood lipping and 2 coats of melamine polish.					
The exterior visible portion of the desk shall be finished with 1.0mm thick approved laminate on visible sides as per bank's colour scheme with matching top band skirting (100mm Canara Bank Yellow Top Band and 100mm bottom skirting of Canara Bank Blue Colour). All inner surfaces shall be finished with approved 0.8mm thk laminate in white shade. Item shall include all required hardware & accessories such as SS clamps, screws, slits etc to ensure that the rigid fixing of the desk members / parts and complete the item upto the satisfaction of the bank / Architect.					
6 LOGO BOARDS FOR COUNTER FRONT ELEVATION					
Supplying and fixing logo boards on the front elevation laminated surface of counters with 5mm thick acrylic sheet of size 18" x 18", attached with SS glass studs (1" or more). Stickers with bank logo (colour and shape as per Bank scheme) in the center to be pasted on the back side of the acrylic sheet neatly without any bubbles. The logo board must be placed on the centre of the front elevation of the counters visible to the customers EXCEPT on the Branch Manager's Table.					
7 GLASS BARRIER					
Providing and fixing glass barrier in the front of clerical / working counters made out of 10mm thick clear float glass with chamfered and polished edges. The glass must be supported at each end of the individual counters either with low ht. partitions or 3"x3" square towers of required height made with 19mm thick approved ply finished with 1mm thick laminate of approved shade on all faces as per the design approved by bank. In case of square towers, the top of the towers should be finished with 1mm thk approved laminate. The glass should be clamped rigidly to the low ht. partition / towers with teakwood beading finished with melamine polish along with necessary hardware / accessories as required. The height of the glass barrier shall be 450 mm (or as directed by the bank). The length of the glass barrier in single piece must be equal to the length of the individual counter. Item shall also include frosting film of aproved make with approved artwork. Film shall be of approved make, self-adhesive with bubblefree installation.					

	There shall be 2 uniform slits, each 100mm high; one at the bottom of the glass barrier just above the counter / Table top & one at the vertical centre of the glass barrier.				
	8 PANELING				
8a	WALL / COLUMN PANELING (Full Ht. - till soffit of false ceiling) (IN ATM Room / Walls in Manager Cabin / Walls in Cash cabin / Independent pillars in branch hall / Side wall adjacent to Officer Table ONLY)	930.00	Sq. Ft.		
	<p>Providing and fixing in position wall panelling in 600 X 600 mm grid (horizontally and vertically) comprising of 25 mm X 50 mm heavy duty GI Box Sections (1.6 mm) with 8 mm thick ply finished with 1 mm thick laminate finish of approved shade and make. The soffits of the doors / windows shall also be covered with paneling as well. Item shall include 100mm high skirting on bottom of the finished floor in Canara Bank Blue shade and a top band of 100mm high from the soffit/ceiling/visible top height of the paneling in Canara Bank Yellow shade. Remaining area shall be finished with 1.0mm thk white laminate of approved make.</p> <p>Note - No paneling shall be provided behind the storage / cabinets / tables sides or any other surface which is not visible (no payment for same shall be entertained by the bank). Entire paneling shall be provided only on visible surfaces as per approved layout or as directed by the Bank. Also, no paneling shall be provided on the columns embedded in walls. The paneling should be provided on independent pillars in the branch hall only that too till soffit of false ceiling.</p>				
	Note:- In case of wall not being true to plumb extra shims of aluminium section shall be provided. Nothing extra shall be payable in this regard.				
	<p>Note:</p> <p>a) In case of false ceiling, area of panelling payable will be below the false ceiling only.</p> <p>b) Measurement of height shall be taken from finished floor only, in case of varying heights on either side of panelling, average height shall be considered.</p> <p>c) Openings/ door/ glass shall not be measured for payment.</p>				
	9 GYPSUM FALSE CEILING (Branch & ATM)				
	<p>Providing and fixing at all height false ceiling and making coves including providing and fixing of framework made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS : 277 and consisting of angle cleats. The perimeter of ceiling fixed to wall/ partition with the help of rawl plugs at 450 mm centre to centre with 25 mm long drive-all screws @ 230 mm interval including jointing and fixing to a flush finish of tapered and square edges of the board with recommended filler, jointing tapes, finisher and one coat of primer suitable for board as per manufactures specification and also including the cost of making openings for light fittings, grills, diffusers, cut-outs made with frame of perimeter channels suitably fixed all complete as per drawing and specification and direction of the Engineer in Charge with: 12.5 mm thick tapered edge gypsum board conforming to IS:2095- Part-I of India Gypsum/ approved make for both framework and the board.</p>	550.00	Sq. Ft.		
	<p>Item to include painting with plastic emulsion paint with 'Velvet Touch' of approved brand and manufacture to give an even shade: Two or more coats on new work with rollers/ spray of make Asian/ Berger/ Dulux paint. Note:- Measurement shall be taken of the plan area only. Suspending system and frame work shall match layout of Electrical/ fire protection wiring/ fixtures etc. Rate to include provision of extra frame work needed due to above and to include necessary scaffolding etc. all complete.</p>				

10	Providing and fixing False Ceiling with Mineral Fibre Acoustic (micro perforated matching with existing) Ceiling Tiles of Armstrong/ USG/ Boral with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 15 mm wide Silhouette type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Ceiling tiles of Dune Premier of size 600 x 600 x 15 mm (thk.) to be placed in the grid. Rate to include making necessary cut-outs or openings for light fixtures, air conditioners and other utilities etc. complete to the satisfaction of Architect/ Bank's Engineer.	286	Sq. Ft.		
11	Providing and applying Birla putty over plastered surface to prepare the surface even and smooth all complete as per the directions of Engineer-in-charge.	100.00	Sq. Ft.		
12	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work with rollers/ spray of make Asian/ Berger/ Dulux paint.	100.00	Sq. Ft.		
13	Painting with synthetic enamel paint on metal of approved brand and manufacture to give an even shade: Two or more coats on new/existing work.	210	Sq. Ft.		
14	VERTICAL BLINDS	150.00	Sq. Ft.		
	Providing & installing flame retardent & water proof 100 mm wide vertical blinds of approved make in combination of three colours matching with the branch ambience (White, blue and yellow or as approved by the Bank). The blinds shall be operatable in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. Item shall be complete along with all the required accessories & hardwares such as pull cords, brackets, threads etc. All metal parts shall be corrosion resistant and rotating parts shall be self lubricating. The fixing of the top rail shall be with special GI brackets at approx 1meter c/c. complete as directed by the Bank.				
15	GLASS SHELVES	15.00	Sq. Ft.		
	Providing and fixing glass panes / shelves of required sizes with all edges neatly grinded, polished and fixed to the wall surfaces using SS D-brackets. The glass shall be 10mm thk plain glass of approved make. Item shall include all required arrangement / hardwares/ accessories to complete the job upto the satisfaction of bank / Architect. <u>Note</u> - For the purpose of contractor's payment, front elevation area shall be measured.				
16	CHEQUE DROP / SUGGESTION BOX (with glass front)	1.00	Nos.		
	Supplying and fixing wall mounted Cheque Drop Box of outer size 10" (D) X 12" (W) X 20" (H) with front openable partly glazed shutter, lock, slot for dropping cheques from top along with all required hardwares & accessories like SS handle, SS butt hinges etc to complete the job upto the satisfaction of the bank / Architect. The box shall be made out of 12mm thk approved plywood finished with 1mm thk approved laminate on outer faces & 0.8mm thk white laminate on all inner faces. The front door shall have 6mm thk glass of size 6"x12" fixed with beach wood beeding. All exposed edges of Plywood shall be fixed with teakwood lipping of appropriate thickness enough to cover the entire exposed edges with 2 coats melamine polish. The box shall be complete with all accessories like SS hinges, SS Handles, Locks etc of approved makes.				
17	NOTICE / PIN-UP BOARD	2.00	Nos.		
	Providing & fixing Notice Board made of tag board of approved make & design of size 4'-0" X 3'-0" with powder coated aluminum border / frame. The board should be 3/4" thk straw board with velvet type fabric covering of Canara Bank blue shade.				
18	ACP WALL PANELLING (FOR outside front walls and outer pillars of ATM only)	210.00	Sq. Ft.		

	Providing & fixing in position ACP (Aluminium Composite Panel) wall panelling having minimum ACP thickness of 3mm and minimum foil thickness of 0.25 mm on both sides with Aluminium framing tube sections of min 1.5" X 1" (20 gauge or down) @ 2'-0" C/C both ways. Panels shall be neatly fixed to the frame with 3M or equivalent adhesive and joints shall be finished with silicon based sealant. ACP shall be of approved make and in Ivory & Canara Bank Blue shade as per bank's approval. Item shall include proving & fixing additional sections as required for fixing Indoor AC units, proper access panel for ATM power point, proper locking arrangement for plug point by providing additional framing etc complete. <u>Note</u> - For the purpose of payment, the measurements shall be taken up to the visible height / false ceiling level only.				
19	ACP PARTITION (FOR TOILET PARTITION)	175.00	Sq. Ft.		
	Providing & fixing in position ACP (Aluminium Composite Panel) partition having minimum ACP thickness of 3 mm (on both side of partition) and minimum foil thickness of 0.25 mm on both sides with Aluminium framing tube sections of min 2" X 2" (20 gauge or down) @ 2'-0" C/C both ways. Panels shall be neatly fixed to the frame with 3M or equivalent adhesive and joints shall be finished with silicon based sealant. ACP shall be of approved make and in Ivory & Canara Bank Blue shade as per bank's approval. Item shall include proving & fixing additional sections as required for fixing Indoor AC units, proper access panel for ATM power point, proper locking arrangement for plug point by providing additional framing etc complete. <u>Note</u> - For the purpose of payment, the measurements shall be taken up to the visible height / false ceiling level only.				
20	BOXING FOR ROLLING SHUTTER	40.00	Sq. Ft.		
	Providing and fixing rolling shutter panelling / enclosure of required size as per description at Sr. No.9. The rate shall inclusive of necessary hardware fittings like hinges, screws, tower bolts sealant, trap door, locking arrangement etc complete.				
21	FIXING THE DANGLERS	175.00	Sq. inch		
	Providing & Fixing Danglers as directed by the Bank Staff / Architect on the either hanging through ceiling or placing on front of counters on glass partition etc. complete in all respect with-out spoiling the décor				
22	ONE WAY FILM OVER GLASS	150.00	Sq. Ft.		
	Providing and fixing One Way film as directed by Bank/ Architect over Glass to proper level, with out air bubbles / cuts / folds etc. complete.				
GRAND TOTAL (Rs.)					