







<div> <div> কানাড়া বেঙ্ক <small>काबत छकावत एटि संस्था</small> </div> <div> केनरा बैंक <small>गावत सवकाव का उणक्रम</small> </div> <div> Canara Bank <small>A Government of India Undertaking</small> </div> <div>  </div> </div> <div> ॥ डिजिटल सिंडिकेट Syndicate ॥ </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	CARPENTRY IN LAMINATE				
	GENERAL NOTES FOR CARPENTRY WORKS				
	1. All Plywood and Block board to be used in Carpentry works should strictly be of Century/ Green/ Duro ply/ Kitply/ Archid ply only				
	2. All Plywood/ Block Board used to be of commercial grade but of above make only				
	3. All laminates should strictly be 1.0mm thk of Century/Greenlam or Merino make				
A	TABLE , DESKS , DRAWERS AND STORAGES				
	ALL TABLES / WORK STATIONS SHOULD HAVE KEYBOARD TRAY, CPU TROLLEY(METAL), FOOT REST AND RATES SHOULD BE QUOTED ACCORDINGLY WITHOUT ANY EXTRA CLAIM				
i	Front Office/ Clerical Counter:	RFT	32.00		
	Providing and fixing in position Front Office Counter 2'-6" wide as per drawing comprising of the following complete in all respects:-				
	i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1½"x1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine finish.				
	ii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
	iii) Vertical drop box (horizontal band) of size 12" ht x 10" thickness (hollow inside) shall be provided suspended from the ceiling lvl on the facia above the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light,				
	iv) Glazed partition above working top (ON FRONT AND SIDES) dividing each work station to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.				
	v) vertical supports made with 18 mm thick plywood finished with white enamel paint.				
	vi) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.				
	vii) Footrest made with T.W. member of size 4"x1 ½ " finished with french polish.				
	viii) 3-Drawer units as per drawing shall be provided with multipurpose Godrej locks in				
	Each drawer. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.				
	ix) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.				
	The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided				
	The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
ii	Same as above but of 600mm wide without Front Glass	RFT	8.00		
iii	CASH COUNTER & SINGLE WINDOW COUNTER TABLE (EXCLUDING SIDE & REAR PARTITION)	RFT	5.00		
	Providing and fixing teller counter as shown in the drwng. It shall consist of 18/19 mm thk comm. ply. counter top & laminate finished ledge at 3' 6" height from FFL. The counter shall consists of 18/19mm thk. Comm. ply table top of size as per design as mentioned in the detailed drawings of Cash Counter and finished with 1.0mm thk laminate (suede finish) of approved shade and make in approved pattern. It shall be supported on 18/19mm thk. Comm. Ply verticals on either sides and finished with 1.0 mm thk laminate of approved shade and make. The counter shall be provided with a front apron made with 18/19mm thk commercial ply and finished with 1.0 mm thk laminate of approved shade and make. 18/19mm thk plywood ledge 1'6" wide finished with approved shade of laminate along with edge moulded on both sides & 6" wide protruding (edge moulded) shall be provided at 3'-6" from FFL. The front portion shall be provided with 12 mm thick clear toughened glass with machined polished edges fixed from the top of the ledge to 7'-0"- 8'-0" height and fixed on the sides with 4 1/2" gap at the bottom for teller supported on the sides by D clips.				


<div> <div> कानाडा बैंक <small>काबत हककाबत एटि संस्था</small> </div> <div> केनरा बैंक <small>गावत सवकाब का उणक्रम</small> </div> <div> Canara Bank <small>A Government of India Undertaking</small> </div> <div>  </div> </div> <div> ॥ डिजिटल सिंडिकेट Syndicate ॥ </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	1no. Computer key board tray (either ready made / made to the order as per architects design using 18/19 mm thk comm ply base and 1" x 2" round edged moulding on the front fixed with telescopic sliders(approved make), 1 no. 18/19 mm thk. Comm. ply for Shelf below the table shall be provided for the CPU, 2 / 3 nos. (equal sized) Drawer units shall be provided as shown in drgs. Drawer shall consist of 12mm thk. Comm. Ply, sides, back & base, facia of drawers shall be of 18/19 mm thk. Comm. Ply finished in 1 mm laminate with steam beach wooden moulding on edges of drawer units.. Each drawer shall slide on a pair of approved make telescopic drawer sliders, provision to accommodate currency notes of different denominations shall be provided on the top drawer unit, which should be finished with 1mm thick laminate. A 19mm x 7mm steam beach wooden moulding with mellamine shall be provided to the edge of the table. All the exposed surfaces shall be finished with 1mm laminate all inner surfaces excluding drawers to be finished with frenchpolish and inside of the drawers with melamine finish. A 12mm thick soft board of good density to be mounted over 12mm thick comm.ply below the customer top and in between space of staff counter. The soft board to be covered with plain fabric teal green colour (approx. cost Rs.250/mtrs) from front and edges.				
	Rate shall be inclusive of <u>12mm thk toughened glass</u> and all necessary approved fittings like locks, handle, D-clips, telescopic channel, magnet etc. all complete				
	NOTE- Side & rear partition shall be paid extra as per actual measurement at site				
	The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the Vertical drop and also in the 12"x10" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing/ as directed.				
	The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
iv	Manager's Table of size 6'-0"(L) x 2'-6"(W) x 2'-6"(H) with 8mm thk clear Glass (all edges mirror polished) on Top	NOS	1.00		
	Providing and making Manager Table in laminate finish of size 6'-0" X 2'-6". It shall consist of 3/4" thk plywood top as per design(double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES) supported on 3/4" thk plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
v	Officer's Table of size 5'-0"(L) x 2'-6"(W) x 2'-6"(H)	NOS	4.00		
	Providing and making Officer's Table in laminate finish of size 5'-0" X 2'-6". It shall consist of 3/4" thk plywood top as per design(double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES) supported on 3/4" thk plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
vi	MAY I HELP YOU- TABLE	NOS	1.00		
	Providing and laying a Plain Table for Security Gurd with a Pencil Drawers for over all size of top as mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
vii	Side Cadenza of size 1'-6"(W) x 3'-6"(L) x 2'-6" (H) (FOR MANAGER)	NOS	1.00		

<div> <div> কানাড়া বেঙ্ক <small>कावाड बँक</small> </div> <div> केनरा बैंक <small>कावड बँक</small> </div> <div> Canara Bank <small>A Government of India Undertaking</small> </div> <div>  </div> </div> <div> চিভিকিট সিণ্ডিকেট <small>Syndicate</small> </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit (C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
viii	Side Cadenza of size 1'-6"(W) x 3'-0"(L) x 2'-6" (H) (FOR OFFICERS)	NOS	4.00		
	Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit (C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
viii	LOW HT RUNNING STORAGE(1'-6"DX2'-6"HT) (BACK CADENZA)	SFT	122.00		
	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make . Note- The Height of the running stoarge should be 2'-6" and should comprise of a 6" high drawe and shutters below. No shelves should be provided inside the shutters				
ix	OVER HEAD STORAGE	SFT	42.00		
	Providng and fixing over-head storages which consists of 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & t.w lipping matching with approved laminate on all the edges. They shall consist of 3/4" thk plywood top , sides and bottom and 1/4" thk marine plywood back. A 3/4" thk ply wood palmet shall be provided below the storage to house the tube light. All the external surfaces shall be finished with 1.0mm thk laminate of approved shade. Divisions of shutter shall be made equally in accordance to the length of the storage. All internal surfaces shall be finished with french polish including the shutter. Rate shall be inclusive of all necessary hardware fittings of approved make like- hinges, locks, towerbolts, handles etc.Note- the pelmet for tubelights will not be considered as separte item on in the measurement				
x	FULL HT. STORAGE	SFT	328.00		

<div> <div> কানাড়া বেঙ্ক <small>काबल डककाबल अडल सङ्गठन</small> </div> <div> केनरा बैंक <small>काबल डककाबल का डककाबल</small> </div> <div> Canara Bank <small>A Government of India Undertaking</small> </div> <div>  </div> </div> <div> ॥ डिजिटल सिंडिकेट ॥ Syndicate </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.comm. ply top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type hinges of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages (as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval (approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.				
B	PANELLING				
1	PANELLING ON WALLS/ COLUMNS IN LAMINATE FINISH				
	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consists of aluminium sections 50mm x 38mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 18/19mm thk commercial grade plywood and finished with 1.0mm thk laminate or left naked as per the direction of the EIC/architect. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required.				
a	In 12 mm plywood finish in laminate for sealing of window	SFT	24		
b	In Laminate Finish over Ply	SFT	712		
2	PANNELLING WITH LECQUERED GLASS OF APPROVED SHADE	SFT	112.00		
	Providing and fixing of paneling with or without frame so as to receive a plain and even surface in exact plumb line , covered with 9mm thick commel ply and finished with 8/9mm thick TEMPERED LECQUERED GLASS of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of siver metal laminate as and where required and as per the direction of the Consultant Architect/ Engineer.				
C	PARTITIONS				
	(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca/ rcc ceiling/slab but the area of partition payable will be below the false ceiling only).				
1	Full Height Solid Partition B/S Laminate	SFT	202.00		
	Providing & fixing in position solid Full Height Partition in frame work in 2'x 2' grid (horizontally and vertically) comprising of 2"x 2" T.W. Section with 8 mm thick plywood on both sides finished with 1 mm thick laminates of approved make and colour as shown in drawing. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
2	FULL HEIGHT PARTLY GLAZED PARTITION	SFT	138.00		
	Providing and fixing full ht. partly glazed partition at places as mentioned in the drawing and as directed by the Architect/ EIC. The partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures.The framing shall be fixed with 8/9 mm thk. commercial grade plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine Polish.				
5	FULLY GLAZED PARTITION WITH TOUGHENED GLASS(In Manager cabin Front , Self Service Area & Front Glazing)	SFT	158.00		
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.Rate shall be inclusive of frosted film and bank logo to be fixed over the glass surface as per deign and as directed by the architect				
6	SEMI HEIGHT SOLID/ SEMI GLAZED PARTITION FOR CASH CABIN , SINGLE WINDOW COUNTER AND OTHER AREAS	SFT	352.00		

<div> <div> কানাড়া বেঙ্ক <small>काबत छकाबत एटि संछ्छा</small> </div> <div> केनरा बैंक <small>गाबत संकाब का उछक्रण</small> </div> <div> Canara Bank <small>A Government of India Undertaking</small> </div> <div>  </div> </div> <div> सिंडिकेट सिंडिकेट Syndicate </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	Providing and fixing in position Semi Height Semi Glazed/ solid Partition at places as indicated in the drawing in Aluminium frame work in 2'x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 1.8mm thk Aluminium Section , fixed with 8/9 mm thk plywood on both sides and then finished with 1.0 mm thick laminate of approved shade and make in approved pattern. Item to include 8/10 mm thick itched glass or clear glass with frosted film of approved pattern. All edges should be fixed with T.W beading and should be finished in melamine polish of matching laminate colour as directed including wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
7	FULL HEIGHT SOLID PARTITION FINISHED WITH ONE SIDE LAMINATE OVER PLY AND OTHER SIDE WITH A.C BOARD FINISHED WITH POP & PAINT INCLUDING DOOR (Having Fire Rating of 3Hours for UPS Room)	SFT	210.00		
	Providing & fixing in position Partition in Aluminium frame work in 2'x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 1.8mm thk Aluminium Section covered with with 8/10 mm thick Aesbestos Sheet and finished with POP and paint on one side and the other sides to be finished with 8/9mm thk Plywood and finished with approved shade of laminate. It shall also consist of a Flush door of required size and fixed with aesbestos Sheet on one side and laminate on other sides with the same specifications as mentioned in the above line. Rates shall be inclusive of all hardware fittings and fixtures such as - hinges, handles, locks, door closer, door stopper etc. all complete				
D	DOORS				
a	SOLID DOORS- IN LAMINATE FINISH (BOTH SIDE LAMINATE)				
	Providing and fixing solid doors of sizes as shown in the drawing.The door shutter shall consist of 3 nos 2" x1" C.P teak wood styles and 3 nos 3" x 1" C.P teak wood bottom, middle and top rails. The wooden framing will be covered with 1/4" thk plywood on both sides. A door frame of size 3"x1 1/2" t.w section finished with mellamine polish shall be provided. Rates shall be inclusive of approved locking system(Godrejmake- Ultra mortise dead lock), door stopper, a pair of handles, tower bolts etc and misc. hardware items of approved make				
i	2'-6"-0"x7'-0"-IN LAMINATE FINISH (WITH 1 1/2X4" WOODEN FRAME)	NOS	2.00		
b	PARTLY GLAZED DOOR				
	Specification same as above except for 8mm thk Modi Guard clear float glass shall be provided at 4'-0" from floor lvi The door shall be finished in 1.0 mm thk laminate on both sides				
I	PARTLY GLAZED DOORS AT MANAGER CABIN, AND OTHER AREAS	NOS			
II	AT ENTRANCE TO SINGLE WINDOW COUNTER , PASSING OFFICER & CASH COUNTER PASSAGE	NOS	1.00		
III	2'-6" X 6'-0" TELLER COUNTER & SW COUNTER DOOR WITH NIGHT LATCH	NOS	1.00		
IV	4'-0" high Wicked Door as per design	NOS	3.00		
c	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)- AT ENTRANCE & BM'S CABIN	SFT	46.00		
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to acCommercial gradeodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)				
E	FALSE CEILING AND POP WORKS				
1	GYPSUM BOARD CEILING	SFT	1150.00		

<div> <div> <div>কানাড়া বেঙ্ক</div> <div>काबल ढकाबल अडल सलङ्गल</div> </div> <div> <div>केनरा बैंक</div> <div>गाबल सलकाब का उलङ्गल</div> </div> <div> <div>Canara Bank</div> <div>A Government of India Undertaking</div> </div> <div>  </div> </div> <div> <div>॥ ढलङ्कलकल सलङ्कलकल Syndicate ॥</div> </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	<p>Providing and fixing 1/2" thk Gypsum India Board false ceiling at levels as shown in the drg. From the FFL. Rate shall be inclusive of all Gypsum India Components contained G.I perimeter channels of size 0.55 thk having one flange of 20mm and another flange of 30mm and a web of 27mm along the perimeter of the ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centres. The suspending G.I intermediate channels of size 45mm, 0.9mm thk with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angles of width 25mm x 10mm x 0.55mm thk fixed to soffit with G.I cleat and steel expansion fastener at every 610mm c/c. Ceiling sections of 0.55mm thk having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in directions perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment. The board are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & jointing paper tape. Rate shall be inclusive of any vertical ceiling part, cutouts for spot and tube lights, a.c grills, fire and security system cutouts. All Sections should adhere to the manufacturer's guidelines .</p>				
	<p>Note- Rates shall be inclusive of The drop/band of 6"-12" between the Gypsum-Gypsum (Higher-Lower levels) and Armstrong-Gypsum (Higher-Lower levels). No extra can be claimed for the same. Amount will be paid as per the measurement of the horizontal surfaces of Gypsum and Armstrong and nothing will be paid for vertical surface / band/ drop as it is all inclusive in the Rate</p>				
2	MODULAR FALSE CEILING- ARMSTRONG make	SFT	1260.00		
	<p>Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm grid sections) false ceiling of size 24" X24" AT LEVELS AS SHOWN IN THE DRG. FROM THE FFL. Rates shall be inclusive of providing the total system with installation etc. The contractor has to maintain all ceiling tiles in good order and replace the defective tiles (at his own cost) before the handing over of the site.</p>				
	<p>Note- Rates shall be inclusive of The drop/band of 6"-12" between the gypsum(at lower level) and Armstrong(at heigher level). No extra can be claimed for the same. Amount will be paid as per the measurement of the horizontal surfaces of Gypsum and Armstrong and nothing will be paid for vertical surface / band/ drop as it is all inclusive. Rate</p>				
F	PAINTING				
1	LUSTRE PAINT WITH POP PUNNING ON GYPSUM FALSE CEILING	SFT	1280.00		
	<p>Providing & applying Luster Paint on walls, columns & ceilings over pop punning. The rate shall include scrapping, levelling & preparing the surface. with pop , jointing compound and Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.</p>				
2	DISTEMPER PAINTS FOR WALLS (TOILETS, STORE, UPS AND STRONG ROOM)	SFT	4800.00		
	<p>Providing and applying Distemper paint on walls , columns & ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 3 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided.Note- Rates shall also include - filling up the cracks in the wall & ceilings, making good surface .</p>				
3	WALL PUTTY/ POP PUNNING (ON BANKING HALL WALLS AND GYPSUM CEILING ONLY)	SFT	380		
	<p>Providing and applying POP Punning on walls and columns (average 6mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the windows and door frames. If the average thickness is found to be 4mm or less than POP will be considered as a putti finish and the rate shall be 50% of the quoted rate</p>				
	<p>If Wall Putty is provided on RCC ceiling/ Slab and other area than banking hall, then the same shall not be payable</p>				
4	PLASTIC EMULSION PAINT (ON BANKING HALL WALLS ONLY)	SFT	380		
	<p>Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.</p>				
5					
G	MISC. ITEMS				
1	VERTICAL BLINDS	SFT	242.00		
	<p>Supplying and Fixing VERTICAL BLINDS Vista/Mac/Parytex make. Blinds made using 100% polyester with acrylic polymer coating, of the shade and colour as approved by the Architect/ Bank ffficial(only for external windows. In case of front facia necessary approval need to be obtained)</p>				
2	PIN UP BOARD	SFT	24.00		

<div> <div> কানাড়া বেঙ্ক <small>कावाड बँक</small> </div> <div> केनरा बैंक <small>कावरा बँक</small> </div> <div> Canara Bank <small>A Government of India Undertaking</small> </div> <div>  </div> </div> <div> ॥ डिजिटल सिंडিকেट Syndicate ॥ </div>					
BOQ FOR FURNISHING WORKS AT CANARA BANK SIVASAGAR BRANCH ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	Providing and fixing Pin-Up board of sizes as mentioned in the drawing in 1/2" thk soft board of good density to be mounted over 12mm thk ply and fixed to partition/ walls or at places as directed by the architect. The soft board shall be covered with valver cloth of approved shade and make (BASIC RATE RS. 200 /R.MTS.) .				
3	SHUTTER BOXING	SFT	38.00		
	Providing and Fixing Shutter Boxing with 19mm thk Marine Ply and Finished with Approved Shade of laminate> The boxing of shutter should be made openable type for periodic maintainance. <u>Note the mode of measurement would be the multiplication of the length and the height of the boxing</u>				
4	NOTICE BOARD	SFT	12.00		
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
5	SIDE/CORNER/CENTRE TABLE				
	Providing and making corner/ side/ centre table of below mentioned sizes as per drawing. Table top shall consist of 12mm thk glass with chamfered edge with approved quality of itching. The base shall be made up of CP TEAK WOOD frame/ 3/4" plywood or as directed by the architect. All exposed faces shall be finished with natural polish(if wood frames are used) or with 1.0mm thk laminate of approved shade for ply. All inner surfaces should be finished with natural french polish				
a	CORNER TABLE(1'-6" X 1'-6 X 1'-6HT)	NOS	4.00		
b	CENTRE TABLE(1'-6" X 2'-6 X 1'-6HT)	NOS	2.00		
6	WRITING LEDGE	NOS	4.00		
	Providing and fixing Wall Mounted Writing Ledge Of Size 4'-0" x 1'-3" x 1"(H), made out of 19mm thk Plywood of approved make and finished with 1mm Thk approved shade of laminate. This ledge should have 4 nos of Pockets made along 4' length with the Supporting wall as base with 3" clear space to house withdraws/deposit etc slips. All inner surfaces of the Ledge should also be laminated. A 12mm thk Clear Glass, Mirror polished on all sides of size 4'-0" x 1'-3" shall be fixed with 4 nos 1-1/2" dia and 4" High S. S Studs should be fixed on the Top portion of the ledge.				
7	COMPLAIN BOX & SUGGESTION BOX	NOS	1.00		
	Supplying and erecting free-standing complain box of overall size 300 mm long x 200 mm deep x 450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete with hardware fittings and fixtures of approved make and quality.Top and all exposed surfaces of block board are to be finished with 1.00 mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.				
8	CHEQUE DROP BOX	NOS	1.00		
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.P teak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved designand quality.				
9	10MM GLASS SHELVES- 250-300MM WIDE	RFT	18		
	Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass selves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ pannelling, at an interval of 24-30" as per design and as directed by the achitect				
10	DRY PLANTER BOX WITH POT & PLANTS (WITHOUT FLOWER POT)	NOS	0		
	Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18 mm thk. sandwiched plywood - sides finished in both inner and outer surfaces with 1.0mm thk laminate of approved shade and all exposed side edges of Ply/ board shall be covered with teak wood beading finished with matching Deco paint to give it similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with artificial/ natural plants as per architect's choice.				
11	COLOURED ACRYLIC SHEET LOGO FO THE BANK, BACK LIT (600 X 600)	NOS	2.00		

[illegible]