

BOQ FOR FURNISHING WORK OF CANARA					
BANK BRANCH AT BILASPUR, DISTT. YAMUNANAGAR (HR.)					
FURNISHING WORK					
S. No.	Description	Quantity	Unit	Rate	Amount
1	FALSE CEILING (Including ATM Ceiling)			(Rs.)	(Rs.)
a	Providing and fixing GYPSUM BOARD FALSE CEILING in levels as per the detailed drawing - made up of G.I frames as specified by Gypsum India/Saint -Gobain Gyproc/Armstrong and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India/ Saint Gobain/Armstrong/Gyproc Spacing of intermediate channels shall be at 1200 mm c/c, and ceiling section at 457 mm c/c the work includes taping and jointing, applying primer, two or more coats of plastic emulsion paint of approved shade ICI/ASHIAN PAINTS make, making cut-out for light fixtures, etc. The Final court shall be done with FOAM ROLLER, and no brush marks should be visible. Providing of perimeter channels/ beading etc. as per drawing complete in all respects.(All measurement in sqft only)	750	SFT		
b	ARMSTRONG (DUNE)/DEXUNE (STAR ELITE) RH-99 /GRID FALSE CEILING				
	Providing and fixing of false ceilings at all heights of 600 mm x 600 mm ARMSTRONG (DUNE)/DEXUNE (STAR ELITE) Mineral Fibre ceiling tiles of Beveled Tegular Edge RH-99 laid on Armstrong/Dexune 15mm exposed powder coated silhoutte grid system. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tee.	470	SFT		
2	PARTITIONS				
a1	Low height Partition				
	Providing & fixing of LOW HEIGHT PARTITION (HT. 4'-6") made of 1.75" x 1.75" X 16 gauge aluminum extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level with rawl plugs/ steel lugs / screw. The frame work to be clad with 9mm thk MDF board exterior grade of CENTURY/ GREEN Make on both faces finished with 1mm thick high gloss laminate of of CENTURY/ AMULYA/ GREENLAM Make of approved shade. Till the height of 3'-3" and 1'-3"(12mm thk.) glass with etching of MODI/ SAINT GOBAIN/ASAHI on top complete with teak beading, The spirit polishing of teak sections of approved shade as per drawing Complete in all respects to the complete satisfaction of the Architect.	100	SFT		
a2	Full height Partition				
	Providing & fixing of FULL HEIGHT PARTITION (HT. 9'-0") partly glazed, made of 1.75" x 1.75" x 16 gauge Aluminium extruded sections at 18" c/c both ways. The bottom member shall be aluminium extruded sections of size 65mm X 44mm X 16 gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs/ steel lugs / screw. The frame work to be clad with 9mm thk MDF board exterior grade of CENTURY/ GREEN Make on both faces finished with 1mm thick high gloss laminate of of CENTURY/ AMULYA/ GREENLAM Make of approved shade and minimum 8 mm thick glass of MODI/SAINT- GOBAIN/ASAHI with etching as required on the glazed portion. The work includes spirit polishing of shade on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. Including doors but excluding cost of door closers, mortise locks. Door closer should be made of GODREJ/OZONE & mortise lock of GODREJ. The job also includes removing of existing partition and dumping the malba at authorized malba dumping ground.	500	SFT		
a3	UPS Room Partition				
	Providing & fixing of UPS Room PARTITION (HT. 7'-6") made of 1.75" x 1.75" X 16 gauge aluminum extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level with rawl plugs/ steel lugs / screw. The frame work to be clad with 8mm thk Bison Board on both sides finished with 1mm thick laminate of of CENTURY/ SUNMICA/ GREENLAM Make of approved shade on outer face and enamel paint on inner face complete in all respects to the complete satisfaction of the Architect. Including doors but excluding cost of door closers, mortise locks. Door closer should be of GODREJ/OZONE & mortise lock of GODREJ The spirit polishing teak sections of approved shade as per drawing	90	SFT		

a4	12mm Thick TOUGHENED GLASS Fixed Partitions Including Doors With Etching Upto 9'-0" Ht.				
	Providing and fixing in position 12mm clear float toughened Glass partition including Doors with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same.				
	The cost to include all hardware (PATCH FITTINGS etc) required of Hettich /Godrej/Dorma or approved equivalent make floor spring with its accessories, top pivot, center lock, 450mm glass door handles etc., and single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge, along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed.	270	SFT		
	The cost to include the cost of bevelling and smoothing of the exposed edges of the glass.				
b	CASH CABIN PARTITION				
	Providing & fixing of CASH CABIN PARTITION (HT. 7'-3") (partly glazed (6 mm glass of Modi/Saint-Gobain/Asahi) as per design), made of 1.75" x 1.75" Aluminium extruded sections at 18" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65mm X 44 mm X 16 Guage. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs/ steel lugs / screw. The frame work to be clad with 9mm thk MDF board exterior grade of CENTURY/ GREEN Make on both faces finished with 1mm thick high gloss laminate of of CENTURY/ AMULYA/ GREENLAM Make of approved shade. The work includes providing a 6" x 9" voucher cut out with tray, spirit polishing of shade on woodwork and steam beach beading etc. Including doors but excluding cost of door closers mortise locks, door closer. Complete in all respects to the complete satisfaction of the Architect./bank.	60	SFT		
c	Cash Cabin front Partition With 12 mm thick Toughened Glass including fixing. Complete in all respect.	25	SFT		
d	Providing and fixing 1.5 feet high 12 mm Glass on counters adjacent to Cash cabin and other counters complete as per drawing including glass support. Glass has to fixed as vertical partition in the front end of the counter (towards customer side) to restrict direct access of customer	50	SFT		
e	Night Latch for Cash cabin door (Make Godrej)	1	NOS		
f	Mortise locks (with handles).(Make Godrej)	7	NOS		
g	Hydraulic Door closer.(Make Godrej/Universal)	4	NOS		
h	Floor springs.for main entrance door.(make Godrej , Universal, Ozone)	3	NOS		
3	ENTRANCE DOOR				
a	MAIN ENTRANCE DOOR WITH LOGO :- 4'-0"x7'-0"(All aluminium sections powder-coated).glass for doors: 12mm thick Toughened Glass with etching of logo & Aluminium sections(Hindalco/Jindal) for door shutter :3 1/4"x1 3/4" x 2mm thick, bottom member 4 1/2" x 1 3/4" x 2mm & 18" SS handle, lock & Tower bolts etc. complete in all respects including powder coating. (Make : Hindalco/ Jindal). Quoted rates shall include fixing of floor spring also.	0	SFT		
b	ATM MAIN ENTRANCE DOOR WITH LOGO :- 3'-0"x7'-0"(All aluminium sections powder-coated).glass for doors: 6 mm thick glass with etching of logo & Aluminium sections JINDAL /HINDALCO for door shutter :vertical member83.5mm x45mm 2mm thick, Top and bottom member 85-100mmx45mmx2mm thick, Middle member Approx. 83.5mm to 100mmx45mmx2mm. 18" SS handle, Lock & Tower bolts etc. complete in all respects including powder coating. Rate should be inclusive of making arrangements for fixing entrance access lock with suitable aluminium box section adjoining the main door and Floor springs.for main entrance door.(make Godrej , OZONE, Sandhu)	0	SFT		
c	FIXED GLAZING (BRANCH+ATM)				
	Providing and fixing external FIXED GLAZING comprising of 6 mm thick glass of MODI, SAINT GOBAIN, ASAHI Make with top, bottom and vertical frames comprising of powder coated (shade as approved) Aluminium members of approved shade approximate 4" x 1 3/4" x 2mm thick. top, bottom & vertical member with clip sections as per specifications and drawings to complete satisfaction of the Architect. Vertical member towards door side should have 100mm width so that Access lock should be provided easily.(MAKE HINDALCO, JINDAL)	0	SFT		
4	COUNTERS AND TABLES				

	a	Providing and fixing MANAGER'S TABLE with 10mm beveled glass with hole for wires of approved make to be fitted on top obtain the total <i>height of 2'-6" as per detailed drawing, made up of 19mm Ply of CENTURY/ GREEN approved Make and finished with 1 mm thick high gloss laminate of make, and shade as approved, as per detailed drawing.</i> Table (with one side drawer unit and another side drawer unit) shall be provided with drawers sliding on telescopic channels (Ebco/hetich make) and one cabinet with proper locking arrangements and keyboard with telescopic channels (Ebco/hetich make) . Tabletop shall be finished with 1.0mm thick laminate of approved shade & quality. The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, spirit polishing of steam beach/ white cedar beading etc. and The inner exposed surfaces of table, side drawer unit, etc to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank.				
		Table size: 6'-0" x 3'- 0" x 2'-6" (Must be kept loose without fixing to the wall)	1	NOS		
	b	SIDE CREDENZAS (Must be made loose without fixing to wall/partition.) :				
		Providing and fixing SIDE CREDENZAS including Manager Cabin of size 3' to 4'0" x 1'3" x 2'6" made of 19mm Ply of CENTURY/ GREEN Make finished with 1 mm thick high gloss laminate of approved Make and shade on top , back, sides and front having two drawers and cabinet below complete with all accessories like locks, handles, magnetic catcher etc. Teak wood beading on all exposed edges with spirit polish. (Should not be attached with partitions). The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/ Bank.	4	NOS		
	c	CASH COUNTER				
		Providing and fixing of CASH COUNTER with granite table top 2'-6"/3'-9" high made up of 19mm Ply of CENTURY/ GREEN PLY Make and finished with 1 mm thick high gloss laminate of CENTURY/ AMULYA/ GREENLAM Make, shade as approved and as per detailed drawing. 2'-6' wide working table top, key board tray, drawer with telescopic channels (Ebco make)(TOP DRAWER SHOULD BE DIVIDED INTO SECTIONS SO AS TO PILE DIFFERENT CURRENCY NOTES SEPERATELY) and cupboard. <i>All exposed surfaces (such as counter front, sides, drawers and cupboard etc) to be finished with 1mm thick laminate of approved make.</i> Tabletop shall be finished with 1mm thick laminate .The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank. The work includes fixing of furniture locks, wire managers, spirit polish of steam beach wood beading/ lipping etc. complete in all respects to the entire satisfaction of Architect. Transaction top should be minimum 18"	5	RFT		
	d	WORK STATIONS TABLE				
		Providing and fixing of COMPUTER work Stations as per layout plan and and 10mm beveled glass with hole for wires of approved make to be fitted on top obtain the total height of 2'-6" high working top (As per drawing) made up of 19mm Ply of CENTURY/ GREEN Make, finished with 1 mm thick high gloss laminate of CENTURY/ AMULYA/ GREENLAM Make, shade as approved as per the detailed drawing . The tables shall have 2'-6" X 4'-0" and 2'-6" x 5'-0" table top as per approved shade and color.	5	NOS		
		<i>All exposed surfaces (such as counter front, sides, drawers and cupboard etc) must be finished with 1mm thick laminate of approved make. Tabletop shall be finished with 1mm thick laminate. The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank.</i> Each unit of table shall be provided with keyboard tray with telescopic channels(EBCO). Tabletop shall be finished with 1.0mm laminate of approved shade & quality. The work includes fixing of wire managers, locks, footrests, spirit polishing the steam beach beading, lipping, exposed frame, etc. as per drawings, and The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank.				
5		MISCELLANEOUS FURNITURE				
	a	STORAGE CABINETS WITH LOCKS, HANDLE (Must be kept loose without fixing to wall/Partition; each storage must be made as independent unit and all the side (back, side, front & top side) of the storage also to be finished with mica and 19mm Ply				

		Providing & fixing STORAGE CABINETS of feet long 2'-6" ht and 1'-4" deep as per layout plan made up of 19mm Ply of CENTURY/ GREEN Make and finished with 1mm thick high gloss laminate of CENTURY/ AMULYA/ GREENLAM Make, shade as approved and per detailed drawing . With BOX SIZE OF 2.5 FEET WITH shelves made up of 19mm thick commercial board, each drawer(with lock) & cabinet(with lock) 19mm thickness portion every place must be finished with proper liping/ margin finish. The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank. The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc complete in all respects to the complete satisfaction of the Architect.	35	RFT		
	a1	Providing & fixing STORAGE CABINETS of feet long 9'-0" ht and 1'-4" deep as per layout plan made up of 19mm Ply of CENTURY/ GREEN Make and finished with 1mm thick high gloss laminate of CENTURY/ AMULYA/ GREENLAM Make, shade as approved and per detailed drawing . With BOX SIZE OF FEET WITH shelves made up of 19mm thick commercial board, & cabinet(with lock) 19mm thickness portion every place must be finished with proper liping/ margin finish. The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank. The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc complete in all respects to the complete satisfaction of the Architect.	150	SFT		
	b	VOUCHER STAND (4'Lx1'6W"x3'9"h)				
		Providing and fixing VOUCHER STAND (4'Length x3'9"height portion must be made of CENTURY/AMULYA/GREEN/ECOTEC complete of 19mm ply without cut/ joint and all side finished with 1.0 mm thk high gloss laminate), including separately make lockable Clearing & separately make Suggestion Box, writing top at 3'9" height with space for vouchers and 4x3' Notice Board-as per	1	NOS		
		specifications laid down in the detailed drawing and as per Bank specifications. Below Writing top 8"(h)x7"(L) voucher boxes of equal size 6 to 7 nos & one open self (9"below the voucher box) at 28" height must be provided. Clearing & suggestion box must be prepared loose of size 20"Hx13"Lx9"wide(each) and should be fitted below the self in 28" space. Clearing & suggestion box top from where cheque/suggestion to be dropped cut out portion must be oval shaped instead of flat shape & front portion of the box should be provided with glass for transparent inside/out side vision of the box.The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank.				
	c	Roller Blinds Providing and fixing Roller blinds (Trac / vista / Mac make of approved colours (50mm / 89 mm width) complete in all respects for manager's cabin glazing and front side windows. (basic rate of fabric shall not be less than Rs 90/- per mtr.)of roller blinds with necessary accessories like channel,string ,control unit ,fabric etc complete	0	SFT		
	d	Providing & fixing ELECTRICAL PANEL BOXING of 9'-0" ht and depth as per size of the electrical panel, layout plan made up of 19mm Ply of CENTURY/ GREEN Make and finished with 1mm thick high gloss laminate of CENTURY/ AMULYA/ GREENLAM Make, shade as approved , The inner exposed surfaces to be finished with 0.8mm thick laminate of white shade complete in all respects to the entire satisfaction of the Architect/Bank. A fix glass window should also be given to show the indicator LEDS of the panel inside. The work also includes supplying, fixing of hinges, magnetic catchers, handles, Steam Beach lipping, Ventilator Grill etc complete in all respects to the complete satisfaction of the Architect.	1	NOS		
	e	COLUMN/WALL PANELLING				
		Providing and fixing of COLUMN/ WALL PANELLING (4'-0"/ 9'-0" Ht.) as per design, consisting of 9mm thick MDF board exterior grade CENTURY/ GREEN Make fixed on wall with Aluminium framing at 2'-0" C/c both ways. The above shall be laminated with 1mm thick high gloss laminate CENTURY/ MERINO/ GREENLAM Make, The work includes sprit polishing of wood beading, complete in all respects as per detailed drawings to the complete satisfaction of the Architect.	450	SFT		
	f	WICKET GATE Providing and fixing 3' - 0' ht. Wicket Gate between the counters to check the movements of customers inside the restricted area. Fully paneled door shutter including the door frame made up of styles and top rail, bottom rail using 1st class hardwood, 9mm MDF board exterior grade of CENTURY/GREEN/ECOTEC Make to be fixed on both faces finished with 1 mm thick high gloss laminate of CENTURY/ MERINO/ GREENLAM/ AMULYA MICA Make. The work includes providing and fixing necessary hardware SS finish latches, butt hinges etc., steam beach beading etc. (spirit polished) as per drawings to the full satisfaction of the Architect, complete in all respects. Please note that all the 19mm thickness portion must be finished with liping/margin	15	SFT		

	g	Texture Paint Finish Providing and applying texture paint of approved colour of (Spectrum make rustic finish), ready mixed material with synthetic binders, applied manually with spatula uniformly on to the wall surfaces, complete including two coats of white plastic emulsion paint over it as per instructions of the architect / Bank's Engineer.	500	SFT		
	h	Aluminium Composite Panel Cladding Providing & Fixing Aluminium Composite Panel 3mm thk of approved colours over columns at the front complete i/c necessary aluminium framing/ sheets, silicon filling of joints, 12mm grooves, etc Make: Alstone or equivalent.	200	SFT		
	i	Dismantling work Dismantling/ Removing/ Refixing of Storage cabinets/ Counters, Alum/ Wooden partitions, networking and electrical fittings/ wires and shifting, etc. Stacking of useable and other materials at suitable place as directed by Branch Incharge/ Architect.	0	JOB		
6		Vitrified Tile flooring (Floor) Providing & Laying Vitrified Tiles of size 600mm x 600mm of Johnson/ Kajaria/ Nitco make to be laid on existing flooring with approved quality tile adhesive such as fevimate-xl, bell endure, laticrete make in thickness not less than 3mm and grouting the joints with white cement slurry mixed with matching pigment, complete in all respects including filling the depressions, if any, as per approved pattern. The cost includes hacking of surface to receive the flooring . Shade: As approved by the Architect.	0	SFT		
			TOTAL		Rs	
		NOTE:- Anti-termite treatment with Chloropyriphos of approved brand and make to be done on all wooden surfaces without any extra charges. No extra amount will be paid.			GST EXTRA @18%	
		The Contractor is strictly advised to use the makes specified/approved by the Bank/Architect, unspecified items will not be paid until they are changed with the specified ones. Copy of Purchase Bills to be submitted to the Architect/ Engineer.				
						