

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
ITEMS					
R1	DISMENTALING OF EXISTING ELECTRICAL WORK AND DISPOSAL OF MALBA TO NEAREST MUNICIPAL GROUND INCLUDING TRANSPORTATION	0.00	JOB		
R2	SITC of 3 Nos. Kit Kat Rewirable Porcelain fuse carrier & Base with neutral link on wooden frame of 100 amp/415 Volt near meter Box complete with connections complete in all respect to the satisfaction of Bank.	1.00	Set		
R3	<p>ELECTRICAL MAIN PANEL: Supply, delivery, installation, testing, commissioning, of L&T make indoor wall/ floor mounted type distribution boards made out of 2 mm thk. CRCA sheet metal duely acid treated premised & painted with 2 coats of enamel paint compartment arrangement for each equipment & bus bar chamber on the top of the panel running horizontal through out its length duly lamp, vermin proof having provision cable by conduit entry , earthling stud as per specification mentioned below duly factory wired confirming to the relevant ISS & as per special condition of contract, making good the damages M.S. Cubical type Panel board should have hinged door at the front. The panel shall be provided with all accessories & following arrangements complete in all respect & direction of EIC (Before Placing the Panel order, firstly it passed by the Bank Authority, otherwise it will not considered). It shall have the following:</p>	1.00	Job		
	<p>INCOMER: 1 No.200 Amp. TPN, MCCB (25 KA breaking capacity) with overvoltage protection as incommer for Main supply.</p> <p>Bus bars 200 Amp., 3 phase, 4 strips, 415 volts, 50 Hz. Electrolytic grade copper Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers.</p> <p>There should be 2 sets of BUS BAR in such a way that AC load should not be connected to GENERATOR power.</p> <p>200 amp Onload changeover with 1 Nos 200 amp 25 KA, TP MCCB for DG supply with 200 amp bus bar.</p> <p>Instruments: TWO set of Digital Multi function Meter (<u>One for Main Power Supply & Other for Generator Supply</u>) of standard make for displaying Input Voltage, Ampere, Power factor, KWH used with CTs.</p> <p>Note-</p> <ol style="list-style-type: none"> All wiring and lugs inside the panel shall be of copper to be fixed using nut-bolt & spring washers. All switchgears shall be properly marked with operaion marks. All MCB to be "C" series 				

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
	<p>OUTGOING: 10 Nos. 32/40/63 Amp. TPN MCB (For LDB/INVERTER, PDB, Branch UPS, Inverter DB and Spare Feeder) from Generator Powered Bus. 8 Nos. 63 Amp. TPN MCB (4 POLE) (For AC DB and Spare Feeders) from Non-Generator Powered Bus. 5 Nos. 32 AMP DP MCB. 3 Nos (for Glow Sign boards, Strong Room & One Spare) from Generator Powered Bus. The design of panel should be got approved by the Architect before manufacturing. Also, the provision for 1/2 spare outgoing should be considered for future expansion. The job shall be completed to the satisfaction of the Bank</p>				
R3A	Supply & Installation of SPD (Surge Protector Device) for general protection of main Electrical Panel Legrad Make Cat No. 412247 (3P+N) , 40 KA, T2- Imax 40KA/pole with complete wiring.	1.00	Nos.		
R4	DISTRIBUTION BOARDS:				
a	<u>Rotary Phase selector switch - TO BE LOCATED INSIDE UPS ROOM</u>				
	SITC of 40/63 Amp. Rotary Phase selector switch complete with RYB indication in enclosure for Branch's UPS input power network, Spare and Inverter. Complete in all respect as required.	3.00	Nos.		
b	<u>U.P.S. DISTRIBUTION BOARD (INCOMER DB) - TO BE LOCATED INSIDE UPS ROOM</u>				
	SITC of the surface / recess mounting following way Double door MCB D.B.- Single phase distribution board (Consumer unit) for single phase out going with IP 42 protection incl. the followings accessories - incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
	INCOMER (Branch UPS & Spare UPS)				
	1 NOS 63 A DPMCB				
	OUTGOINGS				
	2 Nos- 40 Amp DP MCB+ 1 Spare				
	SET AS ABOVE	2.00	Nos		
c	<u>U.P.S. DISTRIBUTION BOARD (OUTGOING DB) - TO BE LOCATED INSIDE UPS ROOM</u>				
	SITC of the surface / recess mounting following way Double door MCB D.B.- Single phase distribution board (Consumer unit) for single phase out going with IP 42 protection incl. the followings accessories - incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
	INCOMER (Branch UPS & Spare UPS)				

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
	1 NOS 40 A DPMCB				
	OUTGOINGS				
	2 Nos- 40 Amp DP MCB+ 1 Spare				
	SET AS ABOVE	2.00	Nos		
d	INVERTER INCOMER & OUTGOING MS BOX - <u>TO BE LOCATED INSIDE UPS ROOM</u>				
	SITC of 32/40 Amp. DP MCB in a MS encloser Single Door complete complete in all respects as required.	2.00	Nos.		
e	<u>LIGHT DISTRIBUTION BOARD</u>				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER - Incoming Supply from Inverter output				
	1 No. DPMCB 40 Amp				
	OUTGOINGS				
	6-8 Nos SPMCB 6-10 Amp				
	SET AS ABOVE	3.00	Nos		
	incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
f	<u>POWER DISTRIBUTION BOARD</u>				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER				
	1 No. TPMCB 63 Amp				
	OUTGOINGS				
	6-12 Nos SPMCB 16/32 Amp				
	SET AS ABOVE	3.00	Nos		
	incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
g	<u>AC DISTRIBUTION BOARD</u>				
	SITC of the surface / recess mounting following way MCB three phase distribution board for single phase outgoing with IP 42 protection , direct on wall incl. the followings accessories				
	INCOMER				
	1 No. TPMCB 63 Amp				
	OUTGOINGS				
	8 Nos DPMCB 25 Amp + 2 Nos Spare				
	SET AS ABOVE	2.00	Nos		
	incl. Electrical connection, earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
h	SITC of 12 WAY SPN Double Door DB complete with 1 No. 40 AMP DP MCB as incomer and 10 NOS. 6-10 AMP SPMCB as outgoing for Branch UPS power distribution to Computer points on Staff Counters / Tables.	2.00	Nos.		
i	SITC of 8 WAY SPN Double Door DB complete with 1 No. 32 AMP DP MCB as incomer and 6 NOS. 6-10 AMP SPMCB as outgoing for UPS power distribution points for ESSENTIAL LODAS like CCTV System, Fire & Burglar Alarm Systems, Networking Rack, Spare (if separate Spare UPS not available) and select Light points powered by UPS.	2.00	Nos.		
j	SITC of 1 no. 10A DP MCB with MS enclosure Industrial Plug Socket Unit with 1.0 mtr long 3 core 2.5 Sqmm Copper flexible cable for strong room power supply switch board installed at STRONG ROOM/SAFE ROOM entrance Gate complete in all respect as required.	0.00	Nos.		
	incl. Electrical connection ,earthing, making good all the damages, painting, cleaning the site, etc complete as per site requirement and as directed.				
R5	CABLES				
	All cables / wires shall be routed through PVC conduits / bends / elbows etc., as required, of appropriate dia. The conduits shall be clamped firmly to the walls / columns / pillars etc. with clips / clamps and fasteners rigidly even if above false ceiling.				
	Complete job shall include cutting chiseling in walls, floor and making good of all chases / cuts etc. with combination of cement-mortar, including painting with type and shade of existing wall. The work shall be completed to the satisfaction of Bank. NO CABLE / WIRE / CONDUIT SHALL BE VISIBLE IN THE BRANCH HALL / CUSTOMER LOBBY / STAFF WORKING AREA.				
a	SITC of 3.5 Core 35.0 Sq.mm Aluminium conductor Armoured Cable for service line connection up to Kit kat fuse unit complete in all respect as required.	35.00	Mtr.		
b	SITC of 4.0 Core 70.0 Sq.mm Aluminium conductor Armoured Cable for service line connection up to Kit kat fuse unit complete in all respect as required.	40.00	Mtr.		
c	SITC of 4 Core 25.0 Sq.mm Copper conductor Armoured Cable for service line connection up to Kit kat fuse unit complete in all respect as required.	45.00	Mtr.		
d	SITC of 4 core 6.0 Sq.mm Copper conductor Armoured Cable from Main Panel to INVERTER, LDB, Spare UPS & Branch UPS input power supply.	58.00	Mtr.		
e	SITC of 2 runs of 6.0 Sq.mm and 1 no. of 2.5 Sqmm FRLS PVC Insulated Multistrand Copper conductor wire from selector switch to UPS/INVERTER to UPS/LDB Distribution boards.	85.00	Mtr.		

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
f	SITC of 4 core 10 Sq.mm + 1 X 4 sq.mm Copper conductor Armoured Cable from main Panel / Non Generator power Bus to AC DB.	45.00	Mtr.		
g	SITC of Sub main Wiring for Strong room and Glow Sign Board with 2 No. 4.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper conductor FR pvc/ xlpe insulated Wire in required dia pvc conduit complete in all respects as required.	65.00	Mtr.		
h	SITC of 2C x 2.5 Sqmm copper earth wire from 6 way DB to network rack , CCTV Fire alarm etc	55.00	Mtr.		
i	SITC of 2C x 1 Sq mm copper wire from main panel to 3 way LED indicator	68.00	Mtr.		
R6	AC POINT (High wall and Cassette)				
a	SITC of AC Point Wiring with 2 No. 4.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & Industrial plug & Socket with 10/16 Amp. DPMCB complete in all respect as required by the Bank (for 1.0 / 1.5 TR Hi-Wall Split ACs)	2.00	Nos.		
b	SITC of AC Point Wiring with 2 No. 6.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & Industrial plug & Socket with 20 Amp. DPMCB complete in all respect as required by the Bank (for 2.0 TR Hi-Wall Split / Cassette ACs). The point shall be placed near outdoor unit.	15.00	Nos.		
c	SITC of AC Point Wiring with 4 No. 6.0 Sq.mm and 1 No. 2.5 Sq.mm Multistrand Copper Wire & 20/32/40 Amp. TPN MCB in a MS Box complete in all respect as required by the Bank (for 3.0 TR/4.0 TR Hi-Wall Cassette ACs). The point shall be placed near outdoor unit.	0.00	Nos.		
R7	EARTHING				
a	Preparation and commissioning of earth pits with PIP technology GEL type 50mmdia 3000mm long earth electro. (One Dedicated Earthing for Spare UPS, Branch UPS and Main Electrical Panel)	4.00	Nos.		
b	Supply fixing and termination of 32x6 mm G.I. strip with earth station below ground level etc as required.	85.00	Mtr.		
c	SITC of Earthing conductor from earth terminal to load point with 10 sq mm multstrand copper conductor FR pvc /XLPE insulated cable in required dia PVC heavy duty conduit complete in all respect as required.	55.00	Mtr.		
R8	UPS POWER POINT	70.00	Nos.		
	Supply & Installation of point wiring for UPS or stabilized power plug points on workstations / table for computers using 3 X1.5 Sq.mm copper conductor multi starnd FR PVC sheathed flexible wire including PVC conduite laid floor raceways/conduit and taken upto table top using PVC rigid or flexible conduits run within wooden/metal partitions. Each point consisting of 1 No. Phase Indication light,3 Nos 6A , 5/6 pin sockets & wired together forming one point. The earth wire of green color only.				
R9	RAW POWER POINT				

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
	Same as serial no.1, but providing power point by using 2*4.00 sq.mm. PVC insulated 1100 V grade copper conductor wire with independent 1*4.0 sq.mm earth wire from D.B. to first point (Primary Point) and first to second point with 2*2.5 sq.mm. PVC insulated 1100 V grade copper conductor wire and 1*2.5 earth wire (Secondary Point). All wiring is to be provided in PVC conduit of suitable size. Each power point (Primary or Secondary) must include providing and fixing of a dual socket combination of 1 no. 16 Amp 6 -pin socket with 16 Amp. switch & 1 no. 6 Amp 5-pin socket with 6 Amp. switch. The switches should be Modular type switch / socket / plate etc. complete assembly).				
	There shall be a maximum of 2 points per circuit				
	NOTE: The power point, complete as mentioned above, shall be placed on the low ht. / full ht. partition above the tables / counters at a suitable place to ensure convenient accessibility for staff.				
a	With 2nos 16A socket with individual 16A switch.	35.00	Nos.		
b	With 1nos 16A socket with individual 16A switch.	20.00	Nos.		
R10	LIGHT/FAN POINT				
	Wiring for light/fan/exhaust fan points using 3 X 1.5 1.1 kV grade PVC insulated stranded copper conductor wire (Finolex/ Havell's/ Richa/ RR kebel/ KEI or equivalent) for phase, neutral and earth (with proper R,Y,B color code) in 25 mm dia heavy duty PVC conduit along with associated accessories like MS junction boxes, bends, saddles, screws et. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/Fan/Exhaust Fan point outlet. etc. to individual modular type switch boards, 10 Amp modular plate type switches etc.(MK/Legrand's/Havel's or equivalent), as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and as per site requirement and as instructed by Engineer In-Charge.				
a	One light point including the cost of 6A modular switch	28.00	Nos.		
b	Two light point including the cost of 6A modular switch	37.00	Nos.		
c	Three light point including the cost of 6A modular switch	85.00	Nos.		
d	Four light point including the cost of 6A modular switch	0.00	Nos.		
e	Ceiling Fan Point including the cost of 6A Switch along with 5 step electronic fan regulator.	4.00	Nos.		
f	Wall Fan Point along with 6 AMP switch & 3 PIN Socket	20.00	Nos.		
g	Exhaust Fan Point along with 6 AMP switch & 3 PIN Socket	8.00	Nos.		
h	SITC of Call Bell Point & Call Bell.	4.00	Nos.		
i	6A Switch & Plug point in same switch board	10.00	Nos.		
j	Cove light points including the cost of 6A modular switch	8.00	Nos.		
k	16A, 5 pin industrail plug & Socket with 25 A MCB protected (for Strong Room/SAFE room & Record room)	0.00	Nos.		

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
R11	DATA CABLING & POINT				
	Supplying and laying of D-Link make CAT-6 (UTP) cable through trenches / conduits.				
a	Supplying and laying D-link make CAT-6 Cable in P.V.C. Conduit Complete with CAT-6 information outlet with plate & surface Box at individual Tables	70.00	Nos.		
b	Supplying and fixing of 1 mtr long crimped patch cord	70.00	Nos.		
c	Supplying and fixing of 2 mtr long crimped patch cord	70.00	Nos.		
d	Supplying and fixing of 24 U Rack complete with exhaust fan, lockable front glass door, cable managers, electrical socket board etc.	2.00	Nos.		
e	Supplying and fixing of 24 port jack panel	2.00	Nos.		
f	Supply and fixing of 1.6 mm thick G.I. Box along with RG 6 T.V Co axial socket with Cover Plate.	4.00	Nos.		
g	Supply, drawing, connecting, testing and commissioning of T.V Coaxial cable RG 6 with conduit.	25.00	Mtr.		
R12	VOICE NETWORKING				
a	Supply and fixing of 1 nos. 50 pair telephone MDF consisting of tag blocks, disconnecter type, complete with powder coated metal enclose, krone tag block mounting arrangement telephone distribution chart and locking arrangement [for P&T/EPABX]	1.00	Job		
b	Supplying and laying telephone cables 0.5mm dia 2 pair electrolytic tinned copper conductors PVC insulated and twisted pair with rip cord, including PVC conduits/Racewaysand RJ11 telephone socket outlet. The rate shall include termination at both ends on tag blocks. 2 Nos. RJ11 Telephone socket with plate and box	35.00	No.		
R13	PUBLIC ADDRESS SYSTEM				
a	SITC of 1000W Class-D Amplifier with 4 independent channels and can provide automatic re-settable overcurrent, overload, overheating, overvoltage, under-voltage and DC protection. Approved Makes : Bosch Praesedio / Honeywell - X618/ Ateis - IDA	1	Set		
b	SITC of 6W Wall / ceiling mount of 96dB . Frequency response of 160Hz-20KHz. The speaker should have tappings at 6W/3W.	15	Set		
c	Supply, Installation, Testing & Commissioning of 12 Volume Controller for all the closed areas.	15	Nos.		
d	Wiring for PA system with the following sizes of PVC insulated copper conductor twisted cables in existing surface/recessed M.S. conduit etc. as complete as required. 2 x 1.5 sq.mm twin twisted PVC wire (30/0.25mm)	110	Mtrs		
R12	FIRE & ELECTRICAL SAFETY INDICATION				
a	Supply and installation of Vinyl sticker for on Electrical DBs like, " <u>Switch Off at Night</u> ", <u>Switch Off For Safety</u> , etc	6.00	Nos.		
b	SITC of a set of indication lamp set (4 Nos. RED, YELLOW, BLUE & GREEN Color) in a concealed PVC modular box.	2.00	No.		

BOQ FOR ELECTRICAL WORKS AT CANARA BANK, REGIONAL OFFICE-GURUGRAM, SECTOR-32, GURUGRAM, HARYANA

S. NO.	DESCRIPTION OF ITEM	QTY	UOM	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
c	Wiring in heavy duty PVC conduit of IS specification of proper size with 2 runs of 1.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade (Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with all material supply installation and commissioning complete from Computer Counter DB, AC DB, LDB, PDB outgoing to a set of indication lamp set (4 Nos. RED, YELLOW, BLUE & GREEN Color).	55.00	Mtrs		
R13	SITC of Angle holder complete in all respect with 9W LED lamp	6.00	Nos.		
R14	SITC of LED COVE/ STRIP LIGHT WITH ITS ELECTRONIC DRIVER(BLUE COLOUR):- SITC of bright LED strip light with its electronic driver complete as required. PHILIPS, WIPRO, HAVELLS, CG.	295.00	Mtrs		
R15	Supply and laying of ISI mark Electrical safety Insulating mat of dimension 1000mm X 1000mm in UPS Room.	2.00	Nos.		
R16	Providing Temporary arrangements for functioning of Branch throughout the course of completion of renovation work including temporary shifting of Electrical points, Data Points, Ups Points, Networking etc. to enable smooth functioning of the branch during renovation all complete as per the instructions of Architect / Bank's Engineer .	0.00	Job		
TOTAL					
ITEMS					
C	FIXTURES/FANS (All light fixtures and fans to be supplied COMMERCIAL MODELS only)				
C1	SITC of 36W 2' X 2' Square decorative LED light fitting of approved model & make. (contractor to get the model approved from bank before installation)	70.00	Nos.		
C2	SITC of surface mounted 20W LED batten light including required hanging arrangement wherever required	20.00	Nos.		
C3	SITC of 10W LED Down Lighter of approved make	225.00	Nos.		
C4	SITC of 5-7W LED COB / Spot light of approved model & make (contractor to get the model approved from bank before installation)	20.00	Nos.		
C5	SITC of 450mm Wall Mounted full metal body Fan of approved make.	20.00	Nos.		
C6	SITC of 1200mm / 900mm Ceiling Fan of approved make with required down rod and hanging arrangement	4.00	Nos.		
C7	SITC of 9" metal body exhaust fan of approved make.	8.00	Nos.		
C8	Supply, instalation, testing & Commissioning of 8(2X4) modules brushed brass/copper colour pop-up boxes.(Make-Legrand, model No.-0540 18)(All switch socket, DATA outlet, telephone etc are considered separately)	6.00	Nos.		
C9	Supplying and fixing of High intensity and decorative type profile LED light complete with aluminium profile with cover , LED strip with driver etc and fixing the same with suitable adhesive, nails , making connections testing etc complete as reqd	30.00	Mtrs		
TOTAL					
TOTALFOR ELECTRICAL WORK (A) (Rs.)					
Say Rs.					