

CANARA BANK CIRCLE OFFICE KARNAL

BOQ (BILL OF QUANTITY) OF INTERIOR AND RENOVATION WORK OF CANARA BANK BRANCH AT UTTAWAR, HARYANA.

S. No.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE(Rs.)	AMOUNT(Rs.)
1	REMOVING & SHIFTING OLD FURNITURE				
	Removing and shifting of Existing old Furniture and tables including cash cabin,all type storage, old chairs, wooden/glass partitions and all type doors to bank store/other branch as per bank's instructions including all Labour and transportation with in 15 km.	Job	1.00		
2	PARTITION /PANELLING				
	Measurement of height shall be taken from finished floor level up to the level of ceiling, in case of varying heights on either side of partition, average height shall considered. The rate include Provision of extra frame work as necessary for skirting and making cut-outs for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduit as per drawings & directions. All plywood to be applied anti termite compound.				
i	PARTLY GLAZED MANAGER CABIN PARTITION (FULL HEIGHT)				
	Providing and Fixing of full height wooden glazed partition as per detail drawing made of 2 MM thick Aluminium tube frame The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminium angles and fastened with steel screws.Frame size 50 x 50 MM with 9 MM thick BWR Ply with 1mm thk. Laminate both side in approved colour,design, shape and size, & 12mm thick toughned glass panel fixed upto 8'-0"ht. inculding all exposed surface with teak lipping 6mm thk with 2 coats of melamine polish as required and instructed by Architect and including teak wood door frame (75 mm x75 mm) in between the partition and 2 coats of melamine polish. inculding Anti Termite Treatment.Complete in all respect and satisfacation of Architect/Engg.	Sq Mts	18.00		
ii	LOW HEIGHT PARTITION (4'-0" HEIGHT)				

	Providing and Fixing of low height wooden partition (up to 4'-0" height) made of 2 MM thick Aluminium tube frame The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor with suitable aluminium angles and fastened with steel screws. Frame size 50 x 50 MM with 9 MM thick BWR Ply finished with 1mm thk Laminate both side as per approved colour, design, shape and size, The partition shall be solid till 3'-0" then glazing with 8-10mm thick clear float glass of 1'-0" Height & supported on 4" wide solid partition pillars on both sides of the glass. The exposed edges of the glass shall be bevelled, grinded and machine finished to render smooth edges. The glass in the partitions shall be fixed with beading / moulding on both sides including on top Teak wood lipping 6mm thk as required to be provided at every exposed section of ply with 2 coat melamine polish including Anti Termite Treatment complete in all respect and satisfaction, instructed by Architect/Engg.	Sq Mts	8.00		
iii	FLAP DOOR (4'0" High)				
	Providing and fixing of flap door using 19mm thick block board of approved make laminated on both sides with 1mm thick laminate of approved shade as mentioned above. The exposed edges of the board shall be finished with teakwood beading of appropriate thickness (enough to cover the entire exposed edges). The rate quoted must also include a vertical brass tower bolt assembly, 2 Nos. SS Butt Hinges (100mmx5.5mm size), screws & magnetic ball catchers etc of approved makes. There shall be 100mm high skirting at the bottom of the door with 1mm lamination in Canara Bank Blue shade & a 100mm high top band of Canara Bank Yellow colour at the vertical top of the door so as to match the surrounding scheme.	Sq Mts	1.00		
iv	CASH CABIN PARTITION (Height 7'-6")				
	Providing and fixing both side laminated Solid partition for cash cabin using made of 2 MM thick Aluminium tube frame The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor with suitable aluminium angles and fastened with steel screws. Frame size 50 x 50 MM with 9 MM thick BWR Ply finished with 1mm thk Laminate both side as per approved colour, design, shape and size, The partition shall be solid till 4'-0" height and thereafter an opening of 2'-6" Height & 2'-6" width (or of appropriate size as per site requirement) for Aluminium Decorative Grill (12mm thick having hexagonal openings) which shall be provided with double sided 2 coat melamine polished teakwood beading. Rest of the height shall be solid partition till the height of 7'-6" from the finished floor. All exposed edges of teakwood lipping of appropriate thickness (75mmx6mm thick sections or as per site) enough to cover the entire exposed edges and frame opening for aluminium grill / doors chowkhat / windows etc.) with 2 coat melamine polish.				

	The rate quoted must be inclusive of the 32-35mm thick door (Size - 7'-0"x3'-0") made with commercial plywood / board approved make with 1.0 mm thick matt finish laminate pasted over plywood along with skirting and top band on both side of the door as per bank's colour scheme along with making 6mm thk glass opening of size 18"(W) X 48"(H) positioned at the horizontal centre & 5'-0" height for visibility with proper teakwood framing and polishing. The exposed edges of the door must be finished with teakwood lipping with 2 coats of melamine polish. Item shall also include supply and installation of frosting film of approved make with approved artwork. Film shall be self-adhesive with bubblefree installation to be done on clean glass.				
	A 2" deep slip tray made of 11mm/12mm ply covered with 1.0 mm thick white matt laminate with edges finished with teakwood beading and 2 coats of melamine polish to be affixed at a height of 4'0" from the finished floor on the side partition adjacent to the passing Officer's counter at an appropriate slot to ensure convenient usage by both staff members. The slip tray must be 6" wide 10" long and must be positioned such that it must be emanating 4" on either side of the partition. The front edges of the partitions i.e., the edges visible to the customers, shall be finished with 1.0mm thick laminate of Canara Bank Blue shade. The rate quoted must also include installing / affixing all necessary fittings like 4 Nos. SS Butt Hinges (100mmx5.5mm size), screws, Hydraulic Door Closer, Night latch, SS Handles on both sides & Brass Door Stopper etc as per approved makes.	Sq Mts	12.00		
v	FULLY GLAZED PARTITION - WITH TOUGHENED GLASS				
	USING OZONE / HAFFLE / YALE / GODREJ MAKE FITTINGS				
	Providing and fixing of Fixed Glass partition with 12mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.	Sq Mts	2.00		
vi	GLASS BARRIER				

	Providing and fixing glass barrier in the front of clerical / working counters made out of 12mm thick clear toughened glass with chamfered and polished edges. The glass must be supported at each end of the individual counters either with low height partitions or 3"x3" square towers of required height made with 19mm thick approved ply finished with 1mm thick laminate of approved shade on all faces as per the design approved by bank. In case of square towers, the top of the towers should be finished with 1mm thick approved laminate. The glass should be clamped rigidly to the low height partition / towers with teakwood beading finished with melamine polish along with necessary hardware / accessories as required. The height of the glass barrier shall be 450 mm (or as directed by the bank). The length of the glass barrier in single piece must be equal to the length of the individual counter. Item shall also include frosting film of approved make with approved artwork. Film shall be of approved make, self-adhesive with bubble free installation.	Sq Mts	4.00		
	WALL / COLUMN PANELING (Full Ht. - till soffit of false ceiling) (Walls in Manager Cabin / Walls in Cash cabin / Independent pillars in branch hall / Side wall adjacent to Officer Table ONLY)				
	Providing and Fixing of wooden Panelling of wall on hall and column made of 2 MM thick Aluminium tube frame. The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminium angles and fastened with steel screws. Frame size 25 x 50 MM with 9 MM thick BWR Ply with 1mm thick laminate in approved colour, design, shape and size, including Anti Termite Treatment. The soffits of the doors / windows shall also be covered with paneling as well. Item shall include 100mm high skirting on bottom of the finished floor in Canara Bank Blue shade and a top band of 100mm high from the soffit/ceiling/visible top height of the paneling in Canara Bank Yellow shade. Remaining area shall be finished with 1.0mm thick white laminate of approved make. Complete in all respect and satisfaction of Architect/Engg. Note - No paneling shall be provided behind the storage / cabinets / tables sides or any other surface which is not visible (no payment for same shall be entertained by the bank). Entire paneling shall be provided only on visible surfaces as per approved layout or as directed by the Bank. Also, no paneling shall be provided on the columns embedded in walls. The paneling should be provided on independent pillars in the branch hall only that too till soffit of false ceiling.	Sq Mts	39.00		
	Note:- In case of wall not being true to plumb extra shims of aluminium section shall be provided. Nothing extra shall be payable in this regard.				
	Note: a) In case of false ceiling, area of panelling payable will be below the false ceiling only. b) Measurement of height shall be taken from finished floor only, in case of varying heights on either side of panelling, average height shall be considered. c) Openings/ door/ glass shall not be measured for payment.				
3	DOORS				

i	ENTRANCE/MANAGER DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)				
	DOORS - WITH OZONE / HAFFLE / YALE / GODREJ MAKE FITTINGS				
	Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings(Dorma/Ozone/Haffle/Yale/Godrej make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)	Sq Mts	5.00		
ii	SOLID DOORS-IN LAMINATE FINISH (with hardware fittings MAKE EVERITE/GOLDEN /HARDWIN/EVEREST) (OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT				
	3-0" x 7'-0" - IN LAMINATE FINISH - (WITH 3.5" x 2" finished size WOODEN FRAME)				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3.5" x 2" steam beach section shall be provided finished in mellamine. Rate shall include Dead lock (Godrej Make), floor springs / door closure (as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5"hinges 4 Nos., buffers, tower bolts, door frame (3.5"x2" etc with necessary hardware items and with or with out door frames.	Sq Mts	2.00		
4	COUNTERS & TABLES				
	Providing & Fixing Box type Tables and counters of size mentioned below as per branch drawing and layout. The tables / counters are made out of 19mm thick approved ply / block board frame work for top, verticals, apron, sides, drawer unit with shelves, shutters, customer top, foot rest. The sides, sliding shutters, front apron of drawer unit shall be made out of 19.0mm thick approved ply while backs & bottom of drawer unit shall be made with 6mm thick approved ply. The drawer unit of 450mm width x 750mm height x 500mm depth or size approved by the bank shall be placed on a suitable side of the table / counter as per layout. The drawer unit shall consisting of 3 nos. drawers of equal height to cover the entire height of the unit & each must be 450mm deep OR of size & number as approved by the bank. Each drawer shall have SS handles with multipurpose concealed lock. The drawers shall be fixed with telescopic SS sliding channels of approved make with easy push-pull mechanism.All inner surface shall				

	<p>A uniform 100mm high skirting shall be provided at the visible bottom of the side unit with 1.0mm thick laminate of Canara Bank Blue shade. All inner surface shall be finished with 0.8mm thick white laminate with matching edge tapes for all exposed edges. A fixed footrest made with T.W. member of size 4"x1.5" finished with french polish shall also be provided at the bottom of the inside of the tables / counters at a comfortable height. The working top of ALL counters / tables shall be provided with 10mm thick clear glass on top with edges bevelled and machine finished to render smooth edges. Grooves / openings for cable managers shall also be provisioned in the table and glass along with supply & fixing of cable manager. The shape of the top glass shall be prepared / cut in such a manner that the entire surface of the working top of the table / counters should be covered by the top glass.</p>				
	<p>All the open surfaces of the tables / counters / drawer units shall be completely covered with 1mm thick laminates. The front apron and visible side apron(s) of the counters / tables shall be provided with 100mm top band of 1.0mm thk laminate of Canara Bank Yellow shade & 100mm skirting of 1.0mm thk laminate of Canara Bank Blue shade. The remaining area shall be provided with 1.0mm thick white laminate. The counter / table top shall be provided with 1.0mm thick laminate of Canara Bank Blue shade. The other exposed edges shall be finished with teakwood lipping & 2 coats of melamine polish. All inner surfaces shall be finished with approved 0.8 mm thick laminate of ivory / white shade of approved make.</p>				
	<p>All table / counters shall be provided with sliding key board unit of size 12"x20" made of 19mm thick approved board finished with 1.0mm white laminate and mounted with telescopic channels of approved make on the sides made out from 12mm thk approved board with 1.0mm thick white laminate. All exposed edges to be finished with teakwood beadings of appropriate size and 2 coats of melamine polish along with all other finishes / hardware / fittings etc required to complete the job</p>				

	For CASH COUNTER- Same as above but the cash counter shall have two working tops viz. one working top at height of 2'6" for staff & other, the customer top, at height of 4'-00" for customer use. The customer top shall be 450mm wide of length as mentioned below and shall be fabricated such that it is projected 150mm outwards i.e. towards the customer. The rate quoted must include full front portion and customer top of mentioned height and style made out of 19mm approved ply and 1.0mm thick laminate of design as approved by the Bank, along with 12mm plain toughened front glass which should be 3'-6" high over and above the customer top and of required length as mentioned below. A support partition shall also be provided on top of the glass till a height of 7'-6" from the finished floor. The partition over the glass shall be made out of 19mm thk approved board finished with 1.0mm thick laminate of Canara Bank Blue shade. The front glass shall be fixed rigidly over the customer top with teakwood beadings on both sides finished with 2 coats of melamine polish. Two openings / slits shall be provided in the front glass - one opening of 300mmx150mm on the horizontal centre at the bottom of the glass and another 4" wide horizontal slit at the vertical centre of the front glass for convenient cash and voice transaction. The glass edges shall be bevelled on all exposed edges on both faces to ensure safe & smooth edges.All inner surface shall be finished with 0.8mm thick white laminate with matching edge tapes for all exposed edges.				
i	Manager Table (Size 6'-0"x3'-0"x2'-6"(H))	Nos	1.00		
ii	Officer Table (Size: 4'0"x2'0"x2'6"(H))	Nos	5.00		
iii	Cash Counters (Width of working top: 3'0" & width of customer top: 1'6"; Heights as per description above)	Rmt	1.50		
5	STORAGE CABINETS / CREDENZAS				
	Providing & placing in position box type storage cabinets / Credenzas 18" deep & height as given below made out of 19mm approved board with 1mm laminate with shade as per bank's approved scheme. The top of the low height storages / credenzas shall be finished with 1.0mm thk Canara Bank Blue laminate. The sides, partition, top, shelves & bottom shall be made out of 19mm thk. approved board and back made out of 6mm thk. approved ply. Item shall have one 6" high drawers on top made out of 19mm thick approved ply / board complete with handles, locks etc of approved makes. The shutters made out of 19mm commercial ply wood finished with 1.0mm thk laminates of approved scheme on the outer surface shallcover the remaining space available below the drawers. All inner surface shall be finished with 0.8mm thick white laminate with matching edge tapes for all exposed edges. A 100mm high top band shall be provided on top front face of the storage cabinets / credenzas finished with 1mm thk canara bank yellow laminate & 100mm high skirting finished with canara bank blue laminate shall be provided as per approved make.				

	The drawer must be finished with 1.0mm thk laminate of shade as per Bank's scheme on outer surface and 0.8mm thick white laminate on the inner surfaces. The drawers shall be supported with SS telescopic sliding channels of approved make with smooth push-pull mechanism along with SS handles and individual locks. The shutters below the drawer shall be supported with soft close clip-on SS Hinges of approved make of required number depending upon the size of the shutter. Each shutter shall be supplied with necessary accessories and hardware such as individual locks, SS handles, magnetic ball catchers, SS tower bolts, individual locks etc. of approved makes screwed and fixed rigidly. Horizontal shelves & vertical planks made out of 19mm thick commercial board shall be provided inside the shutters in such a manner to create optimum number of storage chambers each of equal storage space depending upon the size of the cabinets / credenzas. These partitions shall be finished with 1mm thick white laminate on all faces and exposed side (thickness) edges of the partition members shall be finished with teakwood lipping and 2 coats of melamine polish. Note - For the purpose of contractors bill payment, only front elevation area shall be measured				
i	Side credenza adjacent to the tables and counters (2'-6" High & 3'-0" Wide OR as mentioned in layout) with 1 no. 6" high drawers at top & shutters below drawer.	Sq Mts	1.00		
ii	Low Ht. Storage (2'-6" High) (FOR B.M. Cabin and Cash Cabin only) with 1 no. 6" high drawers at top & shutters below drawer.	Sq Mts	3.00		
iii	Low Ht. Storage (4'-0" High) (FOR space behind staff counters in Branch Hall only) without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights.	Sq Mts	14.00		
iv	Full Ht. Storage (8'-6" High) but without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights	Sq Mts	14.00		
6	CUSTOMER WRITING DESK.				

	Supply and fixing of free standing box type customer writing desk of required length, 42" height and 18" deep. The desk shall be made out of 19mm thick approved block / ply upto the height of 36" and glass bins above (open towards the front for keeping challans) of size 6" X 6" each made up of 10 mm thick plain glass on back & side partitions of the bins affixed firmly to the base and the writing top over the bins shall be made of 12mm thk clear glass, finished with smooth edges and sealed with silicon sealant. The bottom of the desk shall consist of 2 nos. box type cabinets of size - 12" (w) x 24" (h) x 18" (d) made out of 19mm thick approved ply with shutters with a viewing glass pane of appropriate size using 6-8mm plain glass and 20mm horizontal slit at the top of the shutter. The shutter shall be complete with all accessories like lock, SS handles, SS Hinges etc. All the exposed surfaces of the board shall be covered with 1mm thk laminate of approved shades and exposed edges to be finished with teakwood lipping and 2 coats of melamine polish.	Rmt	1.5		
	he exterior visible portion of the desk shall be finished with 1.0mm thick approved laminate on visible sides as per bank's colour scheme with matching top band skirting (100mm Canara Bank Yellow Top Band and 100mm bottom skirting of Canara Bank Blue Colour). All inner surfaces shall be finished with approved 0.8mm thk laminate in white shade. Item shall include all required hardware & accessories such as SS clamps, screws, slits etc to ensure that the rigid fixing of the desk members / parts and complete the item upto the satisfaction of the bank / Architect.				
7	FALSE CEILING (Branch & ATM)				
i	FALSE CEILING - GYP BOARD				
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffite at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffite with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.	Sq Mts	72.00		

	The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire,security systems cut outs and the ceiling is finished with acrylic Emulsion Paint including surface preparation with two coats of putty, primer and sanding all complete. All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured.				
ii	MODULAR FALSE CEILING - ARMSTRONG / equivalent make				
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drwng. from FFL. Rate shall be inclusive of providing the total system with installation etcThe contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations (till Inauguration).	Sq Mts	31.00		
8	VERTICAL BLINDS				
	Providing and fixing Vertical blinds of approved design and shade by the Architect,incl all std fittings as per manufacturer's specification. The work to be completed as per specification and approval of the architect. (approved brand Vista, Hunter Dogulus)	Sq Mts	5.00		
9	GLASS SHELVES				
	Providing and fixing glass panes / shelves of required sizes with all edges neatly grinded, polished and fixed to the wall surfaces using SS D-brackets. The glass shall be 10mm thk plain glass of approved make. Item shall include all required arrangement / hardwares/ accessories to complete the job upto the satisfaction of bank / Architect. Note - For the purpose of contractor's payment, front elevation	Sq Mts	2.00		
10	CHEQUE DROP / SUGGESTION BOX (with glass front)				
	Supplying and fixing wall mounted Cheque Drop Box of outer size 10" (D) X 12" (W) X 20" (H) with front openable partlyglazed shutter, lock, slot for dropping cheques from top along with all required hardwares & accessories like SS handle, SS butt hinges etc to complete the job upto the satisfaction of the bank / Architect. The box shall be made out of 12mm thk approved plywood finished with 1mm thk approved laminate on outer faces & 0.8mm thk white laminate on all inner faces.	Nos	2.00		
11	NOTICE / PIN-UP BOARD				
	Providing & fixing Notice Board made of tag board of approved make & design of size 4'-0" X 3'-0" with powder coated aluminum border / frame. The board should be 3/4" thk straw board with velvet type fabric covering of Canara Bank blue shade.	Nos	2.00		
12	BOXING FOR ROLLING SHUTTER				
	Supply and installation of boxing of rolling shutter with 4mm ACP Sheet consisting of 3mm tk FRgrade mineral core Sandwiched between two aluminium sheets (.5mm thick) with 25 x 25 mm aluminium tube at spacing 600 x 600 of approved make.	Sq Mts	5.00		

13	PAINT WORK				
i	Providing and applying three coats of pre-approved Plastic acrylic emulsion paint to walls, partitions etc. including surface preparation with two coats of putty, primer and sanding all complete. With the necessary drying periods for each coat. The final finish should be of a uniform and neat finish to the satisfaction of the Architect. Cost to include for all heights and surfaces , complete in all respect (Low VOC contain paint) Make: ICI DULUX ,Asian Paints.	Sq Mts	10.00		
ii	Painting two coats of enamel paint (Asian/BERGER) including scrubbing, sand paper, making base applying primer etc complete in all respect in , grills etc.complete in all respect	Sq Mts	22.00		
14	Antitermite treatment (Pest Control) for entire floor area and hidden woodwork with 10 year Guarantee certificate on stamp paper complete.	Sq Mts	139.00		
	TOTAL OF INTERIOR & RENOVATION WORK (EXCLUDING GST)				
	Discount if any (Only on Excluding GST Amount Only)				
	Net Amount (After Discount if any - Excluding GST)				
	GST as Extra as applicable				
	Grand total with GST Amount				

Place :-

Date :-

Seal and Signature of the contractor with address