

BILL OF QUANTITY OF INTERIOR DESIGN AND FURNITURE WORKS FOR CANARA BANK, CPH AT VIJAYAWA

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
	FOURTH FLOOR INTERIOR (CPH)				
1	Providing and fixing ENTRANCE (3'-6"x7') DOOR and PARTITION (WITH TOUGHENED GLASS) Shall be 2'-6" wide Double leaf glass shutter. Door shutter made up of 12mm thick SGG SECURIT/AIS STRONGLAS- impact resistance glass with pencil polish edges all around. Etching details for glass door as per design, floor spring, bottom lock, center lock, SS brushed handle of 2'0" long 1" dia on both sides. specifications, patch fittings etc. as directed by Bank / Architect. complete as shown in drawing. (Bank logo to be etched on glass shutter and other etching to be done on fixed glass as directed by the bank .)	70	Sft		
2	Providing and fixing FULL HEIGHT PARTITION with GLAZED PANEL (With Door) in double skin of 9mm thk. BWR grade ply with 1.0mm thk shell finish laminate on both sides fixed to natural melamine polished Beach wood bottom, middle and top rail of 3" x 2" and concealed Aluminium section verticals of 2" x 1" at not more than 4'-0" apart including fitting door frame where indicated with beach wood frame of 4" x 2" complete as shown in drawing. Each cabin shall have one door 3'-0" x 7'-0" size with 6" handles on both sides, brass hinges, Door closure (heavy duty) of approved make & locking arrangements (the door to be made out of 32mm block board) . it shall be of natural melamine polished beach wood, above 3'-0" with 6mm plain float glass and 12mmx12mm BW beading, all in natural melamine mate polished, incl. fitting door frame where indicated with beach wood frame of 4" x 2" complete as shown in drawing. <u>(Verticals to go upto the RCC roof for support, but measurement rate shall be made only upto the false ceiling only and shall not incl. the door shutter which is a separate item).</u>	360	sft		
3	LOW HEIGHT with DOUBLE SKIN(3'-6" ht.) partition at work station, - Providing and Fixing low & Half height partitions 3' 6" with double skin panelling up to 3'-0" and 12mm thick clear float sandwich glass (as specified by banks engineer) above frame less on the top and sides and sturdily fixed at the bottom on a polished teakwood with D clip ,all complete job with all other specifications. Complete as shown in drawing.	890	Sft		
4	LOW HEIGHT with DOUBLE SKIN partition for the running table at VCIP room(4-6" ht.) - Providing and Fixing low & Half height partitions 4' 6" with double skin panelling up to 3'-0" and 12mm thick clear float sandwich glass (as specified by banks engineer) above frame less on the top and sides and sturdily fixed at the bottom on a polished teakwood all complete job with all other specifications. Complete as shown in drawing.	125	sft		
	LOW HEIGHT partition for the existing glazed portion of the building (4'-6" ht.) , - Providing and Fixing low height partitions 4' 6" (as specified by banks engineer) and sturdily fixed at the bottom on a polished teakwood all complete job with all other specifications. Complete as shown in drawing.	250	sft		
5	Providing and fixing FULL HEIGHT PARTITION solid in double skin of 9mm thk. BWR grade ply with 1.0mm thk shell finish laminate on both sides fixed to natural melamine polished Beach wood bottom, middle and top rail of 3" x 2" and concealed Aluminium section verticals of 2" x 1" at not more than 4'-0" apart including fitting door frame where indicated with beach wood frame of 4" x 2", complete as shown in drawing. (Verticals to go upto the RCC roof for support, but measurement rate shall be made only upto the false ceiling only and shall not incl. the door shutter which is a separate item).	550	Sft		

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
6	FALSE CEILING: Provided & fixing with Indian gypsum or equivalent suspended false ceiling two coat Luppam and two coat of acrylic emulsion paint. (in any shape as shown in drawing) which includes providing and fixing G.I perimeter channels of 0.55mm thk having one flange of 20mm & another flange of 30mm & a web of 27mm along the perimeter of the ceiling, screw fixed to the brick wall with the help of nylon sleeves & screws, at 610 mm centers. as per manufacturers spec.s, taping of joints and finishing. finally the board are to be jointed and finished so as have a flush lock which includes filling & finishing tapered square edges of the boards with jointing compound, paper tape and with one coat of lappam perfectly to level the surface, complete as shown in drawing.	720	Sft		
7	FALSE CEILING (GRID) : The grid false ceiling shall be provided in the Banking Hall, Manager's etc. Refer drwgs. No. 1-4-8. the ceiling height and level shall be provided at the perimeter. The minimum height of the ceiling cavity should be 100mm. All service fittings integrated within the suspended ceiling must be independently supported from the ceiling grid by a structure designed for the purpose. Ceiling tiles: shall be armstrong fine figured classic lite RH99 of 16mm thickness. Suspension system: shall be of armstrong trulok silhouette reveal profile grid system with 15mm flanges incorporating 3mm central recess in global white with black reveal. silhouette main runners and cross tees to have mitred ends and "birdsmouth" notches to provide mitred cruciform junctions.	1,800	Sft		
	Installation: main runners will be placed at 1200mm centres securely fixed to the structural soffit by approved hangers at 1200mm maximum centres and not more than 150mm from spliced joints. the last runner at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mm long cross tees to be interlock between main runners at 600mm centres to from 1200x600mm modules. cross tees 600mm require independent support. 600x600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200mm cross tees. the 1200mm cross tees to have central "birdsmouth" notches to facilitate fitting of 600mm cross tees. the perimeter trim to be armstrong trulok equal wall angle of white color secured to walls at 450mm maximum centres.complete as shown in drawing.				

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
8	Providing and Fixing the new work station as per the drawing (4'-0"/3'6"x2'-0"): table made out of 18 mm BWR grade ply board (approved make)structure with edges fixed with teak wooden lipping ,having officer table top 2'-6" from the ground level & 2'-6" clear top width. Each unit shall be provided with a sliding key board tray 2'-3" of wide with sliders, individual drawer with cupboard below the table along with locking arrangements aluminum handle, brass hinges etc the front back & top surface shall be laminated with 1.0mm thick gloss laminate (Bank colour).The internal surface shall be painted with two coats of enamel paint (VANILLACREAM, CODE -3229) of Asian paints, over a coat of primer. Provision for footrest of size 75mmx 38mm shall be made at the bottom. Wire manager shall be provided at the corner of the counter top. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing.	61	No		
9	AGM TABLE (6'-0"x3'-0"): Fabricating manger's Table made out of 18mm BWR Grade ply, having table top 2'-6" height from the ground level & 3'-0" clear top width. it will have a side table of size 1'-6" x 3'-0" Table shall be provided with a sliding keyboard tray 2'-3" wide with slider, 2nos drawers on either sides and cupboard below the drawer locking arrangements, aluminum handles, brass hinges etc all exposed surface shall be laminated with 1.0 mm thk rubber wood laminate. 12mm thk plain glass on table top as per shape with cutting for wire manager. The internal surfaces shall be painted with two coats of enamel paint over a coat of primer. Provision for c.p.u stand 1'-0" x 2'-0" & foot rest of size 75mm x 38mm shall be at bottom .wire manger shall be provided to the counter all exposed edges of the block board shall be provided with teak wood beading and polishing etc, complete. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing.	1	No		
10	Providing and fixing LOW HT STORAGE/ GENERAL CUPBOARDS with 19mm BWR grade ply wood structure, shutters & backing with edges fixed with 6mm teak wooden lipping .the unit shall be provided with drawer, shelves etc. all necessary fixtures like aluminum door handles, brass hinges sliders for drawers, magnetic catcher, locks etc. all exposed surface shall be laminated with 1.5 mm thk approved colour laminate. The internal surfaces shall be painted with two coats of enamel paint over a coat of primer. All exposed edges of the block board shall be provided with (1"x 3/4") teak wood beading and polishing etc, complete as shown in drawing.	15	Rft		
11	Wall & Column Paneling laminate finish: Shall be made up of Concealed Aluminium section verticals 2"x1" internal frame work. The framing shall be fixed at intervals of 2'0" c/c. the framing shall be fixed with 6mm thick BWR grade ply and 4mm ply as to form grooves finished with 1.00mm thick laminate of approved color with 4mm groove forming 1'6"-2'0" panels. 1/2"x1/2" teak wood beading shall be fixed on all the corners as to form a design and shall be melamine polished. the skirting shall be finished with 3" wide 1.00mm thick brushed SS laminate of euro make.	1,175	Sft		
12	Providing and fixing FLUSH DOORS of 35mm thk with 1.0 mm thk. shell finish laminate both sides with TW polished edge beading to all in exposed edges, hole cuttings in any shape and size with 6mm glass fixing to TW beading in the door including all accessories of a approved brand such as locks, handles, door closure(reputed make) etc., complete as shown in drawing.	130	Sft		

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
13	ROLLER BLINDS: Providing vertical blinds of (ivory) guardian tilter wand cord lock 4" wide strip complete as per architect direction.	440	Sft		
14	Providing and fixing covering to rolling shutter and shutters for covering electrical panel board, etc., with 18mm BWR ply with 1mm thick shell finish laminate of approved shade and make including painting of inside with primer and two coats of synthetic enamel paint, and providing teak wood beading to all exposed edges including all accessories hinges, handles, ballcatches, etc., complete.	60	Sft		
15	Painting of internal wall (with Putty where ever required) & two coats of plastic emmulsion paint of approved Make/ brand and approved colour (Including ATM)	1,039	SFT		
A	TOTAL AMOUNT FOR BRANCH INTERIOR WORKS :				
	TOTAL AMOUNT for Interior Works For CPH(FOURTH FLOOR):				
	GST 18% EXTRA				