



PREMISES & ESTATE SECTION, CIRCLE OFFICE TC NO. 26/173 (1), PB NO 159, M G ROAD  
THIRUVANANTHAPURAM - 695 001  
TEL: 0471-2331340 email: pecotvm@canarabank.com

**TENDER DOCUMENT  
(FOR FURNISHING WORKS)**

**AT  
CANARA BANK  
PADINJARE VEMBALLUR BRANCH**

**NOTICE INVITING THE TENDER , GENERAL RULES & INSTRUCTIONS  
GENERAL CONDITIONS, SPECIAL CONDITIONS, OFFER LETTER,  
APPENDICES, SCHEDULE OF QUANTITIES.**

SIGNATURE OF TENDERER

## CONTENTS

<u>NOTICE INVITING THE TENDER</u> .....	1
<u>GENERAL RULES &amp; INSTRUCTIONS TO TENDERERS</u> .....	2
<u>GENERAL CONDITIONS OF CONTRACT</u> .....	6
<u>SPECIAL CONDITIONS OF CONTRACT</u> .....	26
<u>OFFER LETTER</u> .....	28
<u>APPENDIX-1 - IMPORTANT TERMS</u> .....	30
<u>APPENDIX-2 - RUNNING A/C BILL FORMAT</u> .....	31
<u>APPENDIX -3 - CERTIFICATE FOR PAYMENT</u> .....	32
<u>APPENDIX- 4 - MEASUREMENT CERTIFICATE</u> .....	33
<u>APPENDIX-5 - CONTRACT AGREEMENT FORMAT</u> .....	34
<u>APPENDIX -6 - INDEMNITY BOND FORMAT</u> .....	36
<u>APPENDIX-7 - FORMAT FOR RATE ANALYSIS OF ITEMS</u> .....	37
<u>APPENDIX-8 - LIST OF RELATIVES WORKING IN CANARA BANK</u> .....	38
<u>APPENDIX -9 - LIST OF APPROVED MAKES</u> .....	39
<u>PRICE BID</u> .....	41

**NOTICE INVITING THE TENDER**

To,

M/s

Sealed tenders on item rate basis are invited from Bank's Panel Contractors in **Class A, B & C (15 Lakhs and above)** of Trivandrum Circle and **Class A & B (30 Lakhs and above)** contractors of Madurai, Mangalore and Chennai Circle for the **Furnishing works at Padinjare Vemballur Branch**. Tender Documents may be obtained from Canara Bank, Premises & Estate Section, Circle Office, Thiruvananthapuram during working hours till **06.06.2024**.

**Earnest Money Deposit** : **NIL**

**Period of completion** : **45 days**

**Last date, time and place for Submission of tender** : **On or before 3.00PM, 06.06.2024 to**  
**The Assistant General Manager**  
**Canara Bank**  
**Premises & Estate Section**  
**Circle Office, Thiruvananthapuram**

**Time and date of opening of tender** : **3.30 PM on 06.06.2024**

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**ASSISTANT GENERAL MANAGER**  
**Canara Bank**  
**Premises & Estate Section**  
**Circle Office, Thiruvananthapuram**

Date: **31.05.2024**

**SIGNATURE OF TENDERER**

## GENERAL RULES & INSTRUCTIONS TO TENDERERS

- 1) The completed Tender documents comprising of Notice Inviting the Tender (NIT), General rules & Instructions, General conditions of tender, Special conditions, Offer Letter, Appendices and Schedule of quantities, drawings, should be submitted to the Manager at the address given in the Tender Notice. The Tender document should be **sealed in** an envelope super scribed as "Tender for Interior furnishing works of **Padinjare Vemballur Branch**". The Tenderer's name and address should also be put on the envelope.
- 2) Last date for receipt of tenders: As stated in the tender notice.
- 3) The Tenderer are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of the site and dimensions, the means of access to the site, availability of materials and obtain all necessary information's as to risks, contingencies and other circumstances which may influence or affect their tender.
- 4) Tenderer should ensure that their tenders are submitted before the date and time specified above.
- 5) Tenderer are requested to put their firm's signature on each page of the tender documents as a token of acceptance.
- 6) Tenderer should fill in all the relevant blanks and put their signature in the relevant places indicated in the documents.
- 7) It will be obligatory on the part of the Tenderer to tender and sign the tendered documents for all the component parts and that, after the work is awarded, he / they will have to enter into an agreement for each component with the competent authority of the Employer.
- 8) The Tenderer should quote in figures as well as in words the rate, and amount tendered by them. The amount for each item should be worked out and the requisite totals given. The rates quoted shall be all inclusive rates for the item of work described, including materials, labour, tools & plant, carriage & transport, supervision, overheads & profits, taxes, VAT, service tax, cess, fees, mobilizing and other charges whatsoever including any anticipated or un-anticipated difficulties, etc. complete for proper execution of the work as per drawings and specifications and no claim whatsoever for any extra payment shall be maintainable.
- 9) When a Tenderer signs a tender in an Indian language, the tendered amount and the total amount tendered should also be written in the same language. In the case of illiterate Tenderer the rates or the amounts tendered should be attested by a witness.

SIGNATURE OF TENDERER

- 10) The Schedule of Quantities should be filled as follows:
- a. The “Rate” Column to be legibly filled in ink in both figures and words.
  - b. ‘Amount’ column to be filled for each item and the total amount for each trade to be given.
  - c. All corrections/ over writings are to be initialed. Failing which the tender shall be rejected.
  - d. All the items of the schedule of quantities shall be filled, failing which the tender shall be rejected.
  - e. Tenderer’s signature to be put on each page of the Schedule of quantities and in the “Abstract Sheet”.
  - f. The “Amount” column for alternative items for which the quantities are mentioned should be filled up.
  - g. The “Rate” column for "Rate only" items should be filled up.

Special care should be taken to write the rates in figures as well as in words and the amounts in figures only, in such a way that interpolation is not possible. The total amount should be written both in figures and in words.

- 11) No alterations or additions are to be made by the Tenderer in the tender document. Violation of this instruction will attract rejection of the tender at the discretion of Architect/Bank.
- 12) Tender shall be quoted on prescribed Form only and quoting in any other form will be rejected. All rates shall be quoted on the proper form of the tender alone. Quoted rates and units different from prescribed in the tender schedule will be liable for rejection.
- 13) Earnest money accompanying the tender will be accepted only in the form of Crossed Demand Draft on any of the Nationalized Banks/ State bank drawn in favour of “**Canara Bank, Premises & Estate Section, Circle Office, Thiruvananthapuram**” payable at Thiruvananthapuram” & not in favour of any other authority. Any tender, which is not accompanied by Earnest Money Deposit in the form of DD, shall be summarily rejected.
- 14) The EMD of the Tenderer whose tender is accepted, shall be forfeited in full in case he does not remit the Initial Security Deposit or execute the agreement or submit the Indemnity Bond within the period stipulated period mentioned in the award letter.
- 15) The Sealed Envelopes shall be **opened at the specified time** in the presence of the

SIGNATURE OF TENDERER

tenderer or their authorized representatives if they desire to attend. Bank shall open the tenders on the specified date & time even if the tenderer or their authorized representatives are not present.

- 16) The tender for the work shall not be witnessed by a tenderer or tenderers' who himself / themselves has / have tendered or who may and had/have tendered for the same work. Failure to observe this condition would render tenders of the tenderers tendering as well as witnessing the tender liable to summary rejection.
- 17) The Tenderer is required to check the numbers of the pages and should any be found missing or in duplicate, or the figure or writing indistinct, he must inform the Architect/ Bank at once and have the same rectified. Should the tenderer be in doubt about the precise meaning of any item or any provision or if he wants any clarification, he must inform the Architect/Bank in writing at least one week before the scheduled date of opening. No claim will be allowed in respect of errors in the Tenderers tender due to any mistake in the Schedule of Quantities, which should have been but was not rectified in the manner described above.
- 18) The articles of Agreement should not be filled. It is only a format for information. The agreement shall execute on this format with the successful tenderer only.
- 19) Rate in words will be taken in correct over rate in figures. If the amount of an item does not tally with the rate quoted in words, the rate quoted in words shall be taken as correct.

Contractors are forewarned that no errors whatsoever arithmetical or otherwise will be permitted in their tenders. Tenders containing many errors are liable to be rejected at the discretion of Bank.

- 20) Tenderers should note that their tenders should remain open for consideration for a minimum period of **120 days** from the date of the opening of tenders.
- 21) If any tenderer withdraws his tender before the said period or makes any modifications in the terms and conditions of the tender, or quoted rates then the Employer shall, without prejudice to any other right or remedy, be at liberty to **forfeit full value** of the earnest money as aforesaid.
- 22) A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charges consequent on any misunderstanding or otherwise shall be allowed. Submission of a tender by a Tenderer implies that he has read this notice and all other Tender/ contract documents and has made himself aware of the scope and specifications of the work to be done and local conditions and other factors bearing on the execution of the work.
- 23) All the parts of this tender document shall form a part of the contract document.

SIGNATURE OF TENDERER

- 24) The Tenderer shall agree that until a formal agreement on stamp paper is prepared and signed, this tender shall constitute a binding contract between the Tenderer and the Employer.
- 25) On acceptance of the tender, the name of the accredited representative(s) of the Tenderer who would be responsible for taking instructions from the Employer shall be communicated to the Employer.
- 26) The Bank reserves the right to accept any tender or accept tenders in part or to reject any or all tenders without assigning any reasons thereof and will not be liable to offer any explanation whatsoever.
- 27) Canvassing in connection with tenders is strictly prohibited and the tenders submitted by the Tenderer who resort to canvassing will be liable for rejection.
- 28) Tenderers are requested to note that non-compliance of the above instructions is liable to render rejection of their Tender.
- 29) EMD of unsuccessful tenderers will be refunded without any interest.

ASSISTANT GENERAL MANAGER  
Canara Bank Premises & Estate Section  
Circle Office, Thiruvananthapuram

SIGNATURE OF TENDERER

## GENERAL CONDITIONS OF CONTRACT

### 1. INTERPRETATION

In construing these conditions, the specifications, the schedule of quantities, tender and Agreement, the following words shall have the meaning herein assigned to them except where the subject or context otherwise requires.

**Employer or Bank:** The term "Employer " or "Bank" shall denote CANARA BANK with their Head Office at BANGALORE represented by Assistant General Manager, Canara Bank, Premises & Estate Section, Circle office, Thiruvananthapuram and any of its employees or representative authorized on their behalf.

**Architects:** The term "Architects" shall mean ..... Or in the event of his/their ceasing to be the Architects for the purpose of this contract such other person/s the Employer shall nominate for the purpose.

**Site Engineer:** The term "Site Engineer" shall mean authorised Engineer appointed by Architect or Bank for day-to-day supervision of works at site as per tender terms.

**Contractors:** The term "Contractor"," Bidder" or "Tenderer" shall mean \_\_\_\_\_ (Name and address of Contractor) and his/their heirs, legal representatives, assigns and successors.

**Site:** The "site" shall mean **PADINJARE VEMBALLUR BRANCH, CANARA BANK, BUILDING NO: 381/B, SREENARAYANAPURAM PANCHAYATH, KODUNGALLUR TALUK, THRISSUR**, where the renovation works are to be carried out.

**Drawings:** "Drawings" means the drawings referred to in the Specification and any modification of such drawings approved in writing by the Architect/ Bank and such other drawings as may from time to time be furnished or approved in writing by the Architect/ Bank.

**Work / Works** shall mean the work or works to be executed or done under this contract and shall include materials, apparatus, equipment, plant, fittings and other things for incorporation in the works.

**Contract** means the contract effected by the contractor's Tender and the Employer's acceptance thereof comprising (in addition to the Tender and Acceptance) the priced Schedule of Quantities and Schedules, Schedules of particulars (if any), Specifications and Drawings, these General Conditions of Contract, Special Conditions contained in, Appendices, Annexure or attached to any of the forgoing documents, any alterations agreed in writing between the parties before the formal acceptance of the Tender, all these documents taken together, shall be deemed to form one contract and shall be complementary to one another.

SIGNATURE OF TENDERER

**"Technical Specification"** means the specification annexed to or issued with this tender or detailed in the schedule of quantities.

**"Approved"** means approved in writing including subsequent written confirmation of previous verbal approval and "approval" means approval in writing including as aforesaid.

**'Market rate'** means the rate as prevailing in the market and recommended by the Architect and as approved by the Employer on the basis of cost of materials, labour, plant etc inclusive of any tax, duty, octroi etc. at the time of execution of work.

**"The Schedule of Quantities"** or "Priced Schedule of Quantities" shall mean the schedule (or bill) of quantities with specifications as specified and forming part of this contract.

**"Act of Insolvency"** shall mean any act such as defined by the Presidency Towns Insolvency Act or in Provincial Insolvency Act or any amending statutes.

## 2. SCOPE OF WORKS:

The work consists of **Interior furnishing of the Bank's above mentioned branch/office/ATM premises** in accordance with the "Schedule of Quantities". Employer/Architects may in their absolute discretion issue further and/or written instruction, details, directions & explanations, which are, hereafter collectively referred to as "The Employer's instructions" in regard to:

- a) The variation or modification of the design quality or quantity of works or the addition or omission or substitution of any work.
- b) Any discrepancy in the drawings or between the schedule of quantities and/or drawings and/or specification.
- c) The removal from the site of any defective material brought thereon by the contractor and the substitution of any other material thereof.
- d) The demolition removal and/or re-execution of any work executed by the contractor/s.
- e) The dismissal from the work of any persons employed there upon.
- f) The opening up for inspection of any work covered up.
- g) The rectification and making good of any defects under clauses hereinafter mentioned and those arising during the defect liability period.

The work is to be carried out in accordance with drawings, specifications, the schedule of quantities and any further drawings, which may be given by the Architect/ Bank during the execution of the work.

In case any detailed Working/Fabrication/Shop Drawings are necessary, contractor shall prepare such detailed drawings and/or dimensioned sketches thereof and get approved by the

SIGNATURE OF TENDERER

Bank / Architect prior to taking up such work.

The contractor shall ask in writing for all clarifications on matters occurring anywhere in drawings for additional instructions at least 10 days ahead from the time when it is required for implementations so that the Employer may be able to give decision thereon.

No works, for which rates are not specifically mentioned in the priced schedule of quantities, shall be taken up without written permission of the Employer/Architects. Rates of items not mentioned in the priced schedule of quantities shall be fixed by the employer in consultation with the Architects as provided in Clause "variation". Regarding all factory made products for which **ISI marked products** are available, only products bearing ISI marking shall be used in the work.

The whole work including all extra and additional items if any is to be completed within the period of completion as stated in Notice Inviting the Tender and the Contractor will be required, if necessary to work overtime to fulfill the Banks/Architect's instruction to complete the work by the stipulated date. No extra payment will be allowed on the quoted rates for such overtime work.

The existing passenger lifts will not be permitted for shifting of materials, debris etc.

### **3. TENDER**

The tenderers should note that the tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self-supporting.

The works will be paid for as "measured work" on the basis of actual work done on item rate basis and not as "lump sum" contract as per the rate quoted in the Schedule of quantities.

All items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection.

In the case of items of lump-sum charges in the tender in respect of any item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum rates as will be assessed to be payable by the Employer/Architects.

### **4. AGREEMENT, INDEMNITY BOND**

The successful contractor shall sign a Contract Agreement as per format enclosed as **Appendix 5** and shall pay for all stamps paper charges and legal expenses, incidental thereto. The contractor shall submit Indemnity Bond as per format enclosed as **Appendix 6**.

The contract agreement and Indemnity bond shall be executed within **7 days** from the from the date of receipt of letter of acceptance of tender, failing which the Employer at his discretion, without prejudice to any other rights/remedies available under the terms of

SIGNATURE OF TENDERER

this Contract may revoke the letter of acceptance and forfeit the Earnest money deposit furnished along with the tender.

#### **5. PERMITS AND LICENCES**

Permits and Licenses for release of materials, which are under Government control, shall be arranged by the contractor. The Employer may render necessary assistance, sign any forms or applications that may be necessary but shall not be responsible for actual procurement or for any delay in procurement.

It may be clearly understood that no compensation or additional charges can be claimed by the contractor for non-receipt of any controlled materials in due time on this account or according to his own requirements.

The Employer/Architects shall be indemnified against all Government or legal actions for theft or misuse of controlled materials in the custody of the contractor.

#### **6. GOVERNMENT AND LOCAL RULES**

The contractor shall confirm to the provisions of all local laws and Acts relating to the work and to the Regulations etc., of the Government and Local Authorities. The cost, if any, shall be deemed to have been included in quoted rates, taking into account all liabilities for licenses, fees. The tenderer shall indemnify the Employer against any such liabilities in compliance of the local acts, rules.

#### **7. QUOTED RATES**

The rates shall be as per the Schedule of Quantities and include the following:

- (i) The rates quoted by the contractor shall be held to include for providing all materials, testing of materials, labour and fixing all scaffolding, conveyance and delivery, unloading, carrying in storing, hoisting, all labour, setting, fitting and fixing in position making, cutting, wastages, return of packing and all materials and labour and cleaning of work place, everything else necessary for the proper completion of each item of work including over- heads and profits.
- (ii) The rates must include in their tender rates quoted for all duties royalties, cess, sales tax, VAT, service tax or any other taxes or local charges if applicable. Any variations in the above shall not be paid. No extra claim on this account will in any case be entertained.
- (iii) The rates quoted by the contractor should cover for work at all heights and levels for all items of work under this contract. Lifting of materials will not form any criteria for claiming extra payment.

**FUNCTIONING BRANCH - Timings of work - Cleaning of site on daily basis** wherever the works are carried out in functioning branch or office the timings of work shall be beyond the office hours as fixed by the Employer.

The works, all cuttings, waste materials, rejected materials and other rubbish as it accumulates shall be cleaned from time to time during the progress of the work and at completion of **each day's** work and to be cleared and carted away from the branch premises / site.

SIGNATURE OF TENDERER

Contractor's quoted rates shall allow for the above factors also.

### **8. QUANTITY OF WORK TO BE EXECUTED**

The quantities shown in the schedule of quantities are only approximate and are intended to cover the entire work but the Employer reserves the right to execute only a part or the whole or any excess thereof without assigning any reason therefore. In case of increase it shall be as per the variation clause.

### **9. OTHER PERSONS ENGAGED BY THE EMPLOYER**

The Employer reserves the right to execute any part of the work included in this contract or any work, which is not included in this contract by other Agency or persons, and contractor shall allow all reasonable facilities and use of his scaffolding for the execution of such work. The main contractor shall extend all co- operation in this regard.

### **10. EARNEST MONEY, SECURITY DEPOSIT & RETENTION MONEY**

The tenderer will have to deposit the amount specified in the NIT at the time of submission of tender as Earnest Money deposit. No interest shall be paid on the Earnest Money deposit.

The successful tenderer to whom the contract is awarded will have to deposit as Initial security deposit a further sum to make up 2% of the value of the accepted tender including the Earnest Money. The initial Security Deposit will have to be made within **7 days** from the date of receipt of letter of acceptance of tender, failing which the Employer at his discretion, without prejudice to any other rights/remedies available under the terms of this Contract may revoke the letter of acceptance and forfeit the Earnest money deposit furnished along with the tender. No interest shall be paid on the Initial security deposit.

Apart from the initial security deposit made as above, retention money shall be deducted from progressive running bills @ 8% of the gross value of each running bill till the **total security deposit** ,( i.e., the initial Security Deposit plus the retention money) equals the amount mentioned below :

- a) 10% on the first rupees one lakh of the estimated cost of work.
- b) 7.5% on the next rupees one lakh of the estimated cost of work
- c) 5% on the remaining amount of the estimated cost of work.

The total security deposit amount will be refunded to the contractor, after de- ducting any sum due from the contractor on any account under this contract,

14 (fourteen) days after the end of **defects liability period** provided he has satisfactorily rectified all the defects in accordance with the conditions of the con- tract. No interest is allowed on retention money & total security deposit.

### **11. CONTRACTOR TO PROVIDE EVERYTHING NECESSARY**

The contractor shall provide everything necessary for the proper execution of the work

SIGNATURE OF TENDERER

according to the intent and meaning of the drawings, schedule of quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Employer/ Architects whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of work within the contemplation of the contract, and beyond the unit price no extra payment will be allowed for incidental or contingent work, labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in the tender documents.

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackle, machineries and equipments and all the necessary centering, scaffolding, staging, planking, timbering, watching and lighting by night as well as by day required not only for the proper execution and protection of the said work **but also for the protection of the public and safety of any adjacent walls, houses, building, all other erections, matters and things** and the contractor shall take down and remove any or all such centering, scaffolding, planking, timbering, strutting, shorting etc., as occasion shall be required or when ordered so to do, and shall fully reinstate and make good all matters and things disturbed during the execution of works to the satisfaction of the Employer/ Architects.

The contractor shall at all times give access to **workers employed by the Employer** or any men employed on the premises and to provide such parties with proper sufficient and if required, special scaffolding, hoists and ladders etc. in any work, where directed by the employer as may be required to enable such workmen to lay or fix pipes, electrical wiring, special fittings etc. The quoted rates of the tenderers shall accordingly include all these above-mentioned contingent works.

## **12. TIME OF COMPLETION, EXTENSION OF TIME & PROGRESS CHART**

**Time of completion:** The entire work is to be completed in all respects within the stipulated period stated in the Notice Inviting the tender.

The order to commence the works shall be given by the Bank only after depositing the Initial security deposit, signing of agreement, submission of Indemnity bond, submission of Insurance.

Time is the essence of the contract and shall be strictly observed by the contractor.

**Extension of Time:** If in the opinion of the Employer/ Bank the works were delayed for reasons beyond control of the contractor, the Bank may grant a fair and reasonable extension of time for completion of the contract works.

Request for extension of time, to be eligible for consideration, shall be made by the Contractor in writing within fourteen days of the happening of the event causing delay to the Architect/ Bank. The Contractor shall also, if practicable, indicate in such a request the total period for which extension is desired, overlapping period, if any, with earlier events causing delays, net

SIGNATURE OF TENDERER

extension required.

In such case, the Employer may give a fair and reasonable extension of time for completion of work. Such extension shall be communicated to the contractor by the Employer in writing, within **15 days** of the date of such request.

While granting extension, the Employer shall notify the contractor the period of time which will not qualify for levy of liquidated damages.

For the period in excess of original stipulated time period and authorised extension of time (i.e. period not qualifying for levy of liquidated damages), granted by the Employer, the provision of liquidated damages as stated under **Clause 13** hereof will become applicable.

However, the contract shall remain in force even for the period beyond the due date of completion irrespective whether the extension is granted or not.

**Progress of work:** The contractor shall maintain proportionate progress on the basis of a Programme Chart submitted by the contractor immediately before commencement of work and agreed to by the Employer/ Architects. Contractor should also include planning for procurement of scarce material well in advance and reflect the same in the programme chart so that there is no delay in completion of the project.

### **13. LIQUIDATED DAMAGES**

Time is the essence of the contract. The completion of the **works** is essential to comply with various requirements of the bank. Thus the contractor shall be aware and take note that non-completion of the works will affect the Banks committed programs and thus the loss by way delayed completion of related works etc, are invaluable and cannot be easily assessed. Therefore, it is part of the agreed terms that in the event of any delay in completion of the work, the Bank is liable to charge the Contractor without the necessity of providing for any details of such losses suffered by the Bank.

Thus if the Contractor fails to complete the works within the time for completion stated in the Notice Inviting the Tender or within any extended time under **Clause 12** hereof, the Contractor shall pay the Employer the sum at the rate of **1%(one per cent) of the Contract Value per week of delay subject to a limit of**

**10%(ten percent) of the Contract Value as "Liquidated damages"** for the period during which the said works shall so remain incomplete or the Employer may deduct aforesaid sum towards such damages from any monies due to the Contractor.

For this purpose the term 'Contract Value' shall be value at the contract rates of the work as ordered / accepted.

The Employer shall have the right to adjust, / set-off against any sum payable to the contractor under this or any other contract with the Employer anywhere in India/outside India.

SIGNATURE OF TENDERER

#### **14. PROTECTION TO WORKS, STORAGE**

**Protective Measures:** The contractor shall make suitable arrangements for watching and protecting the works and surrounding property by day, by night, on Sundays and other holidays, on round the clock basis and no extra will be paid by Bank for such services.

Contractor shall indemnify the Employer against any possible damage to the building, roads or members of the public in course of execution of the work.

Should the work be suspended by reason of rain, strike, lockouts or any other cause, the contractor shall take all precautions necessary for the protection of work and at his own expenses shall make good any damage arising from any of these causes.

**Storage of materials:** The contractor shall provide adequate protection of the materials, work etc., and also other work that may be executed on the site.

All offensive, inflammable materials shall not be stored in the premises.

#### **15. NOTICE AND PATENTS OF APPROPRIATE AUTHORITY AND OWNERS**

The contractor shall conform to the provisions of any Acts of the Legislature relating to the work, and to the Regulations and Bye-laws of any authorities, and /or any water, lighting and other companies, and/or authorities with whose systems the structures were proposed to have connection and shall before making any variations from the drawings or specification that may be associated to so conform, give the Employer/Architects written notices specifying the variations proposed to be made and the reasons for making them and apply for instruction thereon. The Employer/Architects on receipt of such intimation shall give a decision within a reasonable time.

The contractor/s shall arrange to give all notices required for by the said Acts, Regulations or Bye-laws to be given to any authority, and to pay to such authority or to any public officer all fees that may be properly chargeable in respect of the work and lodge the receipts with the Employer.

The contractor shall indemnify the Employer against all claims in respect of patent rights, royalties, damages to buildings, roads or members of public in course of execution of work and shall defend all actions arising from such claims and shall keep the Employer saved harmless and indemnified in all respects from such actions, costs and expenses.

#### **16. SETTING OUT WORKS**

The contractor shall set out the works and shall be responsible for the true and perfect setting out of the work and for the correctness of the positions, levels, dimensions and alignment of all parts thereof. If at any time, any error shall appear during the progress of any part of the work, the contractor shall at his own expenses rectify such error, if called upon to the satisfaction of the Employer. The contractor shall further set out the works to the alternative positions at the site until one is finally approved and the rates quoted in his tender should

SIGNATURE OF TENDERER

include for this and no extra on this account will be entertained.

### **17. MATERIALS, WORKMANSHIP, SAMPLES OF MATERIALS**

All the materials (except where otherwise described) stores and equipment required for the full performance of the work under the contract must be provided through normal channels and must include charge for import duties, sales tax, octroi, VAT, service tax and other charges and must be the best of their kind available and the contractor/s must be entirely responsible for the proper and efficient carrying out of the work.

The work must be done in the best workman like manner.

**Samples** of all materials to be used must be submitted to the Employer/Architects when so directed by the Engineer/ Architects and written approval from Employer/Architects must be obtained prior to placement of order for the material.

Before ordering any material, the Contractor shall get samples of the materials approved from the Bank/ Architect well in time. The samples of materials shall be got tested from approved laboratories at the contractor's cost before approval if ordered by the Bank/ Architect. No claim will be allowed for delay to the progress of work caused by tests. If called upon by the Bank, the contractor shall produce proof for having arranged for the supply of materials well in time.

### **18. REMOVAL OF IMPROPER WORK, RECTIFICATION, REJECTED MATERIALS**

The Employer shall during the progress of the work have power to order for removal of work within such reasonable time or times as may be specified in the order of any materials which in the opinion of the Employer/Architects are not in accordance with specifications or drawings or instructions.

All materials / or workmanship which in the opinion of the Bank are / is defective / not conforming to specifications / drawings or un-suitable, shall be re- moved immediately from the site and shall be substituted/ reworked with proper material and / or workmanship forth with as per drawings, specifications at the cost of the contractors .

In case the contractor refuses to comply with the orders of the Employer/ Architect, then the Employer shall have the power to employ and pay other agencies to carry out the work and all expenses consequent thereon or incidental thereto as certified by the Employer/ Architects shall be borne by the contractor or may be deducted from any money due to or that may become due to the contractor under this contract or any other contract. No certificate, which may be given by the Architects/ employer, shall relieve the contractor from his liability in respect of unsound work or bad materials.

### **19. ACCESS**

Any authorized representative of the Employer/ architect shall at all reasonable times have free access to the works and/or to the workshop, factories or other places where materials are being prepared or constructed for the work and also to any place where the materials are lying or from where they are being obtained, and the contractor shall give every facility to the

SIGNATURE OF TENDERER

Employer or their representatives necessary for inspection and examination and test of the materials and workmanship. Except the representatives of the Employer no person shall be allowed at any time without the written permission of the Employer.

## **20. SITE ENGINEER**

The term 'Site Engineer' shall mean the person appointed and paid by the Employer/Architect to superintend the work. The contractor shall afford the Site Engineer every facility and assistance for examining the works and materials and for checking and measuring work and materials.

The work will from time to time be examined by the Architects, Engineer from the Premises Department of the Employer and the Site Engineer. But such examination shall not in any way exonerate the contractor from the obligation to remedy any defects, which may be found to exist at any stage of the work or after the same is complete. Subject to the limitations of this clause the contractor shall take instructions only from the Architects/Employer.

## **21. CONTRACTOR'S EMPLOYEES**

The contractor shall employ technically qualified staff and competent supervisors for the work who shall be available (by turn) throughout the working hours to receive and comply with instructions of the Employer/Architects. The contractor shall employ in connection with the work, persons having the appropriate skill or ability to perform their job efficiently.

No labourer below the age of Eighteen years shall be employed on the work.

Any labourer supplied by the contractor to be engaged on the work on day work basis either wholly or partly under the direct order or control of the Employer or his representative shall be deemed to be a person employed by the contractor.

The contractor shall comply with the provisions of all labour legislation including the requirements of

- a) The Payment of Wages Act
- b) Minimum wages Act
- c) Employer's Liability Act
- d) Workmen's Compensation Act
- e) Contract Labour (Regulation & Abolition) Act, 1970 and Central Rules 1971
- f) Apprentices Act 1981
- g) Any other Act or enactment relating thereto and rules framed there under from time to time.
- h) Indian Electricity Act (IE Act) and follow the rules.

The contractor shall keep the Employer saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the Employer in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any Health Officer of the State or any local authority or of the Employer regarding the maintenance of proper environmental sanitation of the area where the contractor's labourers are housed or accommodated, for the prevention of small pox, cholera, plague, typhoid, malaria and other contagious diseases. The contractor shall provide, maintain and keep in good sanitary accommodation and provide facilities for pure drinking water at all times of the use of men engaged on the works and shall remove and clear away the same on completion of the works. Adequate precautions shall be taken by the contractor to prevent nuisance of any kind on the works or the lands adjoining the same.

The contractor shall arrange to provide first aid treatment to the labourers engaged on the works. He shall within 24 hours of the occurrence of any accident at or about the site or in connection with execution of the works, report such accident to the Employer and also to the competent authority where such report is required by law.

The contractor shall pay rates of Wages and observe hours of work and conditions or employment according to existing rules under Minimum Wages Act. Further, it shall be contractor's responsibility to ensure that he pays his workmen wages which are not lower than the minimum prescribed by the Union Government and State Government in which area this contract is being operated.

## **22. DISMISSAL OF WORKMAN**

The contractor shall on the request of the Employer immediately dismiss from works any person employed thereon by him, who may in the opinion of the Employer be unsuitable or incompetent or who may misconduct himself. Such discharges shall not be the basis of any claim for compensation or damages against the employer or any of their officer or employee.

## **23. DAMAGE TO PERSONS AND PROPERTY INSURANCE ETC.**

The contractor shall be responsible for all injury to the work or workmen, persons, animals or things and for all damages to the structural and/or decorative part of property which may arise from the operations or neglect of himself or of any sub-contractor or of any of his or a sub-contractor's employees, whether such injury or damage arise from carelessness, accident or any other cause whatsoever in any way connected with the carrying out of this contract. The clause shall be held to include inter-alia, any damage to buildings whether immediately adjacent or otherwise, and any damage to roads, streets, foot paths or ways as well as damages caused to the buildings and the works forming the subject of this contract by rain, wind or other inclemency of the weather. The contractor shall indemnify the Employer and hold harmless in respect of all and any expenses arising from any such injury or damages to persons or property as aforesaid and also in respect of any claim made in respect of injury or damages under any acts of compensation or damage consequent upon such claim. **The contractor shall submit an indemnity bond in Bank's approved proforma (enclosed under Appendix-6) in a stamp paper. Indemnify the Bank / Architect from any damages, prosecution, other legal suits and claims arising out of any mishaps occurring at the site due to faulty work, faulty construction and for violating rules and regulations for which the contractor shall be solely responsible.**

The contractor shall reinstate all damage of every sort mentioned in this clause, so as to deliver

SIGNATURE OF TENDERER

the whole of the contract works complete and perfect in every respect and so as to make good or otherwise satisfy all claims for damages to the property or third parties.

The contractor shall affect the necessary insurance and indemnify the Employer / Architect entirely from all responsibility in this respect. The insurance must be placed with a company approved by the Employer and must be effected **jointly in the name of the contractor and the Employer and the policy lodged with the latter**. The scope of insurance is to include damage or loss to the works itself till this is made over in a complete state and also the workmen/ labours/ supervisors employed in the work. Insurance is compulsory and must be affected from the very initial stage before commencement of the work.

The contractor shall also be responsible for anything, which may be excluded from damage to any property arising out of incidents, negligence or defective carrying out of this contract.

The Employer shall be at liberty and is hereby empowered to deduct the amount of any damages, compensations, costs, charges and expenses arising or accruing from or in respect of any such claim or damages from any sums due or to become due to the contractor.

#### **24. INSURANCE**

The Contractor shall, at his own expense insure the works , effect and maintain till the completion of the contract a **Contractors All Risks Policy (CAR)** for Insurance, with an insurance company approved by the Employer, for the full amount of the contract .The scope of the cover shall include fire, lightning, explosion, crashing, aircraft, extinguishing water or other fighting measures, flood, inundation , rain, windstorm of any kind, earthquake, subsidence, landslide, rockslide, bad workmanship, lack of skill, negligence , malicious acts or human error, additional cover for third party liability and surrounding properties. The CAR shall be held in the joint names of the Employer and the Contractor (the name of the former being placed first in the policy.) with Employer as beneficiary against all risk as per the standard all risk policy for Contractors and deposit such policy or policies with the Employer with **7(seven)** days from the date of receipt of the letter of acceptance of tender.

The Contractor shall also indemnify the Employer against all claims which may be made upon the Employer, whether under the Workmen's Compensation Act or any other statute in force, during the currency of this contract or at Common Law in respect of any employee of the Contractor or of sub- Contractor and shall be at his own expense obtain, **effect and maintain until the completion of the Contract a policy of Insurance against such risk in respect of employees of contractor or sub-contractor with an Insurance Company approved by the Employer,** a comprehensive policy of Insurance and de- posit such policy or policies with the Employer from time to time during the currency of this contract.

In default of the Contractor insuring as provided above, the Employer on his behalf may so insure and may deduct the premiums paid from any money due, or which may become due to the contractor.

The Contractor shall upon settlement by the Insurer of any claim made against the insurer pursuant to a policy taken under this clause, proceed with due diligence to rebuild or repair

SIGNATURE OF TENDERER

the works destroyed or damaged. In this event all the monies received from the Insurer in respect of such damage shall be paid to the Contractor and the Contractor shall not be entitled to any further payment in respect of the expenditure incurred for rebuilding or repairing of the materials or goods destroyed or damaged.

The Contractor, in case of re-building or reinstatement after damage shall be entitled to such extension of time for completion as the Architect may deem fit, but shall, however, not be entitled to reimbursement by the Employer of any shortfall or deficiency in the amount paid by the insurer in settlement of any claim arising as set out herein.

Without prejudice to his liability under this clause, the Contractor shall also cause all sub-Contractors to effect for their respective portions of the works, similar policies of insurance in accordance with the provisions of this clause and shall produce or cause to produce to the Employer such policies. The Contractor shall not permit a sub-Contractor to commence work at the site unless the said insurance policies are submitted. In the event of failure of the sub-contractor to commence work at the site, the contractor shall be responsible for any claim or damage attributable to the said sub-Contractor.

#### **25 ACCOUNTS RECEIPTS & VOUCHERS**

The contractor shall, upon the request of the Employer furnish them with all the invoices, accounts, receipts and other vouchers that they may require in connection with the works under this contract, if the contractor shall use materials less than what he is required under the contract, the value of the difference in the quantity of the materials he was required to use and that he actually used shall be deducted from his dues. The decision of the Employer shall be final and binding on the contractor as to the amount of materials the contractor is required to use for any work under this contract.

#### **26 . MEASUREMENTS**

All measurements shall be carried out as per relevant IS code unless otherwise stated elsewhere in this document. Before taking any measurement of any work the Site Engineer/ Architect/ employer or a subordinate deputed by him shall give reasonable notice to the contractor. If the contractor fails to attend at the measurements after such notice or fails to counter sign or to record the difference within a week from the date of measurement in the manner required by the Site Engineer then in any such event the measurements taken by the Site Engineer or by the subordinate deputed by him as the case may be is final and binding on the contractor and the contractor shall have no right to dispute the same.

#### **27. CONCEALED WORK**

The contractor shall give due notice to the Employer/Architects whenever any work is to be concealed or otherwise becoming inaccessible later on, in order that the work may be inspected and correct dimensions taken before such burial, in default whereof the same shall, at the opinion of the Employer/Architect be either opened up for measurement at the contractor's expense or no payment may be made for such materials. Should any dispute or differences arise after the execution of any work as to measurements etc., or other matters which cannot be conveniently tested or checked, the notes of the Employer/Architects shall be accepted as correct and binding on the contractor.

SIGNATURE OF TENDERER

## 28. INITIAL & INTERIUM PAYMENTS

**Initial Mobilization Advance:** No mobilization advance will be considered by Bank.

**Running Bill payments:** All bills shall be prepared by the contractor in the form prescribed by the Employer/ Architects. Normally one interim bill shall be prepared each month subject to minimum value for interim certificate as stated in the **Appendix-1**. The bills in proper forms must be duly accompanied by detailed measurements & test certificate in support of the quantities of work done and must show deductions for all previous payments, retention money, etc.

The Architects shall issue a certificate after due scrutiny of the contractor's bill stating the value of the work executed, amount due to the contractor from the Employer and the contractor shall be entitled to payment thereof, within the period of honoring certificate stated in the **Appendix-1 subject to its correctness and verification by Employer**.

The amount stated in an interim certificate shall be the value of work properly executed and material advance upto 75% of invoiced value of materials brought to site for alternate incorporation into the work after preparation of the previous bill less the amount to be retained by the Employer as **retention money vide clause 10** of these conditions. Advance paid for materials already incorporated in the work shall be recovered.

**The material advance** shall be admissible only on materials, which in the opinion of the Architect/ employer are imperishable in nature, are genuinely required for use in the work in the near future, are of the required quality and are adequately protected against damage, theft, loss etc.

If the Employer has supplied any materials or goods to the contractor, the cost of any such materials or goods will be progressively deducted from the amount due to contractor in accordance with the quantities consumed in the work.

All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the requiring of bad, unsound, and imperfect or unskilled work to be removed and taken away and reconstructed, or re-erected or be considered as an admission of the due performance of the contract, or any part thereof in any respect or the accruing of any claim, nor shall it conclude, determine or affect in anyway the power of the Employer under these conditions or any of them as to the final settlement and adjustment of the accounts or otherwise or in any other way vary or affect the contract. In all the above the **Appendix 2, 3 & 4**, shall be followed.

## 29.FINAL PAYMENT

The final bill shall be submitted by the contractor to the Architect within one month of the date of completion of the work certified by the Architect and payment shall be made within **one month** for such of those items and quantities that in the opinion of the Employer are undisputed.

SIGNATURE OF TENDERER

Payments of final bill shall be made after deduction of Retention Money as specified in **clause 10** of these conditions, which sum shall be refunded as stipulated in **Clause 10**. The acceptance of payment of the final bill by the contractor would indicate that he will have no further claim in respect of the work executed.

### **30. VARIATION / DEVIATION**

The Employer shall have powers to order additional /non-tendered items or to modify the tendered items, to vary the quantities of tendered items and not to execute certain items. All such orders shall be in writing.

The rate or price of all such additional items/non-tendered/modified items will be worked out on the basis of rates quoted for similar items in the contract wherever existing or on engineering rate analysis based on prevalent fair price of labour, material and other components as required. The tender rates shall hold good for any increase or decrease in the tendered quantities up-to variation of 25%.

For variation beyond 25%, the rate may be reviewed based on prevalent fair price of labour, materials and other components as per the rate analysis format given in **Appendix- 7**. The contractor shall submit detailed analysis of rates and supporting documents to the Employer/Architect within 7 days of being directed to execute such items/quantities and the Employer/Architect shall assess the analysis and approve reasonable and justified rate.

No such additional or modified items or variation in quantities (except variation in quantities as per approved drawings) shall be executed by the Contractor without prior written approval of the Employer / Architect.

### **31. SUBSTITUTION**

Should the contractor desire to substitute any materials and workmanship, he/they must obtain the approval of the Employer/Architects in writing for any such substitution well in advance. Materials designated in the Schedule of Quantities and specification indefinitely by such term as "Equal", "Equivalent" or "Other approved" etc. specific approval of the Employer/Architects has to be obtained in writing.

### **32. COMPLETION OF WORK**

On completion of the work the contractor shall clean all windows, doors, fittings, fixtures, furnitures etc of all paint/polish/distemper splashes/dirt/dust / adhesives etc, if necessary all hardware, clean inside and outside, all floor, stair-cases, and every part of the building and the surroundings.

On receipt of such written intimation from the contractor on completion of the work, the Architect/ Employer shall arrange to inspect the work and certify completion if the work has been completed satisfactorily. If not, the Architect/ Employer shall inform the Contractor the deficiencies/defects in the work and the contractor shall attend to them properly and again intimate the Employer/Architect for further inspection.

The work shall not be considered as complete until the Employer/Architects have certified in

SIGNATURE OF TENDERER

writing that it has been completed satisfactorily without any apparent defects and the Defects Liability Period shall commence from the date of such certificate

No such certificates shall be issued until the contractor clears away and re- moves from the site all constructional plant, surplus materials, rubbish temporary works of every kind and leaves the whole of the site and the works clean and in a workman like condition to the satisfaction of the Employer/Architects.

### **33. DEFECTS AFTER COMPLETION**

The contractor shall make good at his own cost and to the satisfaction of the Employer all defects which may appear during the defect liability period of **one year from the date of completion of the works.**

In default the Employer may employ and pay other persons to amend and make good such damages, losses and expenses consequent thereon or incidental thereto shall be made good and borne by the contractor and such damages, loss and expenses shall be recoverable from him by the Employer or may be deducted by the employer, in lieu of such amending and making good by the contractor a sum equivalent to the cost of amending such work and in the event of the amount retained being insufficient, recover that balance from the contractor from the amount retained under **clause No.10** under this contract or any other contract together with any expenses the Employer may have incurred in connection therewith.

### **34. IDLE LABOUR**

Whatever the reasons may be no claim for idle labour, additional establishment cost of hire and labour charges of tools and plants would be entertained under any circumstances.

### **35.ASSIGNMENT**

The whole of the works included in the contract shall be executed by the contractor and the contractor shall not directly or indirectly transfer, assign or sublet the contract or any a part, share or interest therein nor, shall take a new partner, without written consent of the Employer and no subletting shall relieve the contractor from the full and entire responsibility of the contract or from active superintendence of the work during their progress.

### **36.ESCALATION:**

The rate quoted shall be firm throughout the tenure of the contract including extension of time, if any, granted and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, VAT, works contract tax, octroi, service tax etc. or any other tax. There shall be **NO ESCALATION** on the quoted rates.

The basic rates indicated in Schedule of quantities for material is only to facili- tate the Bank to select the material.

### **37. SUSPENSION OF WORK**

If the Contractor:

- (i) Having been given by the Bank a notice in writing to rectify, reconstruct or replace

SIGNATURE OF TENDERER

- any defective work or that the work is being performed in an inefficient or otherwise improper or un-workmanship like manner, shall omit to comply with the requirements of such notice for a period of seven days thereafter; or,
- (ii) has without reasonable cause suspended the progress of the work or has failed to proceed with the work so that in the opinion of the bank (which shall be final and binding) that he will be unable to secure completion of the work by the date for completion and continues to do so after a notice in writing of seven days from the bank; or
  - (iii) persistently neglects to carry out his obligations under the contract and/or commits default in complying with any of the terms and conditions of the contract and does not remedy it or take effective steps to remedy it within 7 days after a notice in writing is given to him in that behalf by the bank or
  - (iv) fails to complete the work within the stipulated date or items of work with individual date of completion, if any, stipulated on or before such date(s) of completion and does not complete them within the period specified in the notice given in writing in that behalf by the Bank ; or
  - (v) being a company shall pass a resolution or the court shall make an order that the company shall be wound up or if a receiver or a manager on behalf of a creditor shall be appointed or if circumstances shall arise which entitle the court or the creditor to appoint a receiver or a manager or which entitles the court to make a winding up order; or
  - (vi) If the contractor except on account of any legal restraint upon the Employer preventing the continuance of the work or in the opinion of the Employer shall neglect or fail to proceed with due diligence in the performance of his part of the contract or if he shall more than once make default,

In all the above , the Employer shall have the power to give notice in writing to the contractor requiring the work be proceeded within a reasonable manner and with reasonable dispatch, such notice purport to be a notice under this clause.

After such notice shall have been given the contractor shall not be at liberty to remove from the site of the works or from any ground contiguous thereto any plant or materials to subsist from the date of such notice being given until the notice shall have been complied with. If the contractor shall fail for 7 (seven) days after such notice has been given to proceed with the works as therein prescribe, the Employer may proceed as provided in **clause 38** (Termination of Contract by Employer).

### **38. TERMINATION OF CONTRACT BY EMPLOYER**

If the contractor being a company go into liquidation whether voluntary or compulsory or being a firm shall be dissolved or being an individual shall be adjudicated insolvent or shall make an assignment or a composition for the benefit of the greater part, in number of amount of his creditors or shall enter into a Deed or arrangement with his creditors, or if the Official Assignee in insolvency, or the Receiver of the contractor in insolvency, shall repudiate the contract, or if a Receiver of the contractor's firm appointed by the court shall be unable, within fourteen days after notice to him requiring him to do so, to show to the reasonable satisfaction of the employer that he is able to carry out and fulfill the contract, and if so required by the employer to give reasonable security therefore, or if the contractor shall suffer execution to be issued, or shall suffer any payment under this contract to be attached by or on behalf of any of the

SIGNATURE OF TENDERER

creditors of the contractor, or shall assign, charge or encumber this contract or any payments due or which may become due to the contractor there under, or shall neglect or fail to observe and perform all or any of the acts, matters or things by this contract to be observed and performed by the contractor within three clear days after the notice shall have been given to the contractor in manner hereinafter mentioned requiring the contractor to observe or perform the same or shall use improper materials or workmanship in carrying on the works, or shall in the opinion of the employer not exercise such due diligence and make such due progress as would enable the work to be completed within due time agreed upon, and shall fail to proceed to the satisfaction of the employer after three clear days' notice requiring the contractor so to do shall have been given to the contractor as hereinafter mentioned, or shall abandon the contract, then and in any of the said cases, the bank may not- withstanding previous waiver, determine the contract by a notice in writing to the effect as hereinafter mentioned, but without thereby effecting the powers of the contract the whole of which shall continue in force as fully as if the contract had not been so determined and as if the works subsequently executed had been executed by or on behalf of the contractor (without thereby creating any trust in favor of the contractor). Further the employer or his agent, or servants, may enter upon and take possession of the work and all plants, tools, scaffolding, sheds, machinery, steam and other power, utensils and materials lying upon premises or the adjoining lands or roads and sell the same as his own property or, may employ the same by means of his own servants and workmen in carrying on and completing the works or by employing any other contractors or other persons or person to complete the works, and the contractor shall not in any way interrupt or do any act, matter or thing to prevent or hinder such other contractor or other persons or person employed from completing and finishing the works. When the works shall be completed, or as soon thereafter as conveniently may be, the employer shall give notice in writing to the contractor to remove his surplus materials and plants and, should the contractor fail to do so within a period of 14 days after receipt by him, the employer may sell the same by Public Auction and shall give credit to the contractor for the amount so realized. Any expenses or losses incurred by the employer in getting the works carried out by other persons or contractors shall be adjusted against the amount payable to the contractor by way of selling his tools and plants or due on account of work carried out by the contractor prior to engaging other persons or contractors or against the Security Deposit.

Without prejudice to any of the rights or remedies under this contract if the contractor dies, the Bank shall have the option of terminating the contract without compensation to the contractor.

### 39. ARBITRATION

All disputes or differences of any kind whatsoever which shall at any time arise between the parties hereto touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contract or the construction remaining operation or effect thereof or to the rights or liabilities of the parties or arising out of or in relation thereto whether during or after determination foreclosure or breach of the contract (other than those in respect of which the decision of any person is by the contract expressed to be final and binding) shall after written notice by either party to the contract to the other of them and to the Employer hereinafter mentioned be referred for adjudication to a **sole Arbitrator** to be appointed as hereinafter provided.

SIGNATURE OF TENDERER

For the purpose of appointing the sole Arbitrator referred to above, the Employer will send within thirty days of receipt of the notice, to the contractor a panel of three names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names of aforesaid, select any one of the persons named to be appointed as a sole Arbitrator and communicate his name to the Employer within thirty days of receipt of the names. The Employer shall thereupon without any delay appoint the said person as the Sole Arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the Sole Arbitrator.

If the Employer fails to send to the contractor the panel of three names as aforesaid within the period specified, the contractor shall send to the Employer a panel of three names of persons who shall all be unconnected with either party. The Employer shall on receipt of the named as aforesaid select anyone of the persons name and appoint him as the Sole Arbitrator. If the Employer fails to select the person and appoint him as the Sole Arbitrator within 30 days of receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the Sole Arbitrator and communicate his name to the Employer.

If the Arbitrator so appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another Sole Arbitrator shall be appointed as aforesaid. The work under the Contract shall, however, continue during the arbitration proceedings and no payment due or payable to the contractor shall be withheld on account of such proceedings. The Arbitrator shall give a separate reasoned award in respect of each dispute or difference referred to him. The venue of arbitration shall be such place as may be fixed by the Arbitrator in his sole discretion.

The fees and expenses, if any, of the Arbitrator shall, if required to be paid before the award is made and published, be paid half and half by each of the parties. The Arbitrator may direct to and by whom and in what manner the cost of the reference and of the award including the fees and expenses or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the Arbitrator shall be final and binding on both the parties. Subject to the aforesaid, the provisions of the Arbitration and Conciliation Act, 1996 or any statutory modification or re-enactment thereof and the rules made hereunder, and for the time being in force, shall apply to the arbitration proceeding under this clause.

#### **40.CLOSE RELATIVES**

The contractor shall also intimate the names of persons who are working with him in any capacity or are subsequently employed by him or himself and who are near relative to any Employee of the Canara bank. Any breach of these conditions by the Company or Firm or any other person/ contractor, the tender/work is liable to be cancelled and Earnest Money/ Security Deposit will be forfeited at any stage, whenever it is so noticed. The Bank will not pay any damages to the company or Firm or the concerned person. The Company or Firm or the person is also liable to be debarred for further participation in the tenders in the concerned

SIGNATURE OF TENDERER

circle of the Bank. The details shall be furnished in Appendix 8.

#### **41. RETIRED EMPLOYEES**

No Employee of the employer or employed in any department of the Government of India, PSU , Nationalized/ state bank shall work as a contractor or employee of a contractor for a period of two years after his retirement from service without the previous permission of their employer in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found at any time to be such a person who had not obtained the permission of their employer as aforesaid, before submission of the tender or engagement in the contractor's service, as the case may be. The details shall be furnished in **Appendix 8**.

Signature of the Tenderer With name and address

SIGNATURE OF TENDERER

## SPECIAL CONDITIONS OF CONTRACT

These Special conditions of Contract shall be read in conjunction with the General Conditions of contract, Schedule of quantities, Drawings and any other documents forming part of this contract wherever the context so requires.

Where any portion of the General Conditions of Contract is repugnant to or at variance with any provisions of the Special Conditions of Contract, then unless a different intention appears, the provisions of the Special Conditions of Contract, shall be deemed to over-ride the provisions of the General Conditions of Contract and shall to the extent of such repugnance, or variance, prevail.

In case where the specifications in the drawings or those given in schedule of quantities are found wanting the latest IS specifications then CPWD shall hold good.

### 1. ORDER OF EXECUTION OF DIFFERENT ITEMS OF WORK:

The Bank reserves the right to fix the order in which the various items of work involved in this contract are to be executed and contractor shall comply with the same. There shall be no extra claims on account of this.

### 2. DISCREPANCIES IN DOCUMENTS:

The several documents forming the contract are to be taken mutually explanatory of one another. In the event of any Errors, Omissions and Discrepancies, the same shall be dealt as under:

- ❖ In case of errors, omissions and /or disagreement between written and scaled dimensions on the drawings and specifications etc., the following order of precedence shall apply.
  - Between scaled and written dimension (or description) on a drawing, the latter shall be adopted.
  - Between the written or shown dimensions in the drawings and the corresponding one in the specification, the former shall be taken as authenticated.
- ❖ In case of discrepancy between the schedule of quantities, the specifications and /or the drawings, the following order of preference will be observed.
  - Description in Schedule of Quantities.
  - Drawings.
  - Indian Standard Specifications of B.I.S.
  - CPWD specifications
- ❖ In case of difference between the rates written in figures and the rate in words shall prevail.
- ❖ In case of omissions and/or doubts or discrepancies in any of the items or specifications, a reference shall be made to the Bank whose Elucidation, elaboration, decision shall be considered as authentic.

### 3. DEDUCTIONS AT SOURCE FOR Income tax, VAT (works contract) and other applicable Statutory deductions:

Appropriate deduction as per relevant Income Tax & VAT (works contract tax) Rules applicable  
SIGNATURE OF TENDERER

at the time of payment shall be made on the bills submitted by the contractor and such deducted amounts shall be remitted by the Employer to the respective central/ state government authorities on behalf of the Contractor as per Rules.

#### **4. USEFUL DISMANTLED MATERIALS:**

Before dismantling any item prior permission of the Architect/ Employer shall be obtained and seek instructions for measurement, storage of the materials which shall become the property of the Bank unless otherwise stated in these documents / schedule of quantities.

#### **5. NO OVER LOADING OF SLABS:**

Floors of buildings shall not be over loaded by stacks or materials during execution of the works without the prior approval of the Bank.

#### **6. APPROVED MAKE OF MATERIALS**

The make of the material to be used in the works shall be as per list of approved makes detailed in **Appendix 9** and as per sample got approved from the Bank. A set of specimen samples of all approved materials shall be kept at site or any designated branch of the Bank. The cost of which shall be borne by the Contractor.

All other materials to be used in the works but not covered above but specified in the schedule of quantities (SOQ) including items beyond SOQ shall also be of best of its kind and shall conform to latest Indian Standard Specifications.

#### **7. CORDINATION OF WORKS**

Work involves execution in functioning branch of a Bank; it is intended to undertake works with minimum disturbance to the occupants & customers. Hence the execution needs to be carried out meticulously with proper co- ordination and planning. Further the work needs to be carried out in co- ordination with other agencies.

Signature of the Tenderer/Contractor  
With name and address

SIGNATURE OF TENDERER

**OFFER LETTER**

**The Assistant General Manager  
Canara Bank  
Premises & Estate section  
Circle office, Thiruvananthapuram**

**Name of work: " ....." "**

Dear Sir,

I/We have read and examined the Notice Inviting the Tender ( NIT ), Offer Letter, General rules & Instructions to tenderers, General conditions of tender, Special conditions, Appendices , Schedule of quantities, drawings, and all other documents referred to in this Documents and all other contents in the tender document for the work.

I/We hereby tender for the execution of the work specified for the Employer within the time specified at the rates specified in the attached Priced Schedule of quantities viz., schedule of quantities and in accordance in all respects with the tender documents and in all respects in accordance with, such conditions so far as applicable.

I/We agree to keep the tender open for **120 days** from the due date of submission thereof and undertake not to make any modifications in its terms and conditions. A sum of Rs is hereby forwarded as earnest money in form of Demand Draft of (Name of the issuing Schedule Bank) bearing no. ....  
and date . .....

In the event of the acceptance of my tender , I agree that the earnest money shall be retained by Employer towards security deposit to execute all the works referred to in the tender documents as per the terms and conditions contained or referred to therein.

I/We agree that should I/We fail to deposit the full amount of Initial security deposit and/or fail to commence the work specified **and/or** execute the agreement **and/or** execute the Indemnity bond and/ or submit the Insurance as per the above tender documents, an amount equal to the amount of the earnest money deposit mentioned tender documents shall be absolutely forfeited to the Employer and the same may at the option of the Employer be recovered without prejudice to any other right or remedy available in law, out of the deposit in so far as the same may extend in terms of the said bond and in the event of deficiency out of any other money due to me/us under this contract or otherwise.

I/We hereby declare that I/We treat these tender documents, drawings and other records connected with the work as secret/confidential documents and shall not communicate information/derived there from to any persons other than a person to whom I/We am /are authorised to communicate the same or use the information in any manner prejudiced to the safety of the State / the Employer.

SIGNATURE OF TENDERER

I/We fully understand that you are not bound to accept the lowest or any tender you may receive.

Shri. \_\_\_\_\_, Partner / Proprietor / Authorised representative of the Company, is the person authorised to negotiate commercial, technical terms & conditions & sign on behalf of the firm any Agreement, Bills & receipts for this work.

I/We agree that until a formal agreement on stamp paper is prepared and signed, this tender with your written acceptance thereof shall constitute a binding contract between us.

Dated the: ..... day, ..... month of 2024.

Witness,

1).

2).

Signature of Contractor  
Name & address:  
Full Postal Address including Pin  
Code NO. & Telephone NO.

SIGNATURE OF TENDERER

**APPENDIX-1 - IMPORTANT TERMS**

- 1 Period of Completion : **45 days**
- 2 Defects Liability Period (DLP) : One year from the date of Completion of work unless otherwise specified.
- 3 Date of Commencement : **Third day** from the date of signing of agreement, submission of Indemnity bond, submission of Insurance , depositing of Initial security deposit OR order to commence the works whichever is earlier.
- 4 Liquidated Damages for Delay : As mentioned in the **Clause no.13**
- 5 Period of final measurement : 30(Thirty) days.
- 6 Value of work for claiming the Interim Bills : Minimum of Rs. 5.00 (Five) lakhs based on the **accepted measurements.**
- 7 Period of honoring interim Certificate : 15 days from the date of receipt of bill certified by Architect/Consultant.
- 8 Period of honoring Final Certificate : One month from date of receipt of certified bill correct in all aspects
- 9 Retention Money : 3% of Interim Bill amount subject to the ceiling of the total security deposit
- 10 Total Security Deposit (Maximum) : As per clause no. 10 of General conditions
- 11 Initial Security Deposit EMD : 2% of accepted tendered sum including

**SIGNATURE OF THE TENDERER**

SIGNATURE OF TENDERER

**APPENDIX-2 - RUNNING A/C BILL FORMAT**

1. Name of work :
2. Name of Contractor :
3. Accepted contract amount :
4. Date of commencement :
5. Stipulated date of completion :
6. Actual date of completion :
7. Extension, if any :
8. Insurance valid upto :
  - a) Workmen Compensation Act
  - b) Contractor's all risk Comprehensive
10. Labour license no. and date & valid upto :
11. Serial no. of this bill :
12. No. & date of this bill :
13. Ref. to agreement no. :
14. Earnest money deposit :
15. Total retention money excluding E.M.D as per contract :
16. Total retention money excluding (Date to be mentioned) : which this bill has been prepared

**Note:** i) if part rate is allowed for any item, it should be indicated with reasons

ii) if ad-hoc payment is made, it should be mentioned specially.

Signature of the Contractor

SIGNATURE OF TENDERER

**APPENDIX -3 - CERTIFICATE FOR PAYMENT**

RUNNING BILL NO. \_\_\_\_\_ date .....

Total value of the works executed so far Rs.... (A) Total value of the works till the  
previous bill Rs.... (B)

Total amount due since previous bill Rs \_\_\_\_\_ (A) - (B)

**DEDUCTIONS**

Retention money on value of work as per accepted tenders up to date Rs. \_\_\_\_\_

Less: Already recovered (-) Rs. \_\_\_\_\_

Balance to be recovered Rs. \_\_\_\_\_

Total Deduction as per contract Rs. \_\_\_\_\_

Any other recovery as per contract (-) Rs .....

Net amount payable as per contract Rs. \_\_\_\_\_

(Rupees \_\_\_\_\_) in words.

Signature of Architect

SIGNATURE OF TENDERER

**APPENDIX- 4 - MEASUREMENT CERTIFICATE**

1. The measurements on the basis of which the above entries the Running Bill no. \_\_\_\_\_ were made have been taken jointly on \_\_\_\_\_ and are recorded at pages \_\_\_\_\_ to \_\_\_\_\_ of measurements book no. \_\_\_\_\_
2. The work recorded in the above-mentioned measurements been done at the site satisfactorily as per tender conditions, drawings and specifications.

\_\_\_\_\_  
Signature of Contractor

\_\_\_\_\_  
Signature of Site  
Engineer.

\_\_\_\_\_  
Signature of Architect

Date:

Place:

SIGNATURE OF TENDERER

**APPENDIX-5 - CONTRACT AGREEMENT FORMAT**

This agreement made on this \_\_\_ day of the month of \_\_\_\_\_ in the year two thousand \_\_\_\_\_ (\_\_\_\_\_. 2024) BETWEEN, **Canara Bank** a body corporate constituted under the Banking & Companies (Acquisition and Transfer of Under- takings) Act, 1970, having its Head Office, at 112, J C Road, Bangalore- 560 002, amongst others a **Circle office at Thiruvananthapuram-1** represented by its duly constituted attorney (hereinafter referred to as Bank) of the **ONE PART** ;

AND

M/s. \_\_\_\_\_ duly represented by one of its Proprietor/Partner \_\_\_\_\_

, aged \_\_\_\_\_ years, S/o Sri \_\_\_\_\_, residing at \_\_\_\_\_ and having their office at \_\_\_\_\_

\_\_\_\_\_ (hereinafter called the Contractor) of the **Other part.**

WHEREAS THE Bank is desirous of undertaking the ..... and has accepted the tender opened on ..... 2023 submitted by the contractor & the contractor has agreed to perform as set out and subject to the terms & conditions set forth in the said documents mentioned herein under.

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this agreement words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to.
2. The following documents not inconsistent with these presents shall be deemed to form and be read and construed as part of this agreement viz.,
  - a) The Tender Document comprising Notice inviting the tender , General rules & Instruction to tenderers, General Conditions of the Contract, Special; conditions , Appendix 1 to .. , Priced schedule of quantities, Tender Drawings.
  - b) Corrigendum to tender document if any.
  - c) Letter from contractor dt. \_\_\_\_\_ in response to the negotiation meeting discussions held on \_\_\_\_\_
  - d) Letter of \_\_\_\_\_ Acceptance issued to contractor by Bank - letter No. \_\_\_\_\_ dt.....
  - e) Letters from and to the Contractor, if any, leading to and prior to acceptance letter.

SIGNATURE OF TENDERER

3. In consideration of the payments to be made by the Bank to the Contractor the Contractor hereby covenants and agrees with the Bank to execute, complete and perform the works in conformity in all respects with the Tender document as mentioned in the aforesaid documents which shall form part of this agreement.

In witness whereof, the parties hereunto have set their respective hands and seals the day and year first above written.

For & on behalf of the  
Contractor with seal

For & on behalf of the  
Canara Bank with seal

SIGNATURE OF TENDERER

**APPENDIX -6 - INDEMNITY BOND FORMAT**

THIS DEED OF INDEMNITY BOND executed at Thiruvananthapuram on this \_\_\_\_\_day of \_\_\_\_\_month of year (2024) By M/s \_\_\_\_\_ duly represented by proprietor / one of its partners Sri \_\_\_\_\_, aged \_\_\_\_\_ years, son of Sri \_\_\_\_\_, residing at \_\_\_\_\_.

. In favour of

Canara Bank, a body corporate constituted under the Banking companies (Acquisition and Transfer of undertakings) Act, 1970, having its Head Office, at 112, J.C.Road, Bangalore - 560002.

Whereas I am the authorised partner of M/s \_\_\_\_\_, and had applied for prequalification of contractors for .....

Whereas as my company was shortlisted for issue of tenders and my company became successful in securing the subject work through competitive tendering and the work of \_\_\_\_\_ has been awarded in our favour by Canara Bank, Circle office, Trivandrum vide their letter .....

And where as for undertaking the .....work, my company has entered into contract agreement with Canara Bank on \_\_\_\_\_.

Now this Deed Witnessed that in pursuance of the aforesaid contract agreement dt. \_\_\_ and in consideration of Canara Bank having agreed to make payments on the bills claimed by me/my company based on the works completed by me/my company in respect of ..... and referred to above,

I hereby undertake to indemnify and keep harmless the Canara Bank & its Architect and its officials/ staff from any damages, prosecution, other legal suits and claims arising out of any mishaps occurring at the site due to faulty work, faulty construction and for violating rules and regulations, any possible damage to the building and members of public in course of execution of the work for which I shall be solely responsible.

Signature of Contractor with seal

SIGNATURE OF TENDERER

**APPENDIX-7 - FORMAT FOR RATE ANALYSIS OF ITEMS****I. MATERIAL**

1. Basic Cost of Material Rs. \_\_\_\_\_  
2. Wastage - Rs. \_\_\_\_\_

II. Labour: As per Standard - Rs. \_\_\_\_\_  
Labour output and labour input required for the  
Particular item using quoted labour rates.

III. Machinery / Tools - Rs. \_\_\_\_\_

IV. Inputs of Machinery / Tools requirements as per  
the item and hire charges as per market.

**TOTAL (I) + (II) + (III)** Rs. \_\_\_\_\_

V. Tax Liability  
[as per contractual clauses will be added] - Rs.

VI. Add - ½ % for water charges - Rs. \_\_\_\_\_  
½ % for Electricity - Rs.

VII. Any other Expenditure (please specify) Rs. \_\_\_\_\_

**TOTAL**

Contractor Profit & OH - 15% - Rs. \_\_\_\_\_

**GRAND TOTAL** - Rs. \_\_\_\_\_

TDS will be deducted as per standard norms and recovery shall be made for water and electricity as per tender conditions.

SIGNATURE OF TENDERER

**APPENDIX-8 - LIST OF RELATIVES WORKING IN CANARA BANK**

1. Details List of relatives working in Canara bank;

NAME OF THE OFFICIAL	DESIGNATION	ADDRESS OF THE OFFICE / BRANCH

- 2.Details List of retired Government / PSU/ Bank employees , employed by the tenderer / contractor :

NAME OF THE RETIRED OFFICIAL	DESIGNATION	NAME & ADDRESS OF THE PREVIOUS EMPLOYER

Name & Signature of Tenderer

Public

SIGNATURE OF TENDERER WITH SEAL

## APPENDIX -9 - LIST OF APPROVED MAKES

Sl. No.	Item	Make/Spec
1	Hard Wood (All wood must be well seasoned, free from Knots, other defects, decay and defects due to handling and transportation. Wherever Necessary, provide with anti - termite Treatment)	: Second class Teak /Mahagony/Angily/ Thambakam
2	Lipping	: Beech Wood
3	Plywood - Grade BWR with (IS: 303)	: Anchor (Sevak)/ Archid (Classic)/Greenply (Ecotec)/Kitply(Vista Premium)
		: Colour Greenlam Merino Sunmica White White White Lily Super 101 SUD 21081 White G 324/1324
4	Laminate & Internal Laminate	: Yellow Divine Marino Sun Yellow Yellow Flower G511/1511 207 SUD 21067 Blue Celestial Blue Sky Blue Blue 292 Danube G577A/157 SUD 21132 7A
5	Veneer	: Anchor/Greenply/Euro/Archidply
6	Adhesive	: Fevicol SH/Vamicol
7	Tile Adhesive	: BAL Endura/Webber/Saint Gobain
8	Glass/Float Glass/Mirror	: MODI Guard/Saint Gobain/IAG/Asahi
9	Fixtures (All hardware fixtures and fittings to be powder coated abd finish as per spec)	:
	i. MS 14g powder coated Hinges	: Ebco/Haffelle/Hettich
	ii. Stainless steel/Powder Coated Piano Hinges	: Mowjee/ GARG (ISI)
10	Paint (Enamel, Emulsion)	: Asian/Berger/Nerolac/ICI
11	Base Putty	: National/JK/Asian
12	Melamine/Polsih	: Asian/Berger/Nerolac/ICI/Sheenlac
13	Automobile Duco Paint	: MRF/ICI/Asian
14	Preservatives	: Solignum/Black Japan/Termi Seal
15	Lock & Fittings	: Godrej/Ebco/Yale/Haffele/Dorma/ Hettich

Public

SIGNATURE OF TENDERER WITH SEAL

16	Auto Closing Hinges/Sliders/Wire Manager Keyboard tray etc.	:	Ebco / Haffele / Hettich
17	Aluminium Section	:	Jindal/Hindalco
18	ACP	:	Aludecor/Eurobond/Alutech/Alucobond
19	Flooring (Vitrified/Ceramic tile)	:	Johnson/Kajaria/Somany/Nitco
20	Floor Spring/Door Closer/Handle	:	Haffele/Dorma/Godrej/ Hettich
21	Vertical Blinds/Roller Blinds/Zebra Blinds	:	Vista/Trac/Mac/Hunter Douglas/Technifab
22	Pre Laminated Particle Board & MDF	:	Ecoboard/Merrino/Panelmax
23	Cement Board	:	Visaka/Bison/Everest
24	Gypsum False Ceiling	:	Gypsum India/Gyproc/Saint Gobain
25	False ceiling Tiles	:	AMF/Armstrong /Ecophone/Saint Gobain
26	Wallpaper	:	Marshall / Ego / Softek
27	Glass film & Vinyl Stickers	:	3M/Garware/Avery Dennison/LG Hausys
28	Italian Marble (The lot of marble would be jointly signed by the Bank & Architects)	:	Classic/ Nitco / Elegance
29	Carpet Tiles	:	Nylon carpet tile-Shaw / Milliken / Bentley prince
30	Cement	:	ACC / Ultratech / Ramco/Ambuja -43 grade
31	Bricks	:	Burnt bricks with minimum strength of 35 kg/cm <sup>2</sup>
32	Steel	:	Tata/ Saicon / Vizag (Fe- 500 grade)/Jindal
33	UPVC Window	:	Kommerling, Feneista
34	PU Tactile Tiles	:	Delco, Signxpress India

**NOTE:**

ISI mark should be printed on material wherever applicable

**Any brands indicated under the items specifications in the schedule of quantities will prevail over the above indicated makes.**

Apart from the above makes, any further equivalent make as approved by the Bank, can also be used with prior permission from the Bank.

SIGNATURE OF THE TENDERER

Public

SIGNATURE OF TENDERER WITH SEAL

## PRICE BID

Sl. No	Item Description	Qty	Unit	Unit Price excl. GST	Amount
A	<b>BRANCH</b>				
1	<b>NON GLAZED PARTITION</b>				
	Providing & fixing Full height Non glazed partition upto ceiling height using aluminium rectangular sections size of <b>63.5mmx38.1mm Aluminium frame 1.70 mm thickness</b> for all horizontals & verticals spaced at 2 ft centre to centre or part thereof both ways for supporting frame work. All the panels and on both sides of the partition to be covered with 6mm thick Plywood ( <b>BWR Grade</b> ) <b>IS303</b> and over that 1mm thick laminate of approved colour and brand to be pasted, 3" skirting(CB Blue ) & 3" border(CB Yellow) @ 7' ht to be done. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly necessary cuttings to be made in the plywood ( <b>BWR Grade</b> ) <b>IS303</b> surface to fix switch boxes of electrical, telephone sockets, computer Information outlets etc. Door to be done in same manner with view glass (1'6"x 1'0"). Door Size: 4'0"x7'0" with Cylindrical locks, handle,SS hinges, door closure & stopper, vision panel etc. (Frame work to be supported from the rcc ceiling, but the final measurement for billing would be taken below the false ceiling level only.)	135	Sft		
2	<b>SEMI GLAZED PARTITION @ 4'0" HT.</b>				
	Providing & fixing Semi partly glazed partition using <b>63.5mmx38.1mm Aluminium frame 1.70 mm thk.</b> The bottom panel of 3 ft height to be covered with both side 6mm thick Plywood ( <b>BWR Grade</b> ) <b>IS303</b> & 1mm thick laminate of approved colour and brand. 3" skirting(CB Blue) . The top 1 ft to be fixed with 12mm thick glass with necessary etching designs as per the approved design with Bank logo & border design. The glass shall be fixed with necessary beech wood beadings which are neatly melamine polished. beech wood trimmers of 4" wide to be fixed on the top with melamine polish.Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly necessary cuttings to be made in the partition to fix switch boxes of electrical, telephone sockets, computer Information outlets etc.	60	Sft		
3	<b>BISON BOARD PARTITION (UPS Room)</b>			Internal	
	Providing & fixing Full height partition for Strong Room (8'ht) & UPS (Side) room using aluminium frame works, aluminium rectangular sections of <b>63.5mmx38.1mm with 1.70 mm thickness</b> for all horizontals & verticals spaced at 2 ft centre to centre or part thereof both ways for supporting frame work. All the panels and on both sides of	310	Sft		

	the partition to be covered with <b>8mm thick bison board</b> and over that 2 coat of emulsion paint approved colour to be painted. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly necessary cuttings to be made in the bison board surface to fix switch boxes of electrical, telephone sockets, computer Information outlets etc. Door to be done in same manner with view glass (1'6" x 1'0"). Size: 3'0" x 7'0" with Cylindrical locks, handle, SS hinges, door closure & stopper.				
4	<b>PARTLY GLAZED PARTITION</b>				
	Providing & fixing Full height partly glazed partitions using aluminium rectangular sections size of <b>63.5mm x 38.1mm Aluminium frame 1.70 mm thickness</b> for all horizontals & verticals spaced at 2 ft centre to centre or part thereof both ways for supporting frame work. For the bottom 3 feet height panel and the top panel above 7'0" upto false ceiling level and on both sides to be covered with 6mm thick Plywood ( <b>BWR Grade</b> ) <b>IS303</b> and over that 1mm thick laminate of approved colour and brand to be pasted, 3" skirting (CB Blue) & 3" border (CB Yellow) @ 7' ht to be done (depending on the partition width and to maintain symmetry and keeping in mind the aesthetic value of the interiors), float glass of 8mm thickness to be fixed above 3'0" level for a height of 4'0" with necessary beech wood beadings which shall be neatly melamine polished. The Middle portion 4 ft to be fixed with 8mm thick glass with necessary etching designs as per the approved design with Bank logo & border design. Necessary holes must be made in the partition's frame sections to run the wires, computer cables wherever necessary. Similarly necessary cuttings to be made in the Plywood ( <b>BWR Grade</b> ) <b>IS303</b> surface to fix switch boxes of electrical, telephone sockets, computer Information outlets etc. Door to be done in same manner. Size: 3'0" x 7'0" with Cylindrical locks, handle, SS hinges, door closure & stopper (Frame work to be supported from the rcc ceiling, but the final measurement for billing would be taken below the false ceiling level only).	110	Sft		
5	<b>COMPOSITE PARTITION</b>				
a)	<b>COMPOSITE PARTITION (one side plywood and one side cement board)</b>				
	Providing & fixing composite partitions at Dining Front, Strongroom Front & Record room as per design with fixed on framework using aluminium rectangular sections of <b>63.5mm x 38.1mm Aluminium frame &amp; 1.70mm thickness</b> Spacing of verticals should not be more than 600mm 2 ft centre to centre and covered on one side with 6 mm thick <b>IS303 (BWR) Grade Plywood</b> and the other side with 12 mm thick Cement board using self drilling screws between banking hall and back office area, etc.	370	Sft		

	The partition should withstand its weight. The plywood surface shall be finished with 1mm thick laminate 3" skirting(CB Blue ) & 3" border(CB Yellow) @ 7' ht to be done and the Joints between the Cement board shall be fixed with fiberglass joint mesh and finished with putty. Door to be done in same manner with view glass (1'6"x 1'0"). Size: 3'0"x7'0" with Cylindrical locks, handle, ss hinges, door closure & stopper				
b)	<b>COMPOSITE PARTITION (one side plywood and one side Bison board)</b>				
	Providing & fixing composite partitions at UPS room as per design with fixed on framework using aluminium rectangular sections of <b>63.5mmx 38.1mm Aluminium frame &amp; 1.70mm thickness</b> Spacing of verticals should not be more than 600mm 2 ft centre to centre and covered on one side with 6 mm thick <b>IS303 (BWR) Grade Plywood</b> and the other side with 8mm thick bison board and over that 2 coat of emulsion paint approved colour to be painted. The partition should withstand its weight. The plywood surface shall be finished with 1mm thick laminate 3" skirting(CB Blue ) & 3" border(CB Yellow) @ 7' ht to be done and the Joints between the Cement board shall be fixed with fiberglass joint mesh and finished with putty. Door to be done in same manner with view glass (1'6"x 1'0"). Size: 3'0"x7'0" with Cylindrical locks, handle, ss hinges, door closure & stopper	10	Sft		
6	<b>FULLY GLAZED PARTITION</b>				
a	<b>FRONT ENTRANCE &amp; MANAGER FRONT</b> : Providing and fixing Fully glazed partition <b>Branch Entry &amp; Manager Cabin</b> in front (exterior side) , <b>12 mm thk toughened glass</b> of approved make with patch fittings and glass with necessary etching designs as per the approved design with Bank logo & border design.All edges of the glass to be machine polished (Frame work to be supported from the rcc ceiling, but the final measurement for billing would be taken below the false ceiling level only)	90	Sft		
b	<b>ENTRANCE DOOR</b> : Providing and fixing Fully glazed door for branch entrance & Manager Cabin Front of <b>12 mm thk toughened glass</b> of approved make with patch fittings and door glass with necessary etching designs as per the approved design with Bank logo & border design.All edges of the glass to be machine polished.Door to be provided with <b>16" SS handle</b> of approved make with rubber beading ,Glass to glass lock round type (w/o cut out) and fixed with branded floor spring and floor to door lock of approved make. Branch Door size : <b>5'0"x7'0"</b> - 1 no & Manager Door Size : <b>3'0"x7'0"</b> - 1 no.	60	Sft		
7	<b>SUPERVISOR &amp; JEWEL FRONT GLASS</b>				

	Supervisor & Jewel front 12mm thick glass is fixed using D bracket as per plan, above the table top for a ht of 1'3" respectively. The glass panel shall have designed artistic etching using frosted film.	10	Sft		
8	<b>FRONT COUNTER DIVIDER GLASS</b>				
	Plywood and glass partition between the seats fixed to the top of the Counter. Solid portion to be fabricated from 19mm plywood and pasted with laminate on both sides. The edges to be finished with Beechwood. 12mm glass with curved corner as per drawing to be fixed to the counter and the vertical solid partition using SS brackets.	Nil	Sft		
9	<b>SWC CABIN FRONT GLASS PARTITION</b>				
	SWC cabin front 12mm thick glass is fixed as per plan, above the customer top for a ht of 2'6" respectively. there shall be an transaction opening of 6" x 6" with necessary support frame work & this opening shall have openable type door with locking arrangement from inside. There shall be a horizontal gap of 2" between two glass panels to facilitate communication between customer and cashier. The glass panel shall have designed artistic etching using frosted film.	15	Sft		
10	<b>SWC CABIN PARTITIONS @ 6'0" HT</b>				
	Providing and fixing partition for Single window counters (SWC) cabin on sides & rear partition by using <b>63.5mmx38.1mm Aluminium frame 1.75 mm thk</b> . There shall be atleast three horizontals at 0" 0', 3'0" and 6'0" levels from the floor level. There shall be vertical and horizontal supports for every 2 feet interval or part thereof. The bottom 3'0" height panel to be covered by 6mm thick Plywood ( <b>BWR Grade</b> ) <b>IS303</b> on both sides and finished with 1mm thick lamination. The top panel shall be covered by two numbers panels with 2" communication gap using 12 mm thick glass fixed with necessary beech wood beadings which shall be neatly melamine polished. There shall be provision for challan trays for passing cheques and challans between the Cash /SWC and supervisor tables. The sorting partition also to be done in the same manner with 6mm Plywood ( <b>BWR Grade</b> ) <b>IS303</b> & laminated upto 6'0" ht. without any glass.	120	Sft		
11	<b>SWC &amp; SORTING DOORS</b>				
	Size : 2'6" x6'0" - 2 nos				
	Providing and fixing of solid flush doors of size 2'6" wide and 6'0" high and fixed with 1 mm laminate on both sides. The edges of the door shall be lipped with 6mm thick beech wood beadings. 8mm glass shall be fixed with beadings for 2'0"x 3'0" for SWC door. The door shall be fixed with one number 6 levered <b>Godrej</b> make minimum 3 keys automatic <b>NIGHT LATCH</b> just below 3 feet level and one 3" length powder coated aluminium tower bolt and 4" long SS handle on both the sides. All the exposed wood	30	Sft		

	shall be neatly finished with melamine polish. Door of sorting shall not have glass but with locking provision, handles and all accessories.				
12	<b>SINGLE WINDOW COUNTERS ( SWC )</b>				
	Size: 5'6"x3'0"x3'6"				
	Providing and fixing Single Window Counter (SWC) / Teller Cash counter as shown in the drawing. Customer ledge of width 1'3" shall be at height of 12" above the working counter top (i.e at <b>42" height from floor level</b> ). This customer ledge shall be projected ( 6" towards customer side and 9" towards cashier side). <b>View glass of 12 mm thick of size 1'6"x6"</b> shall be provided for the ledge for view of cash counting as per drawing. The counter shall be made out of 19mm thick plywood( <b>BWR grade</b> )IS303& finished with 1mm thick blue lamination sheet on top. <b>The inside &amp; hidden surfaces shall be painted with 2 coats of enamel paint over 1 coat of smooth putty finish.</b> The cash drawers 3 nos are to be provided with denomination partitions with locking provisions. Customer ledge 1'3" wide and working top 3'0" wide to be provided with <b>12mm thk float glass</b> with high polish.	5.50	Rft		
	The front elevation of the counter shall be as per the design detailed in the drawing or as detailed by the Architect/ Engineer in-charge , front apron of size 2'0"x1'0" of Acrylic panel to be fixed with stainless steel studs ( 4 nos). The bank logo sticker of size 1'0"x1'6" to be fixed on the Acrylic panel. Each counter shall be provided with approved make metal body key board tray and smooth wrist cushion pad and foot rest SS Pipe 50mm dia to be provided. The laminate colours for the counter/ table top, vertical sides, bands, skirting etc shall be strictly as per the recommended colours indicated by Bank. ( Refer Dwg)				
13	<b>FRONT COUNTER TABLES</b>				
	Providing and fixing front counter as per plan, the front, working top, main vertical side supports shall be made out of 19mm thick plywood( <b>BWR grade</b> )IS303 & finished with 1mm thick lamination on all visible sides, 3" skirting(CB Blue) to be done. The <b>counter top</b> shall be fixed and finished with <b>8mm thk clear glass</b> high polished on all sides over the top blue laminate sheet. The inside & hidden surfaces to be <b>painted with 2 coats of enamel paint over 1 coat of smooth putty finish</b> The front elevation of the counter shall be as per the design detailed in the drawing or as detailed by the Architect/ Engineer in-charge using 19mm thick plywood. The top is shown with double thickness finished with beech wood beadings , melamine polished. All counters to be provided with drawer unit comprising of one drawer (telescopic channel) and storage unit ( box type hinges), locks, D type handles	25.50	Rft		

	and all accessories to be provided.All drawers, corners, doors to be finished with beech wood lipping/beading, melamine polished. For all drawers : Recessed Handle(Shutter Handle -Aluminium 3012 Square with endcap) (Ebco/eqlt).				
	The front elevation of the counter shall be as per the design detailed in the drawing or as detailed by the Architect/ Engineer in-charge , front apron of size 2'0"x1'0" of Acrylic panel to be fixed with stainless steel studs ( 4 nos).The bank logo sticker of size 1'0"x1'6" to be fixed on the Acrylic panel. Each counter shall be provided with approved make metal body key board tray with mouse pad and smooth wrist cushion pad and foot rest SS Pipe 50mm dia to be provided. The laminate colours for the counter/ table top ( 3" CB yellow), vertical sides, bands, skirting(3" CB Blue) etc shall be strictly as per the drawing.Hole of 2.5" size at the required location and provided with matching wire manager.				
14	<b>MANAGER TABLE</b> : Size : 6'0"x3'0"x2'6"				
	Same as above specification and fixed with 12mm glass top with bevelling on all sides.Manager Table of 6' 0" (L) x 3' 0" (W) x 2' 6" (H)	1	No		
15	<b>AEO/AUDITOR TABLE</b>				
	Auditor table (Size : 4'0"x2'3"x2'6" -1no & 3'4"x2'3"x2'6" - 1no) to be done with 19mm Plywood ( <b>BWR Grade</b> )IS303 vertical support and top.The table shall be divided with center vertical support so that two persons can share the same. To be provided with key boards - 2nos and footrest SS Pipe 50mm dia to be provided . Top finished with blue laminate, vertical and sides with white laminate and all inside/ hidden surfaces shall be painted with 2 coats of enamel paint over 1 coat of smooth putty finish. <b>8mm glass top</b> to be provided with high polish.	2	Nos		
16	<b>PRINTER TABLE</b>				
	Printer table (Size : 2'3"x2'3"x2'6" - 1 no) table to be done with 19mm Plywood (BWR Grade) top and fixed with 8mm glass top. A small stationary drawer - 1 no to be provided.	1	No		
17	<b>SORTING TABLE</b>				
	Sorting table (Size : 3'3"x1'9"x2'6" - 1 no) table to be done with 19mm Plywood ( <b>BWR Grade</b> ) top and finished with 1mm laminate.	1	No		
18	<b>SIDE STORAGE UNITS</b>				
	Providing and fixing storage units of following sizes, with necessary swinging shutters, all made of 19mm thick plywood ( <b>BWR Grade</b> )IS303 for sides, partitions, top, shelves, bottom, shutters. The exposed surfaces shall be finished with 1mm thick lamination of approved shade & brand. Unit shall have internally one horizontal shelf and vertical partition at necessary intervals, all made with				

	19mm thick plywood (BWR Grade). All <b>internal and hidden surfaces</b> shall be finished with <b>painted</b> . 12mm thick plywood ( <b>BWR Grade</b> )IS303 to be fixed for the rear surface cover with 1 mm thick lamination finish.				
	All the exposed edges shall be lipped with 3/4"x1/2" matching wood beading & neatly polished with 2 coats with melamine polish.( Payable area is per square feet of elevation area of storage units.) The shutters shall have godrej lock provision, D shaped SS 3" size handles, Ball catch, Auto close box hinges, SS Tower bolts as per the requirement.Recessed handle for all side units and half height storage (Shutter Handle -Aluminium 3012 with end cap )(Ebco/eqlt).				
a	Manager table Side Unit : 3'6" (L) x1'6"(W) x2'6" (H)	1	No		
b	Teller Cash (SWC) Side Table: 2'6" (L) x1'6" (W) x 2'6" (H) 1 no	1	No		
19	<b>FILE CABINETS</b>				
	Providing and fixing filing cabinet, made of 19mm Plywood ( <b>BWR Grade</b> )IS303 structure comprising of suitable intermediate horizontal racks with open type doors, finished with 1mm laminate and beech wood beadings neatly melamine polished and inside with painted. The shutters shall have godrej locks, D shaped SS 3" size handles, Ball catch, auto close box hinges, SS Tower bolts as per the requirement.Recessed handle for all storage units (Shutter Handle -Aluminium 3512 )(Ebco/eqlt). All lippings of beech wood (The size shall vary according to the site condition, please check the site condition before making the file cabinets)	150	Sft		
20	<b>VERTICAL BLINDS</b>				
	Providing and fixing of VISTA/ TRAC make vertical blinds of good quality fabric. The top rail shall be made of powder coated aluminium section with best quality sliding arrangement. The approved colour and pattern to be provided in consultation with the Architect.	50	Sft		
21	<b>COLUMN PANELLING</b>				
	Providing & fixing Column panelling using 8 mm thick plywood ( <b>BWR Grade</b> )IS303 fixed over a 2 ft x 2 ft grid and of 2" x 2" wooden section made of hard wood frame work for the wall surface and covering the same with 1.0 mm thick laminate of approved brand and shade. The exposed edges shall be finished with moulded corner matching (beech) wood beading with polish finish.	200	Sft		
22	<b>WRITING DESK</b> - Size : 5'0"x 1'0"x 3'6" - (1 no)				
	Writing desk to be done as per plan with 12mm glass topped with 19mm Plywood ( <b>BWR Grade</b> )IS303structure with boxing as per design, finished with 1mm laminate outside and inside. Suggestion / complaint box and cheque drop box with view glass and locking provision in	1	no		

	same manner to be provided along with the writing desk.( refer dwg)				
23	<b>NOTICE BOARD - Size : 5'0"x4'0" - (1 no)</b>				
	Providing and fixing to the wall , notice board of size 90 cm x 120 cm, with 18 mm BWR grade plywood as base with 1 mm Blue colour laminate pasted on to it on both faces and edges to be edge banded with matching colour. The board shall have sandwich panels of different sizes as shown in the drawing. The panels shall be made of 2 nos 6mm thick acrylic boards fixed to the board using 12mm Glass studs ,and notice board sticker also to be included , labour charges etc complete.	1	no		
24	<b>TROPHY STAND - Size : 3'0"x0'6" - (3nos)</b>				
	Providing and fixing of trophy stand with 12mm thick glass is fixed using F bracket .	3	nos		
25	<b>MINERAL FIBRE BOARD GRID TYPE FALSE CEILING</b>				
	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with Bevelled Tegular Edge Tiles(600 x 600mm) of 16mm thick and 15mm face exposed grid. (Classic Lite RH99 Armstrong or eqlt..)	520	Sft		
	The tile shall be laid on profile grid system with 15mm white flanges incorporating a 6mm central reveal in white/black colour with mitred ends & "bird's mouth" notches to provide mitred cruciform junctions colour global white (Matching to tile color).Grid shall have double stroke rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 38mm (all sections). The deflection loading of the system shall be 7.9 kg/m <sup>2</sup> (as per standard installation layout mentioned below) and main beam tested as per ASTM C635 (Deflection limit less than L/360) with a deflection loading of 9.5 kg/m. The end details of the cross tee shall be made of pre hardened steel clip fixed to the ends of the cross tee to provide double locking between "cross tee to cross tee" and "cross tee to main beam". All main beam to main beam and cross tee to cross tee connection shall have a pull out strength of more than 100kg. The T Sections shall be made of 90 gsm as per IS 277 (2003) pre-painted steel with baked polyester paint of oT bending capability.				
26	<b>GYPBOARD FALSE CEILING</b>				
	Providing and fixing stepped suspended false ceiling with Gypboard of 12.5mm thick to the suspended grid formed of perimeter channel of size 20 x 27 x30 mm (MF6A) and intermediate channel of size 45 x 15 x 0.9 mm (MF7)The G.I. Ceiling section of size 80 x26x0.5 mm (MF .5) shall be provided across the intermediate channel at intervals not more than 475 mm c/c at bottom and the same shall be fixed by GI connections clips of 2.64mm dia at integration	990	Sft		

	points.The Ceiling channels shall be provided with a minimum overlap of 150mm at ends and fixed to the perimeter channels. Only horizontal measurements will be taken for bill calculation. Step/vertical area cost to be included.				
	The suspended strap hangers to be connected with G.I soffit cleat of size 37 x27x25x1.5 mm thick and to be fixed on to the roof slabs/beams by using metal expansion fasteners of 12.5 mm dia to a length of 35 mm.The suspender supporters shall be provided at intervals not more than 1200 mm c/c Additional perimeter channels have to be provided around the cut for light fitting A/C diffusers etc. Additional support for cut outs to be provided at no extra cost. The Gypboard sha;; be fised top the inder side of the suspended grid by using 25mm long dry wall screws. The joints shall be finished with joint paper tape and jointing compound of India Gypboard Ltd. and providing necessary plaster of paris putty.				
	After preparing the surface,Gypboard surface has to be painted with two coats of emulsion of approved make and shade over a coat of primer. Rate shall include making necessary cuttings for light fittings AC diffusers and other fixtures. No deductions shall be made for the opening and no extra payment made for forming any opening up to 0.5 sqm(per opening)				
	The work shall be carried out as per the manufactures specifcations using cold rolled Gypsteel and Sypsum boards manufactured by Gypsum India Ltd.				
	FINISHED PLAN AREA , EXCLUDING THE VERTICAL DROPS WILL BE MEASURED FOR PAYMENT.				
27	<b>WICKET GATE (DOUBLE DOOR) Size 4'0"x2'6" - 1no</b>				
	Providing and fixing of solid flush doors of wicket double door size 4'0" wide and 2'6" high and fixed with 1 mm laminate on both sides. The edges of the door shall be lipped with 6mm thick beach wood beedings. SS handles and tower bolt to be fixed. All the exposed wood shall be neatly finished with melamine polish.	1	no		
28	<b>PANTRY TABLE: - Size : 8'0"X1'9"x2'6" - (1 no)</b>				
	Supplying and fixing of pantry table using 18mm plywood (BWR Grade)IS303 with proper support and finished with matching lamination sheet, provided for keeping bags and tiffin carriers.Counter top fixed with 20mm edge polished Black Granite slab.	1	no		
29	<b>SHUTTER BEAM BOX</b>				
	Providing and fixing ACP for Shutter Box as per Architect's suggestion using 3mm thk Normal Aluminium Composite Panels of approved make over necessary frame work. The joints formed by the junction of two panels shall be filled with silicon sealent. However, only exposed portions shall	70	sft		

	be considered for payment. The bottom panel should be hinged and openable for maintenance of Rolling Shutters. and rates shall be including all accessories hinges, handles, ball catches, etc., complete. Pattern of panelling to be approved from the Architect/Bank. The cost includes MS works and all labour., complete				
30	PU Tactile tiles (directional - 4 strips & warning - 36 studs) with anti-slip pattern: Supply and fixing self - adhesive PU Tactile tiles (yellow) of approved make 300x300x5mm at entrance and ramp as per direction of architect/bank.	15	RM		
31	Providing and fixing 50 mm wide Yellow colour, self-adhesive "EDGE STRIPS" of approved make on risers of staircase to help persons with visual disabilities and elderly including cutting and pasting complete in all respect as per direction of architect/bank	5	RM		
<b>TOTAL (A) (GST EXTRA)</b>			<b>Rs.</b>		
<b>B</b>	<b>ATM</b>				
<b>1</b>	<b>NON GLAZED PARTITION</b>				
	Providing & fixing Non glazed partition upto ceiling height using aluminium rectangular sections size of <b>63.5mmx38.1mm Aluminium frame 1.70 mm thickness</b> for all horizontals & verticals spaced at 2 ft centre to centre or part thereof both ways for supporting frame work. All the panels and on both sides of the partition to be covered with 6mm thick Plywood ( <b>BWR Grade</b> ) <b>IS303</b> and over that 1mm thick laminate of approved colour and brand to be pasted, 3" border(CB Yellow) @ 7' ht to be done. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly necessary cuttings to be made in the plywood ( <b>BWR Grade</b> ) <b>IS303</b> surface to fix switch boxes of electrical, telephone sockets, computer Information outlets etc.(Frame work to be supported from the rcc ceiling)	30	Sft		
<b>2</b>	<b>COMPOSITE PARTITION (one side plywood and one side Bison board)</b>				
	Providing & fixing composite partitions at UPS room as per design with fixed on framework using aluminium rectangular sections of <b>63.5mmx 38.1mm Aluminium frame &amp;1.70mm thickness</b> Spacing of verticals should not be more than 600mm 2 ft centre to centre and covered on one side with 6 mm thick <b>IS303 (BWR) Grade Plywood</b> and the other side with 8mm thick bison board and over that 2 coat of emulsion paint approved colour to be painted. The partition should withstand its weight. The plywood surface shall be finished with 1mm thick laminate 3" skirting (CB Blue) & 3" border (CB Yellow) @ 7' ht to be done and the Joints between the Cement board shall be fixed with	100	Sft		

	fiberglass joint mesh and finished with putty. Door to be done in same manner with view glass (1'6"x 1'0"). Size: 2'6"x7'0" with Cylindrical locks, handle, ss hinges, door closure & stopper				
3	<b>FULLY GLAZED PARTITION</b>				
a	<b>FRONT BOTH SIDE FIXED PARTITION</b> : Providing and fixing Fully glazed partition <b>ATM Entry</b> in front (exterior side) , <b>12 mm thk toughened glass</b> of approved make with patch fittings and Entrance glass with necessary etching designs as per the approved design with Bank logo & border design.All edges of the glass to be machine polished (Frame work to be supported from the rcc ceiling, but the final measurement for billing would be taken below the false ceiling level only)	35	Sft		
b	<b>ENTRANCE DOOR</b> : Providing and fixing Fully glazed door for ATM entrance of <b>12 mm thk toughened glass</b> of approved make with patch fittings and Entrance door glass with necessary etching designs as per the approved design with Bank logo & border design.All edges of the glass to be machine polished.Door to be provided with 16" SS handle of approved make with rubber beading ,Glass to glass lock round type (w/o cut out) and fixed with branded floor spring and floor to door lock of approved make. ATM Door size : 3'6"x7'0" - 1 no.	25	Sft		
4	<b>ACP WALL PANELLING</b>				
	Providing and fixing ACP for ATM Wall as per Architect's suggestion using 3mm thk Normal Aluminium Composite Panels of approved make over necessary frame work. The joints formed by the junction of two panels shall be filled with silicon sealent. However, only exposed portions shall be considered for payment. Pattern of panelling to be approved from the Architect/Bank. The cost includes MS works and all labour., complete	145	sft		
5	<b>GYPBOARD FALSE CEILING</b>				
	Providing and fixing stepped suspended false ceiling with Gypboard of 12.5mm thick to the suspended grid formed of perimeter channel of size 20 x 27 x30 mm (MF6A) and intermediate channel of size 45 x 15 x 0.9 mm (MF7)The G.I. Ceiling section of size 80 x26x0.5 mm (MF .5) shall be provided across the intermediate channel at intervals not more than 475 mm c/c at bottom and the same shall be fixed by GI connections clips of 2.64mm dia at integration points.The Ceiling channels shall be provided with a minimum overlap of 150mm at ends and fixed to the perimeter channels. Only horizontal measurements will be taken for bill calculation. Step/vertical area cost to be included.	65	Sft		
	The suspended strap hangers to be connected with G.I soffit cleat of size 37 x27x25x1.5 mm thick and to be fixed on to the roof slabs/beams by using metal expansion				

	fasteners of 12.5 mm dia to a length of 35 mm. The suspender supporters shall be provided at intervals not more than 1200 mm c/c. Additional perimeter channels have to be provided around the cut for light fitting A/C diffusers etc. Additional support for cut outs to be provided at no extra cost. The Gypboard shall be fixed to the inner side of the suspended grid by using 25mm long dry wall screws. The joints shall be finished with joint paper tape and jointing compound of India Gypboard Ltd. and providing necessary plaster of paris putty.				
	After preparing the surface, Gypboard surface has to be painted with two coats of emulsion of approved make and shade over a coat of primer. Rate shall include making necessary cuttings for light fittings AC diffusers and other fixtures. No deductions shall be made for the opening and no extra payment made for forming any opening up to 0.5 sqm (per opening)				
	The work shall be carried out as per the manufacturer's specifications using cold rolled Gypsteel and Gypsum boards manufactured by Gypsum India Ltd.				
	FINISHED PLAN AREA, EXCLUDING THE VERTICAL DROPS WILL BE MEASURED FOR PAYMENT.				
6	<b>SHUTTER BEAM BOX</b>				
	Providing and fixing ACP for Shutter Box as per Architect's suggestion using 3mm thk Normal Aluminium Composite Panels of approved make over necessary frame work. The joints formed by the junction of two panels shall be filled with silicon sealant. However, only exposed portions shall be considered for payment. The bottom panel should be hinged and openable for maintenance of Rolling Shutters. and rates shall be including all accessories hinges, handles, ballcatches, etc., complete. Pattern of panelling to be approved from the Architect/Bank. The cost includes MS works and all labour., complete	70	sft		
7	<b>VISUAL MERCHANDISING UNIT</b>				
	Providing and fixing Visual Merchandising Unit of height 120cm at a suitable location. The Visual Merchandising Unit shall have 60 cm width, 30 cm depth and 120cm height. The pamphlet holder base and side shall be made of 12mm thick BWR plywood and laminated with 1mm thick matt finished laminate inside. The writing surface shall be made out of 12mm glass supported by 12mm glass separators. The bottom portion of the writing ledge shall be a suggestion box fabricated with 18mm BWR 303 plywood structure covered with ACP. The shutter of the box shall be made of 6mm flexiply in 2 layers covered with ACP on the visible front side. The box shall be provided with slots for dropping complaints. The side of the box should be openable to access inside with handle and lock arrangement. A notice board with cloth over softboard	1	no		

	and a curved pelmet of 4 cms thickness above it shall be provided. The pelmet shall have provision for fixing of round light fixed under it. ACP to be provided for pelmet and all exterior surface of visual merchandising unit.				
8	PU Tactile tiles (directional - 4 strips & warning - 36 studs) with anti-slip pattern: Supply and fixing self - adhesive PU Tactile tiles (yellow) of approved make 300x300x5mm at entrance and ramp as per direction of architect/bank.	5	RM		
9	Providing and fixing 50 mm wide Yellow colour, self-adhesive "EDGE STRIPS" of approved make on risers of staircase to help persons with visual disabilities and elderly including cutting and pasting complete in all respect as per direction of architect/bank	2	RM		
	<b>TOTAL (B) (GST EXTRA)</b>		<b>Rs.</b>		
	<b>Grand Total (GST EXTRA) = A + B</b>		<b>Rs.</b>		

Total cost for the works in words Rupees. \_\_\_\_\_

\_\_\_\_\_ Excluding GST

Note: Rate quoted should be excluding GST

All pages of the tender document should be submitted with sign and seal.

Public

SIGNATURE OF TENDERER WITH SEAL