

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
A	GROUND FLOOR INTERIOR (BRANCH)				
1a	BRANCH ENTRANCE - MAIN DOOR (Teak wood Frame with Toughened Glass): Providing and fixing partly glazed door 7' X 3' using 5"X1 3/4" teak wood frames for all sides, 12mm thick toughen glass of standard make (modi/saint gobain) with double line border etching and design as specified by bank & fixed with necessary teak wood beadings and polishing. The doors to be fixed to frames using top and bottom hinges , patch fittings/floor springs etc as necessary. The Teak Wood frames should be neatly polished with 2 coats of melamine wood polish & stained to the required colour. Providing and fixing GODREJ/OZONE/EQUIVALENT MAKE SS 304 Pull handle-D-Type (25 dia. X 450 mm) to the Main BRANCH/ ATM entrance door. Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS:6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing, stainless steel cover plate of minimum 1.25mm thickness, with brass pivot and single piece M.S. sheet outer box with slide plate, etc., complete as per the direction of Engineer-in-charge	3.00	nos		
b	BRANCH ENTRANCE PARTITION: Providing and fixing wooden partition using 2" X 1" 1.5MM thick concealed Aluminium section frames in both directions with verticals at a spacing of 2 feet c/c in both directions, covered with 9mm thick BWR grade plywood treated with anti termite oil , 1mm thick lamination on both the sides, 12 mm thick float glass (brand as per material specification mentioned) with double line border etching/frosting, fixed with necessary teak wood beadings and minimum 2 coats of polishing.The door area will be deductible from the payable area.	110	sft	Internal	
2	Providing and fixing FULL HEIGHT PARTITION with GLAZED PANEL in double skin of 9mm thk.BWR grade ply with 1.0mm thk shell finish laminate on both sides fixed to natural melamine polished teak wood bottom, middle and top rail of 3" x 2" and concealed Alumimium section verticals of 2" x1" at not more than 4'-0" apart including fitting door frame where indicated with teak wood frame of 4" x 2" complete as shown in drawing. Each cabin shall have one door 3'-0" x 7'-0" size with 6" handles on both sides, brass hinges,Door closure (heavy duty) of approved make & locking arrangements(the door to be made out of 32mm block board) . it shall be of natural melamine polished teak wood, above 3'-0" with 6mm plain float glass and 12mmx12mm TW beading, all in natural melamine mate polished, incl. fitting door frame where indicated with teak wood frame of 4" x 2" complete as shown in drawing. (Verticals to go upto the RCC roof for support, but measurement rate shall be made only upto the false ceiling only and shall not incl. the door shutter which is a seperate item).	155.00	Sft		

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
3	LOW HEIGHT SOLID (4'-0" ht.) , Providing and fixing barrier partitions (maximum 4' in height at centre) between bank counters in Aluminium framework of size 2" x1" at maximum spacing of 600mm c/c both ways with 9 mm thk BWR plywood to both sides finished with 1.0 mm thk laminate fully finished with a bottom skirting as per design, 12 mm thk clear glass ,all exposed edges to be provided with TW lipping finished with melamine polish complete as per the drawing and as directed.The Low height partition is inclusive of the Flap Door including all accessories of a approved brand such as locks, handles, etc., complete as shown in drawing.	96.00	Sft		
4	Providing and fixing FULL HEIGHT SOLID PARTITION in double skin of 9mm thk.BWR grade ply with 1.0mm thk shell finish laminate on both sides fixed to natural melamine polished teak wood bottom, middle and top rail of 3" x 2" and concealed Aluminium section verticals of 2" x 1" at not more than 4'-0" apart including fitting door frame where indicated with teak wood frame of 4" x 2", complete as shown in drawing. (Verticals to go upto the RCC roof for support, but measurement rate shall be made only upto the false ceiling only and shall not incl. the door shutter which is a seperate item).	390.00	Sft		
5	CASH / SWC CABIN'S PARTITION (front side) : Cabin partition made out of (Alumimium section)frame work (3"x2") of outer section & intermediate section of 2"x2" at 2'-0" c/c both ways fixed firmly to the partition & floor with screws, clamps etc. both sides shall be provided with 9mm thick marine BWR grade ply wood secured firmly to the frame with adhesive & chromodised screws up to 2'-6" & above that 3'-0" of 12mm thick clear float glass with etching in single panel fixed to the frame with 25mm x 19 mm (1"x ¾") teak wood moulding / beading on both sides and with 1.0mm thickshell finish laminate, partition wall height shall be 7'-6" from floor level, Complete as shown in drawing.	35.00	Sft		
6	Providing and fixing CASH / SINGLE WINDOW COUNTER TABLE TOPS (5'-0"X2'-9", side table of 3'-0"X1'-3") and Keyboard to be fixed for every cabin, in 18mm thk. marine BWR grade ply horizontals above in 20mm thk. black polished granite at customer ledge of 16" with edge grinding at nosing done at the corner surfaces fixed on top, front edges of ply to be 2" x 1" thk. TW frame on the outside, polished (1"x ¾") teak wood moulding / beading to all exposed edges of ply, all internal exposed surfaces of the table to be painted with two coats of synthetic enamel paint on plywood after one coat of primar, complete as shown in drawing, Complete as shown in drawing.	1.00	no		

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
7	CASH (enclosure) / SWC CABIN'S PARTITION (other 3 sides): Cabin partition made out of (Alumimium section) frame work (3"x2") of outer section & intermediate section of 2"x2" at 2'-0" c/c both ways fixed firmly to the partition & floor with screws, clamps etc. both sides shall be provided with 9mm thick marine BWR Grade ply wood secured firmly to the frame with adhesive & chromodised screws up to 3'-6" & above that 2'-0" of 6mm thick clear float glass with either stickering in single panel fixed to the frame with 25mm x 19 mm (1"x ¾") teak wood moulding / beading on both sides and with 1.0mm thickshell finish laminate, partition wall height shall be 7'-6" from floor level and Each cabin shall have one door 2'-6" x 7'-0" size with 6" handles on both sides, brass hinges,Door closure (heavy duty) of approved make & locking arrangements & provision for slip trays. Providing and fixing Duro lock in Cash cabin / SWC Counter Complete as shown in drawing.	56.00	Sft		
8	ALLUMINIUM GRILL with white/ivory powder coating for Cash cabin top & Strong room inside Safe room partition 8'feet hight above upto to of the ceiling.	73.00	Sft		
9	Providing and fixing CLERICAL/OFFICER (running counters) without side unit TABLE of 4'-0"/5'-0"X 2'-6" , table made out of 18 mm BWR grade ply board (approved make)structure with edges fixed with teak wooden lipping ,having officer table top 2'-6" from the ground level & 2'-6" clear top width. Each unit shall be provided with a sliding key board tray 2'-3" of wide with sliders, cupboard below the drawer with locking arrangements aluminum handle, brass hinges etc the front back & top surface shall be laminated with 1.0mm thickshell finish laminate.8mm thk plain glass on table top as per shape with cutting for wire manager. The edges are to be neatly finished as per the shape indicated by Engineer in charge.The internal surface shall be painted with to coats of enamel paint (VANILLACREAM, CODE - 3229) of Asian paints, over a coat of primer. Provision for footrest of size 75mmx 38mm shall be made at the bottom. Wire manager shall be provided at the corner of the counter top. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x ¾" inner side) and polishing done etc. complete as shown in drawing.	3.00	nos		
10	BRANCH MANGER TABLE (6'-0"x3'-0"): Fabricating manger's Table made out of 18mm BWR Grade ply, having table top 2'-6" height from the ground level & 3'-0" clear top width,a unit of drawer in 18mm thk BWR plywood. it will have a side table of size 1'-6" x 3'-6" Table shall be provided with a sliding keyboard tray 2'-3" wide with slider, 2nos drawers on either sides and cupboard below the drawer locking arrangements, aluminum handles, brass hinges etc all exposed surface shall be laminated with 1.0 mm thick shell finish laminate. 8mm thk plain glass on table top as per shape with cutting for wire manager. The internal surfaces shall be painted with two coats of enamel paint over a coat of primer. Provision for foot rest of size 75mm x 38mm shall be at bottom .wire manger shall be provided to the counter all exposed edges of the block board shall be provided with teak wood beading and polishing etc, complete. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x ¾" inner side) and polishing done etc. complete as shown in drawing.	1.00	No		

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
11	Providing and fixing <u>OFFICER/MANAGER TABLE with SIDE UNIT of 5' X2'-9"</u> , table made out of 18 mm BWR grade ply board (approved make)structure with edges fixed with teak wooden lipping ,having officer table top 2'-6" from the ground level & 2'-6" clear top width, a unit of drawer in 18mm thk BWR plywood. it will have a side table of size 1'-6" x 3'-0". Each unit shall be provided with a sliding key board tray 2'-3" of wide with sliders, cupboard below the drawer with locking arrangements aluminum handle, brass hinges etc the front back & top surface shall be laminated with 1.5mm thick rubber wood laminate.12mm thk plain glass on table top as per shape with cutting for wire manager. The internal surface shall be painted with to coats of enamel paint (VANILLACREAM, CODE -3229) of Asian paints, over a coat of primer. Provision for CPU stand 1'-0" x2'-0"(if required) & footrest of size 75mmx 38mm shall be made at the bottom. Wire manager shall be provided at the corner of the counter top. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing.	2.00	No		
12	FALSE CEILING				
12a	FALSE CEILING (GRID) : The grid false ceiling shall be provided in the Banking Hall, Manager's etc. Refer drwgs. the ceiling height and level shall be provided at the perimeter. The minimum height of the ceiling cavity should be 100mm. All service fittings integrated within the suspended ceiling must be independently supported from the ceiling grid by a structure designed for the purpose. Ceiling tiles: shall be armstrong fine figured classic lite RH99 of 16mm thickness. Suspension system: shall be of armstrong trulok silhouette reveal profile grid system with 15mm flanges incorporating 3mm central recess in global white with black reveal. silhouette main runners and cross tees to have mitred ends and "birdsmouth" notches to provide mitred cruciform junctions.	1,000.00	sft		
	Installation: main runners will be placed at 1200mm centres securely fixed to the structural soffit by approved hangers at 1200mm maximum centres and not more than 150mm from spliced joints. the last runner at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mm long cross tees to be interlock between main runners at 600mm centres to from 1200x600mm modules. cross tees 600mm require independent support. 600x600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200mm cross tees. the 1200mm cross tees to have central "birdsmouth" notches to facilitate fitting of 600mm cross tees. the perimeter trim to be armstrong trulok equal wall angle of white color secured to walls at 450mm maximum centres.complete as shown in drawing.				

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
12b	FALSE CEILING: Provided & fixing with Indian gypsum or equivalent suspended false ceiling two coat Luppam and two coat of acrylic emulsion paint. (in any shape as shown in drawing) which includes providing and fixing G.I perimeter channels of 0.55mm thk having one flange of 20mm & another flange of 30mm & a web of 27mm along the perimeter of the ceiling, screw fixed to the brick wall with the help of nylon sleeves & screws, at 610 mm centers. as per manufacturers spec.s, taping of joints and finishing. finally the board are to be jointed and finished so as have a flush lock which includes filling & finishing tapered square edges of the boards with jointing compound, paper tape and with one coat of lappam perfectly to level the surface, complete as shown in drawing.	86.00	sft		
13	Front RUNING GLASS FRONT above front counter tables (1'-3" ht.) of 12mm thk glass with edge rounding and this is fixed to the 3"dia TW pillars / side partition with coping on the top at the every edge of the table. complete as shown in drawing.	27.00	Rft		
14	Storage cabinet/cupboard: Providing & fixing storage units/siderunners of size 1' 6" wide, 2' 6" height side runners all using MR Grade commercial plywood confirming to IS303-1989. Runnertop,verticals,bottom and centre shelf should be fabricated using 19mm ply, back with 19mm ply and front side shutter with 19mm ply.The shutter with 19mm thk. ply fixed with the help of hinges with two godrej locks.The runner top & all the exposed vertical surfaces shall be finished with 1.00mm thick laminate of approved colour and make.Inner surface should be finished with 0.8mm laminate. All exposed edges of plywood should be fixed with 6mm thk.TW beading and polished. All complete as design and as per standard specifications.	92.00	sft		
15	WRITING TABLE: Minimum dimension of 3'-0"x2'-0" table made out of 12mm glass supported in the center by 6" dia steel pipe grounded to the floor with screws &bolts at a height of 3'-6" & glass edges bewelled to half rounded shape. complete as shown in drawing.	1.00	No.		
16	Providing and fixing CHECK DROP/ SUGGESION BOX (1'-2"X1'-2"X1'-6"ht.) in 18mm thick BWR grade ply, for verticals and horizontals with 1.0mm thk shell finish laminate on all visable outer surfaces with drawer slides incl. all accssories such as handles, auto closing hinges, single key locking system for drawers, complete as shown in the drawing. All exposed ply surfaces to be painted with two coats of synthetic enamel paint on plywood after one coat of primer.	2.00	No.		
17	Providing and fixing Notice Board with pin up board covered with tapestry cloth of size 4' x 3' made of 12mm thick ply wood and finished with 1mm thick laminate and teak wood beeding etc., for appellate authority board, Notice Board, Working hours Board etc	1.00	No.		
18	Providing and fixing Notice Board with pin up board covered with tapestry cloth of size 2' x 3' made of 12mm thick ply wood and finished with 1mm thick laminate and teak wood beeding etc., for appellate authority board, Notice Board, Working hours Board etc	1.00	No.		

S.No	Item	Qty	Unit	Rate in Rupees	Amount (Rs. P.)
19	Providing and fixing FLUSH DOORS of 32mm thk with 1.0 mm thk. shell finish laminate both sides with TW polished edge beading to all in exposed edges, hole cuttings in any shape and size with 6mm glass fixing to TW beading in the door including all accessories of a approved brand such as locks, handles, etc., complete as shown in drawing.	147.00	Sft		
20	VERTICAL ROLLER BLINDS:Providing Roller blinds of (ivory) guardian tilter wand cord lock 4" wide strip complete as per architect direction.	120.00	Sft		
21	Providing and fixing cupboard with shutters for covering electrical panel board, etc., with 18mm BWR ply with 1mm thick shell finish laminate of approved shade and make on outside including painting of inside with primer and two coats of synthetic enamel paint, and providing teak wood beading to all exposed edges, inside of the entire cupboard is to be fixed with the bison board (Fire Proof) to the existing ply wood including all accessories hinges, handles, ballcatches, etc., complete.	50.00	Sft		
22	ACP Panelling (ATM WALLS & ROLLING SHUTTER COVERING): Providing & fixing in position partition made of ACP (Aluminium Composite Panel) with framing of Aluminium Tube sections of min 1.5" x1" and 18 gauges 2'-0" C/C both ways. ACP to be in 2' wide panels or distributed equally. The panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with Silicon based sealant. ACP thickness of 3mm min. Aluminum foil thickness to be 0.20 mm. ACP only on the ATM side with thickness of 3mm minimum. Alubond, Eurobond, Fujibond, Alcobond, Prime Bond or equivalent brands to be used. ACP Door 3'X7' made of Aluminum frame. Trap door to be finished with ACP.	82.00	Sft		
A	TOTAL AMOUNT FOR BRANCH INTERIOR WORKS :				
	DISCOUNT :				
	GRAND TOTAL AFTER DISCOUNT :				
AMOUNT IN WORDS: Rs.					
GST 18% EXTRA					