

CANARA BANK, REGIONAL OFFICE - DURGAPUR

B O Q FOR INTERIOR FURNISHING WORKS

SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	Dismantling existing wooden partition, door etc. located within working area and relocating garbage at a suitable location as shown for acutioning by the bank.	1.00	unit		
2	Providing and fixing in position full height solid partition 65 mm thk. excluding the door made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick, as internal framed structure placed horizontally & vertically in 600mm x 600 mm center to center or as directed by the Architect. The alternate corner vertical members of the partition shall be taken upto the ceiling level (payment shall be made for the partition measured below the false ceiling level) and the same shall be anchored to the ceiling securely with help of suitable cleats. Framework shall be fixed with 6 mm thick marine grade ply (IS - 710) of approved make on both sides finished as per following specifications. The Partition shall be finished with 1.0 mm thick laminate of approved shade and make or equivalent on both the sides. Rate shall be inclusive of provision of pencil groove as directed by the Architect. The ply surface of the groove to be melamine polished. Height of the partitions upto soffit of false ceiling / laminate finish top shall be considered for payment. All corner vertical members of the partition shall be fixed with necessary brackets /supports at RCC levels. The framework above the false ceiling shall not be considered for payment. The item does not include the doors.	265.83	sq. ft.		
3	Providing and fixing Solid Core Flush Door Shutter of 35 mm thk. finished both side with 1 mm thk. approved colour laminate (IS : 2046) with 1.5 mm. groove design fixed to Wooden framework of partition. One vision panel of size 6"x 10" made out of 6 mm thk. Clear glass with moulding with polish to be provided. The rate shall be inclusive of fitting and fixing of 3 nos. 4" s/s hinges, door closer, door stopper, screws, mortice lock, tower bolt of approved make. All edges of the door to be covered with necessary lipping with polish finish. The work should be completed as per specification, design and approval of Architect.				
a	Shutter size : 900 mm. x 2100 mm.	126.00	sq. ft.		
4	Providing & Fixing double skin low ht. partition including wicket door (1400 mm. high) with electrical wire management system, 1000 mm. solid & 300 mm. above glazed & again 100 mm. solid at top, made of aluminium hollow sections of 50mm x 50mm size 1.5mm thick, as internal framed structure placed horizontally & vertically in 600mm x 600mm center to center bothways, double skin partition fixed to aluminium frame made of 6 mm. thk. approved marine grade ply (IS:710), finished both side with approved laminate with 1.5 mm. groove design, 4" high laminated skirting etc., the vertical support of 50 x 50 mm. frame to be extended upto 1400 mm., side & top faces to be covered with 35 x 10 mm. CP teak wood moulding to hold 300 mm. high x 6 mm. thk. glass. The glass will have necessary frosted film design. All exposed teak wood surface to be completed with natural colour high polishing etc. all complete as per design, direction and approval of the Architect.	87.73	sq. ft.		

SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
5	Providing and fixing Storage Unit made out of 19 mm BB for top, sides & 6 mm ply for back finished with 1.0mm laminate. The shelves are made of 19 mm. thk. BB at 400 mm to 425 mm c/c. The shutters to be made out of 19 mm BB with 1.0 mm laminate. The necessary godrej multipurpose locks, 6" SS matt finished handles, SS hinges are to be provided. 4" laminated skirting to be provided as per matching tone. Inside of the storage unit to be synthetic enamel painted in matching tone. All the exposed edges of the boards/ plywoods to be covered with teak wooden lippings/ mouldings duly natural polished all complete. For full ht storage, shutters are to be divided vertically into two parts. The work to be completed as per approval and specification of the architect.				
a	Low Height Storage (1000 mm. high)	332.85	sq. ft.		
b	Full Height Storage (2400 mm. high)	172.25	sq. ft.		
6	Providing & erecting in position free standing table made of 19 mm. thk. BWP grade block board for sides, top & modesty panel, finished with 1 mm. thk. laminate of approved shade & make in outer faces. Inside of the table to be finished with synthetic enamel paint / polish as per matching tone. Drawer cum cabinet unit of approx. overall size of 400 x 600 x 725 mm. (h) of 19 mm. thk. block board. The drawer unit shall comprise of 1 drawer, 1 cabinet with inner faces polished / synthetic enamel painted with approved shade with telescopic drawer slides. the drawer unit shall be finished with 1 mm. laminate. The quoted price should include cost of teak wood moulding to edges, wood lipping, multi locks of Godrej make & other necessary hardware accessories including SS handles, pvc wire manager, keyboard tray (INNOFIT make), mobile CPU trolley, foot rest etc. of approved quality. All table should have a side credenza which shall be 900 mm. long., 400 mm. wide & 750 mm. high with intermediate 1 no. shelf of 19 mm. BB. The side credenza have sliding shutters of 12 mm. thk. ply with 1 mm. thk. laminate finish on visible side. Inside of the unit to be synthetic enamel painted / polished in matching tone. All the ply edges should be lipped & finished with prescribed shade of polish. The rate also include the cost of hardwares like hinges, tower bolts, handles, magnets, wire manager etc.				
a	size : 1500 mm. x 750 mm. x 750 mm.(h) including side credenza & 10 mm. thk glass top with hole for wire manager	8	no.		
b	size : 1200 mm. x 900 mm. x 750 mm.(h) without side credenza but including 10 mm. thk glass top with hole for wire manager	10	no.		
7	Providing and making Conference Table of over all size of top as 1800 mm. x 6000 mm. & 750 mm. high. It shall consist of 19 mm thk. marine grade ply (IS-710) top as per design finished with 4mm thk teak veneer with PU polish finish of approved shade and colour, supported on 5 nos of mullion boxes, as per design of size 900 x 300 mm. made of 19 mm thk. marine ply finished with 1mm thk laminate of approved shade. Mullion boxes are inter connected by 2 nos. boxing, 900 x 150 mm. on top (below table top) and 600 x 100 mm. at bottom (on floor level), finished in laminate of approved shade. The edge of the table top to be of 38 mm. thk.. Table top and its adjacent edges to be finished with teak wooden bead with PU polish finish or similar of approved shade and colour and other external surfaces with 1.0 mm thk laminate of approved shade. The table should have 3 nos. covered matching colour coated aluminium data grommet having adequate power and data sockets. The top surface of the grommet to be flushed with veneer top. The job to be completed as per direction of Architect.	1	unit		

SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
8	Providing and fixing at Wooden work for ceiling made by 6 mm thk marine grade ply (IS-710) to be finished in 4.0 mm thk. polished veneer of approved shade, fixed to suspended Gypsteel chanel of appoprete size to hold the ceiling ply. The item is to be completed in all respects as per design & approval of the architect. The rate to be included for making necessary cut outs for light fittings, ac unit or other equipments.	160.00	sq. ft.		
10	Providing & fixing in position wall / column panelling consisting of 6.0 mm thk. marine grade ply IS:710 with aluminium hat furring channel 22-25 @ 500 mm. both direction. The face of the cladding is to be laminated with 1.0 mm. thk. laminate of approved shade & groove design. The ply surface of the groove is to be melamine polish finished of approved colour. The item is to be completed in all respects as per design & approval of the architect.	337.26	sq. ft.		
11	Providing and fixing of wall paper of approve shade and pattarten of Marshall /Excell/ WK make to wall/partition as per instruction with adhesive including all labour and material. This is to be pasted over POP / Putty surface with primer finish (cost of primer to be included in the rate). The item is to be completed in all respects as per design & approval of the architect. (basic cost of wall paper : Rs. 50.00/ s.ft.) (Location : AGM rm & Conference rm)	820.00	sq. ft.		
12	Providing & fixing in position wall panelling (Location : Conference room) consisting of 9.0 mm thk. Polyester fibre acoustic panel to be fixed over 6.0 mm thk. marine grade ply (IS:710) with aluminium hat furring channel 22-25 @ 500 mm. both direction. The side / edge of the elevated panels to be covered with approved wooden finish laminate 1.0 mm. thk. The item is to be completed in all respects as per design & approval of the architect.	490.84	sq. ft.		
13	Providing and fixing Gypsum false ceiling which includes G.I perimeter channels of size 0.55mm thk. (having one flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling,screw fixed to brick wall/partition with the help of nylon sleeves and screws, at 610mm centres. Then suspending G.I intermediate channels of size 45mm (0.9mm thk. with two flanges of 15mm each) from the soffit at 1220mm centres with flanges of 26mm each with lips of 10.5 mm are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediated channel at 457mm centres.12.5mm tapered edge Gypboard (confirming to IS: 2095 - 1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centers. Screw fixing is to be done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edges of the boards with jointing compound. No extra payment will be made for the cutting of light points , stain glass,cove lighting etc. The measurement will be taken in one level. rate should include	1615.99	sq. ft.		

SI No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
14	Providing & Fixing of Acoustical Ceiling System at Office areas with Armstrong make Fine Fissured microlook edge with 'Revealed Black Grid' system. The tiles 'Armstrong Classic Lite H1892M' or similar with Bevelled Tegular edges should have thickness of 16 mm & Humidity Resistance of 99% RH, Average NRC 0.55, Light Reflectance >84%, Thermal Conductivity k = 0.052- 0.057 w/mK, Colour White, Fire Performance Class 0/Class 1 (BS - 476) in module size of 600mm x 600mm x 16 mm. with Providing and fixing Hot dipped galvanised Steel suspension system (Grid frame) for laying of Acoustical Ceiling Tiles. The item is to be completed in all respects as per design & approval of the architect.	1899.00	sq. ft.		
15	Providing and fixing vertical blinds of 100 mm wide (Mac/Annus) of approved shade and pattern having handrail made of high strength aluminium alloyed wll thickness of 1.2 mm thk handrail to have 25mm decorative insert. Control unit shall be of derlin. The runners are also to be a derlin withantifixtion adhesive. Spacers should be made of stainless steel. Fabric should be polyester viscoted/polyester yarn having protective coating with chemicals for stain resistance & soilrepalancy. The rate shall include necessary scoch gurd treatment on both sides. The overlapping should be uniform and adequate. Necessary operative arrangements frames to be provided. The work to be completed asper specification and approval of the Architect.	567.60	sq. ft.		
16	Providing and fixing soft board/ notice board fabricated out of 12mm BWR ply covered with 12mm soft board padding and upholsply propylene fabric @80/ mtr. Edges of the soft board should have white beach/white ceader moulding with natural polished. Size : 1200 x 750 mm. NB : where pin up board is in a panelled area, the top of the pin up board should be flushed with the panel, kepping the same level. The work should be completed as per design specification & approval of the architect.	60.00	sq. ft.		
GRAND TOTAL					

APPROVED MAKE OF MATERIALS

1	False Ceiling / Channels	India Gypsum / Armstrong / Saint Gobain
2	Wood Frame Work / Wood Section : All Wood, Must be well seasoned, free from knots, other defects decay and defects due to handling and Transportation. Wherever necessary, provide with anti - termite Treatment.	Malaysian Sal/ karpoor
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Ceader
4	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI / Bison by
5	Fire Reterdant Paint	Industrial grads of Noble / Viper
6	BWR Ply (IS-710) / BWP Block board with ISI mark	Century / Green / Sylvan
7	Flush Door	Century / Green / Sylvan
8	Laminate (1.0 mm thk.)	Green lam / Century mica / Sunmica
9	Door Closure (Heavy Duty)	Godrej / Archi / Sterling (DC 2000)
10	Floor Spring (Heavy Duty)	Godrej / Archi / Sterling (FS 3000)
11	Door Lock (Dead)	Godrej / Hafele /Hettich / Kich / Doorset / Yale
12	Door Handles	Godrej / Hafele /Hettich / Kich / Doorset
13	Drawer / Storage Handle	Godrej / Hafele /Hettich / Kich / Doorset
14	Drawer / Storage Lock (Multipurpose)	Ebco / Hafele /Hettich /Doorset
15	Night latch	Godrej / 4C Acme
16	Screws	GKW / Nettle fold
17	Hinges	CIEF
18	Sliding Telescopic Drawer Channel	Ebco / Kombo / Earl Behari / Efficient Gadjets
19	Cable Organiser	Ebco / Innofitt Systems (CM 63.C)
20	Adhesive	Fevicol SH / Fevimate TL
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annus / Window Fashion
23	Glass	Modi /Ashai / Saint Gobain
24	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / ICI
25	PVC Flooring	Krishna Vinyl / Armstrong / Bravo
26	All other items not covered above	As per sample approved by Employer/Consultant