

Section II (Computer wiring & Data cable work)					
SL No	Description of work	Unit	Quantity	Rate	Amount
C1	Concealed/Surface circuit wiring in 16/25mm pvc conduit (2mm Th) pvc conduit From UPS room to U.P.S D.B by (2x6+1x2.5) Sq mm FR PVC insulated copper wire make Havells/Finolex/Polycab/GM including PVC bent pipes, junction Boxes earthing etc. as/required .	RM	60.00		
C2	Concealed/Surface circuit wiring in 16/25mm Dia pvc conduit (2mm Th) for computer power with (2x2.5+1.5) Sqmm copper wire make Havells/Finolex/Polycab/GM pvc bent pipes junction boxes etc as/required from UPS D.B to each computer point through S.P MCB as per drawing.	RM	228.00		
C3	Supply and laying of computer data cabling wire DG-Link/GM CAT 6 with 16/25mm Dia PVC pipe (2mmTh) casing in floor/ wall as required from server to each computer CPU inlet. Note- 450 mm minimum distance between data cabel wire & power wire shoud be maintain horizontal & vertical.	RM	235.00		
C4	Supply & fixing Modular switch board with 5A switch 4 No & 5A 5pin socket 4 No with 1 No indicator & 1 No fuse of make Anchor/L&T/Havells	Each	20		
C5	Supply & fixing out let box DG-link	Each	20		
C6	Supply and fixing Cat 6 patch cord DG-Link approximately 2M length with Rj45 connector both side .	Each	20		
C7	14 Way double door SPN distribution board for UPS (1) 32 Amp DP MCB -1No (2) 10 Amp SP MCB -12 No MCB make by HPL/Standerd/L&T	Set	1.00		
Total section II-					
Total (Section I+II)-					
GST Extra as per Applicable.					

