

केनरा बैंक  Canara Bank



**TENDER FOR PROPOSED INTERIOR FURNISHING  
WORKS AT 2<sup>ND</sup> FLOOR V2 BUILDING, PROPERTY  
NO. 98/4, AIRPORT ROAD, HUBBALLI-580030**

: PRICE BID:

=====

**ISSUED BY**  
DEPUTY GENERAL MANAGER  
PREMISES & ESTATE SECTION  
CANARA BANK CIRCLE OFFICE  
52A, Shanbhag Building, Unkal Cross,  
Sai Nagar Road, Hubballi-580031  
Tel: 0836-2278860.  
e-mail: pecohub@canarabank.com





Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030

BILL OF QUANTITIES

No.	Description	Unit	Qty	Rate	Amount
A	<b>Partition, Paneling and Doors</b>				
	Note: Basic Rate of veneer Rs. 140/sft excluding taxes, transportation loading and unloading				
1	Providing and fixing full height Glass Partition. Partition to be made of 12mm thk toughened glass with exposed edges machine polished upto the false ceiling height. Partition to be fixed with SS glazed partition profiles/ channels of approved make and design, taking necessary MS / wooden supports from the existing ceiling. Ends of profiles to be closed with caps (fabricated in SS if not available in market). Cost inclusive providing and fixing 3M make "crystal design" frosted Film Sheet for the glass partition. All complete as per drawings and/or instructions of the architect.	Sft	1250		
2	Supplying and fixing Partly Glazed Full Height Partition. Partition from 3'-6" to 7'-0" height to be fixed with 12mm thk Float Glass Partition with exposed edges machine polished. Partition From floor to 3'-6" height and 7'-0" to the existing Ceiling height to be made of 2"x2" Aluminium frame work at 2'-0" center to center both ways. The frame work both sides to be covered with 8mm thk BWR plywood upto the false ceiling, finished with 4mm thk veneer / 1mm thk laminate with necessary inlays and grooves as per drawing. Partition at floor level to be fixed with 4" high skirting, made of 12mm thk BWR plywood finished with 4mm thk veneer / 1mm thk laminate and edges covered with approved wood beading. Cost inclusive providing and fixing 3M make "crystal design" frosted Film Sheet for the glass partition. All veneer and beading surface to be finished with melamine polish as instructed by architects. All as per drawings and/or instructions of the architect. All materials to be approved by the architects. Partly Glazed Full Height Partitions (finished with 1mm thk laminate with necessary inlays and grooves as per drawing).	Sft	2150		
3	Providing and fixing Full Solid Height Partition. Partition in 2"x2" Aluminium frame work at 2'-0" center to center upto the Existing Ceiling height. The frame work both sides to be covered with 8mm thk BWR plywood upto the false ceiling, finished with 4mm thk veneer and/or 1mm thk laminate with necessary inlays and grooves as per drawing. Partition at floor level to be fixed with 4" high skirting, made of 12mm thk BWR plywood finished with 1mm thk laminate and edges covered with approved wood beading. All veneer and beading surface to be finished with melamine polish as instructed by architects. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.				
a	Providing and fixing Solid wooden partition (One side Veneer Finish and other side laminate finish)	Sft	2500		
b	Providing and fixing Solid wooden partition (Laminate Finish)	Sft	1650		
4	Providing and fixing Low height partition (Laminate Finish) Providing and fixing 4'-0" to 4'-6" height Partly Glazed Partition. Solid Partition to be made of 2"x2" Aluminium frame work at 2'-0" center to center both ways. The frame work both sides to be covered with 8mm thk BWR plywood finished with 4mm thk veneer / 1mm thk laminate with necessary inlays and grooves as per drawing. Partition at floor level to be fixed with 4" high skirting, made of 12mm thk BWR plywood finished with 4mm thk veneer / 1mm thk laminate and edges covered with approved wood beading. Glazed partition to be made of 8mm thk Float Glass fixed with necessary wood beading [beach wood or equivalent]. Cost inclusive providing and fixing 3M make "crystal design" frosted Film Sheet for the glass partition and making necessary cutouts in glass wherever necessary. All veneer and beading surface to be finished with melamine polish as instructed by architects. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.				
a	Solid Low height partition (finished with 1mm thk laminate with necessary inlays and grooves as per drawing).	Sft	2400		
b	Fixing of 8mm thk float glass for the side partitions.	Sft	200		
5	Providing and fixing Full height Wall Panelling made out of 2"x1" Aluminium frame at 2'-0" c/c both way, covered with 8mm thk BWR plywood, finished with approved 4mm thk veneer / 1mm thk laminate with necessary inlays and grooves as per drawing. Paneling at floor level to be fixed with 4" high skirting, made of 12mm thk BWR plywood finished with 4mm thk veneer / 1mm thk laminate and edges covered with approved wood beading. All veneer and beading surface to be finished with melamine polish as instructed by architects. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.				
a	Full Height Wall Panelling (finished with 4mm thk veneer with necessary inlays and grooves as per drawing).	Sft	1800		



**Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030**

**BILL OF QUANTITIES**

No.	Description	Unit	Qty	Rate	Amount
b	Full Height Wall Panelling (finished with 1mm thk laminate with necessary inlays and grooves as per drawing).	Sft	2250		
c	Full Height Column Panelling (finished with 1mm thk laminate with necessary inlays and grooves as per drawing).	Sft	2450		
6	<b>Glass Doors</b>				
	Providing and fixing Glass Door. The glass shutter to be 12mm thk. toughened glass, all exposed edge machine polished. Shutter to be fixed with Patch Fitting. The door handle shall be 30mm thk. 750 mm long SS brush finished handles, lock as per approved design & make. The rate shall include the cost of all hardware such as patch fittings, handle, locks, rubber bushes etc. and other necessary hardwares. Cost inclusive providing and fixing 3M make "crystal design" frosted Film Sheet for the glass partition. All complete as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Sft	320		
7	Providing & fixing Door With View Panel. The door frame made of approved quality Beach/Safeli wood. The Shutter to be 32mm thk BWR Block Board with both side finished with 4mm thk veneer / 1mm thk laminate with necessary inlays and grooves as per drawing. The door inlet with 8mm thk glass. The edges of the door and four side of the glass shall be fixed with beading. The door to be provided with handles, locks, door closers and stoppers etc. and other necessary hardwares. Door frames to be covered with 12mm thk BWR ply (Jamb lining) on both sides of the frame and finished with 4mm thk veneer / 1mm thk laminate and exposed edges covered with beading. All veneer and beading surface to be finished with melamine polish as instructed by architects. All complete as per drawings and/or instructions of the architect. All materials to be approved by the architects.				
a	Door with view panel and finished with 4mm thk veneer. Size of Door 3'-3"x7'-0"	Sft	182		
b	Door with view panel and finished with 1mm thk laminate. Size of Door 3'-3"x7'-0"	Sft	290		
8	Providing & fixing Solid Door. The door frame made of approved quality Beach/Safeli wood. The Shutter to be 32mm thk BWR Block Board with both side finished with 4mm thk. veneer with necessary inlays and grooves as per drawing. The edges of the door to be covered with beading (beach wood or equiv) and beading surface to be finished with melamine polish. The door to be provided with door closures, handles, locks, stoppers etc. and other necessary hardwares. Cost inclusive of fixing 1mm thk SS Sheet of 1'-0" ht at bottom of the door. All veneer and beading surface to be finished with melamine polish as instructed by architects. All complete as per drawings and/or instructions of the architect.				
a	Solid Wooden Door (Veneer Finish) Size of Door 3'-0"x7'-0"	Sft	42		
8	<b>Tables and storages.</b>				
1	Providing and fixing L Shape (GM's & DGM's) Table (front table to be curve as shown in the detailed drawing), using 19mm thk BWR block board and additional 19mm thk BWR BB around the edges, top to be supported with SS brackets, above 3" wide leg frame on one side and side table on other side as shown in the detail drawing. Leg, pedestal unit and side table frame work to be made of 19mm thk BWR Block Board, side table to have drawers and storage as shown in the detail drawings. Table shall have a apron made of 19mm thk BWR block board and MDF decorative panels fixed to the frames with SS brackets. All outer exposed surfaces to be finished with 4mm thk veneer with necessary SS inlays and grooves as per drawing, internal surfaces to be finished with 1mm thk laminate. The top table shall have 12mm thk Clear Glass top fixed with SS studs, Keyboard Tray, CPU Stand, Wiremanager and footrest. Pedestal unit and side table to be provided with drawers and storage as shown in the detail drawing. All drawers and storage to have SS brush finished handles, telescope channels, box hinges and locks of approved makes. The table top, all shutters/drawers edges to be closed with approved wood				
i	(GM)Front Table Size 8'-0"x3'-6" x2'6"	Nos.	1		
	Side table 4'-6"x1'-6" x2'6"	Nos.	1		
ii	(DGM)Front Table Size 8'-0"x3'-0" x2'6"	Nos.	2		
	Side table 4'-0"x1'-6"x 2'6"	Nos.	2		



Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030

BILL OF QUANTITIES


No.	Description	Unit	Qty	Rate	Amount
2	Providing and fixing L Shape Table (AGM, CM, Manager and Officer's table), using 19mm thk BWR Block Board for main framework. Table to have a pedestal unit with framework made of 19mm thk BWR Block Board. The table to be provided with 12mm thk Clear Glass top, Keyboard Tray with track, CPU Stand, footrest and Wiremanager of approved make. The side table frame work to be made of 19mm thk BWR Block Board side table to have drawers and storage as shown in the drawings. All outer exposed surfaces to be finished with 1mm thk laminate with necessary inlays and grooves as per drawing, internal surfaces to be finished with 2coates of enamel paint. Pedestal unit should have 2 drawers and storage below. All drawers and storage to have SS brush finished handles, telescope channels, box hinges and locks of approved make. Front table shall have additional framework as shown in the detailed drawing made of 19mm thk BWR block board and finished with 1mm thk laminate. Cost inclusive of making niche in the front as shown in the detailed drawing. The plywood and block board edges to be covered with approved wood beading (beach wood or equiv.). All beading surfaces to be finished with melamine polish as instructed by architects. All as per drawings and/or instructions of the				
i	Executive Table (Laminate Finish) Size - Front table 5'-6" x 2'-6" & Side Table 3'-3" x 1'-6"	Nos.	11		
ii	Manager's and Officer's Table. (Laminate Finish) Size - Front table 5'-0" x 2'-6"x2'6" Side Table 3'-3" x 1'-6".x2'6"	Nos.	22		
3	Providing and fixing 2'-0" deep working counter for workstation, using 19mm thk BWR Block Board for frame work and 12mm thk ply for backing. Each counter to be provided with Pedastal units, Keyboard Tray, CPU Stand, Wiremanager and footrest as shown in the drawing. Pedestal unit should have a drawer and storage. All outer exposed surface of the table to be finished with 1mm thk laminate with necessary inlays and grooves as shown in drawing, internal surfaces to be finished with 2 coats of enamel paint. All drawers and storage to have SS brush finished handles, telescope channels, box hinges and locks of approved makes. The table top, all shutters/drawers edges to be closed with approved wood beading finished with melamine polish. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Rft	45		
4	Providing & fixing Video Conference Table. Table top to be made of 19mm thk BWR Block Board with additional 19mm thk BWR BB at edges for increasing the thickness of the table top. Table main and intermediate supports to be made of 1.5" x1.5" thk Alluminium frame work at 1'-6" c/c on bothsides covered with 6mm thk BWR plywood, table edges to be fixed with wood beading [teak wood or equi.] of size 2"x1.5" thk with a cornice design as shown in the drawing. Table to have foot rest of 4"x2" size, fixed to the table supports. All outer exposed surface of table to be covered with approved 1mm thk; aminate with necessary SS inlays and grooves and finished with melamine polish. Frames with openable shutters to be provided to run wiring below the table top and in apron and wire-managers to be provided as shown in the drawing. Cost inclusive of fixing 12mm thk clear float glass with edges machine polished in the centre of the table, fixed to the table with wood beading. The rate includes 15nos of popup metel boxes. All as per drawings and/or instructions of the architect. All materials to be approved by the architects. 15'x6'0"x2'6"	Nos.	1		
5	Providing & fixing 2'-6" wide Conference Table. Table top to be made of 19mm thk BWR Block Board with additional 19mm thk BWR BB at edges for increasing the thickness of the table top. Table main and intermediate supports to be made of 1.5" x1.5" thk Alluminium frame work at 1'-6" c/c on bothsides covered with 6mm thk BWR plywood, table edges to be fixed with wood beading [teak wood or equi.] of size 2"x1.5" thk with a cornice design as shown in the drawing. Table to have foot rest of 4"x2" size, fixed to the table supports. All outer exposed surface of table to be covered with approved 4mm thk veneer with necessary SS inlays and grooves and finished with melamine polish. Frames with openable shutters to be provided to run wiring below the table top and in apron and wire-managers to be provided as shown in the drawing. Cost inclusive of fixing 12mm thk float glass (with etching) of 9" wide with edges machine polished in the edge of the table, fixed to the table with wood beading. All as per drawings and/or instructions of the architect. All materials to be approved by the architects. 76'x2'6"x2'6"	Sft	76		



**Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030**

**BILL OF QUANTITIES**


No.	Description	Unit	Qty	Rate	Amount
6	DINING TABLE Providing and fixing Dining / Cash Room Table with Table top of 25mm thk BB of size as given below and fixed on the BEECHWOOD supporting frame with screws, bolts etc and PVC edge banding / beading as required. Supporting frame made of 50mm x 50mm beechwood - 4nos legs joined together alround at top/ bottom with 50mmx50mm beechwood members for fixity. All visible surfaces to be finished with 1.0mm thk laminate sheet and all internal and underside surfaces to be fixed with 0.8mm thick lamination sheet with matching grains & grooves polished with melamine spray. All wooden members to be polished with melamine finish complete. 1375 X 610 X 760	Nos.	4		
7	Providing and fixing Reception Table Size : 11'0"x2'6"x3'6" Providing, making and placing in position Grahak Mitra Table with following specifications. Main Table Top to have 25mm block board with 6mm thick acrylic solid surface. The vertical supports of the table is to be made with two side boxing of 75mm x 700mm x 950 mm made with 18mm EG-MDF and the front side boxing to 100mm x 400mm x 950mm on either sides and central boxing of 150mm x 420mm x 1050mm, all made with 18mm EG-MDF finished with 1.0mm laminate on exposed sides. The front of the table to have a 420mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick colour RAL-5017-Traffic Blue blue colored lacquered glass. All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm Laminate as specified to be used. All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding. One readymade CPU mobile pedestal. One Molded Key Board Tray with channels etc., One pedestal of 400mm width having Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary	Nos.	1		
8	Providing and fixing Storage Cabinet using 19mm thk BWR Block Board for main framework, 12mm thk BWR plywood for shelves and 8mm thk BWR plywood for backing. All outer exposed surfaces to be finished with 4mm thk veneer / 1mm thk laminate with necessary SS inlays and grooves as per drawing, internal surfaces to be finished with 1mm thk laminate. Storage to have SS brush finished handles, box hinges and locks of approved makes. All exposed plywood edges shall be covered with wood beading. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.				
i	18" deep storage.(4mm thk veneer for outer exposed surface and 1mm thk laminate for inner exposed surface).	Sft	150		
ii	18" deep storage.(1mm thk laminate for outer exposed surface and 0.8mm laminate for inner exposed surface).	Sft	3000		
9	Providing and fixing Storage with Display Unit, using 19mm thk BWR block board for frame work, intermediate partition and shutters with 8mm thk BWR plywood for backing. Unit to have drawers, glass shelves and shutters as shown in the drawing. Shutters and shelves to be made of 12mm thk glass with exposed edges machine polished, shutters to be fixed with approved make of pivot hinges and shelves to be fixed with brackets of approved makes. All exposed surfaces to be finished with 1mm thk laminate with necessary SS inlays and grooves. All drawers and storage to have SS brush finished handles, telescope channels, box hinges and locks of approved makes and design. All as per drawings and/or instructions of the architect.	Sft	175		
10	Providing and fixing 2'-6" height Storage Cabinet with granite top, using 19mm thk BWR Block Board for main framework, 12mm thk BWR plywood for shelves and 8mm thk BWR plywood for backing. All outer exposed surfaces to be finished with 1mm thk laminate with necessary inlays and grooves as per drawing, internal surfaces to be finished with enamel paint. Storage top to be provided with 20mm thk Granite top (basic price of granite 220/sft) as per drawing, with edges polished (cost inclusive of making necessary cutouts in the granite counter with SS Sink). Storage to have SS brush finished handles, box hinges and locks of approved makes. All exposed plywood edges shall be covered with wood beading. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Sft	25		



Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030					
BILL OF QUANTITIES					
No.	Description	Unit	Qty	Rate	Amount
11	Providing and fixing TV Unit using 19mm thk BWR block board for paneling and counter frame work, intermediate partitions, shelves and shutters and 8mm thk BWR plywood for backing and paneling. TV Unit to have drawers and 12 mm thk clear float glass shelves fixed with SS brackets. All outer exposed surface to be finished with 4mm thk veneer with necessary SS inlays and grooves and all internal exposed surfaces to be finished with 1mm thk laminate. All veneer surface to be finished with melamine polish. All drawers and storage to have SS brush finished handle profiles, soft closing telescope channels, box hinges and locks of approved makes and design. All as per drawings and/or instructions of the architect.	Nos.	3		
12	Providing and fixing Center & Corner Tables with 12mm thk glass top [Modi/Saint Gobain make] with edge machine polished. Top shall be supported with SS stud above 3" wide base both side. Table base frame work to be made of 19mm thk BWR Block Board and to be finished with 1mm thk laminate with necessary SS Strip, inlays and grooves as per drawing. Table below 12mm thk glass shelf [Modi/Saint Gobain make] fixed with 'D'-bracket. All as per drawings and/or instructions of the architect.				
i	Centre Tables - 3'-6" x 1'-6" x 1'-6" (LxDxH)	Nos.	6		
ii	Corner Tables - 1'-6" x 1'-6" x 1'-6" (LxDxH)	Nos.	12		
C	Sofa's				
1	Providing & supplying Sofas with of featherlite make as approved.				
i	Two Seater Sofa [Make: Featherlite/BOSQ/GODREJ Color: Black] (design and quality to be matching for other brands).	Nos.	4		
ii	Three Seater Sofa [Make: Featherlite, Model: Pearl - 238 Color: Black] (design and quality to be matching for other brands).	Nos.	12		
	<b>False Ceiling and Painting Works.</b>				
D	Gypsum Board False Ceiling.				
1	Providing and fixing 12mm thick Gypsum Board False Ceiling with painting finish with G. I. frame work, main framing at 1200mm c/c and intermediate framing at 450mm c/c (as per manufacturers specification) in perfect level including making grooves at the junction of ceiling and walls/columns wherever required. All joints shall be fixed with star screws finished with gypsum jointing tape. Rate shall include providing all curves and moldings, providing cutouts for all the services such as - speakers, AC grills, light fittings, wooden members etc. and also providing & painting of ceiling with 1 or more coats of putty shall be finished [sand paper to be applied to receive paint]. 2 or more coats of Plastic Emulsion Paint to be applied over a coat of primer of approved make and color as approved by architect. Vertical bands, quantity will be taken in "Sft". All as per drawings and/or instructions of the architect.	Sft	9800		
	Item same as above except finished with 3M make "DI-NOC category" of different shades. Film sheet to be fixed after painting the ceiling with 1 or more coats of putty and making the surface smooth and level (cost inclusive of all kind of wastages during fixing). Patterns in film sheet should be aligned accurately with each other in joints. All as per drawings and/or instructions of the architect. Basic price of film sheet Rs. 275/- per Sft). All as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Sft	100		
2	Supplying and installing Grid False Ceiling of Armstrong or equivalent make. Grid work shall be made out of approved Silhouette frame. The main tee, cross tees (length 2'0") filled with Quick release speed steel clips the main frame work of 600x600mm c/c height adjustment. The tiles of 600x600 (2'0"x2'0") of approved design. Rate shall include providing all curves and moldings, providing cutouts for all the services such as - speakers, AC grills, light fitting etc. All as per drawings and/or instructions of the architect.	Sft	13800		
3	Providing & fixing veneer false ceiling with required wooden framing from ceiling using 19mm ply finished with 4mm thk veneer finished with melamine polish.	Sft	500		
4	Providing & applying on partitions and walls Texture Paint with basic preparations etc complete, as approved by the bank/architect. Decorative special effect texture paint on wall surface. Providing & applying effects paint of Asian paints royale play Dune / Safari on to the existing wall surface as per selected design and texture including surface preparation as manufacturer recommendation with all necessary clean/sanding the existing surface, applying primer, emulsion base coat and Dune/Safari top coat in selected design. All coats applied as per layers recommended and with all necessary special effect, tool, roller, masking tape etc. Due care to be taken to ensure that adjacent wall partition, false ceiling, furniture is not stained / marked during above process.	Sft	400		



Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030					
BILL OF QUANTITIES					
No.	Description	Unit	Qty	Rate	Amount
5	Providing and fixing wall paper: Providing and fixing approved quality wall paper of washable grade including all adhesive, cutting, pasting etc complete. (Basic price Rs 1100 per smt excluding tax, transportation, wastage, loading / unloading, etc.) Note : Measurement will be taken only for wall paper actually pasted at site.	Sft	200		
6	providing and fixing graphics to glass on column: Providing and fixing approved make and design of graphic films fixed on surface of the glass/wall/partition/panneling. The wall paper to be fixed on smooth surface cost inclusive making the surfaces smooth with 2 coats of primer coat etc. complete.	Sft	200		
7	Providing and fixing Founder's bust with courien top. Using 19mm BWR ply and wooden supports wherever required, all exposed surface should be fixed with 4mm thk veneer finished with melamine polish as per drawing and Architect instruction.	nos	1		
E	<b>Miscellaneous</b>				
1	Providing & fixing Roller Blinds of approved make and finish. Cost shall include top chanel, fixing charges etc. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Sft	1400		
2	Providing & fixing 100mm wide Vertical Blinds of approved make and finish. Cost shall include top chanel, fixing charges etc. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Sft	600		
3	Providing & fixing Soft Board Panels with 8mm th BWR plywood for backing and 12mm thk soft board covered with approved fabric, all edges covered with wood beading, finished with melamine polish, all as per drawings and/or instructions of the architect. All materials to be approved by the architects.	Sft	200		
4	Providing and fixing Writing Board, made of 12mm thk clear float glass with edges machine polished. A white colored opaque film sheet to be fixed behind the glass. Glass to be fixed to the wall / partition using SS studs. All as per drawings and/or instructions of the architect.	Sft	100		
5	Providing and fixing 3mCrystal etching stickers to glass: Providing and fixing in position Designer Film on all glasses as per drawings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.	Sft	900		
6	DOOR CLOSER : P/ F heavy duty Hudraulic wall mounted door closers (UL rated) 68 KG (product code 1938) of Godrej or equivalent).	No	30		
7	MORTISE LOCK : P/ F SS matt finish NEH 05 - 200 mm door handle set with lock body 2C (Product code 7110) of Godrej or equivalent.	No	30		
8	DOOR STOPPER : P/ F door stopper (ISI mark) of brass.	NO	45		
9	Supply & fixing of pin-up board of size (3'-0" X 1'-6") on front partition of cubical tables.	NO	2		
10	Providing, making and fixing in position 12mm thick toughened clear float glass in sizes as per design with studs. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.	sft	125		
11	LACQUERED GLASS WORK Providing and fixing in position 12mm toughened lacquered glass (colour -) for columns. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 2'x7" subject to site conditions. The rate is for a finished item of work etc., complete as directed.	sft	200		
12	SUGGESTION BOX :- P/ F in position of suggetion box made out of 19mm thick approved board with 1mm thick laminate (as approved) on all exposed surfaces and T.W lipping duly melamine polished etc. complete. The item shall also include locking arrangement and other required hard ware etc. complete internal surfaces of the box shall be painted with enamel paint.	No	2		






Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030

BILL OF QUANTITIES

No.	Description	Unit	Qty	Rate	Amount
13	NOTICE BOARD :- P/F in position notice board of size 900x1500x150mm. The side shall be made out of 19mm thick commercial board with 1mm thick laminate(as approved) on all exposed surfaces. It shall have 12mm thick tack board (celotex or equivalent) wrapped with stretched blazer cloth (raymonds of approx Rs. 200.00 per mtrs.) of approved colour and pattern by Bank. It shall be fixed with the help of dash fasteners of required size. The front shall have 6mm thick float glass sliding shutter in two parts. It shall also have 19mm wide two track aluminium channels for sliding arrangements, all round along with locking arrangements. All the exposed edges of board and ply shall be provided with 6mm thick teak/cedar wood lipping which shall be polished and other internal surfaces to be painted with enamel paint with two or more coat over a coat of primer with the desired shade. The item includes hanging and proper grouting of the notice board in the desired place properly as per requirement of the Bank. Complete in all respect.	No.	2		
14	Providing and fixing 2hours Fire rated 40mm thk door including all necessary hardwares. Size: 3'3"x7'0"	no.	2		
F	<b>MODULAR WORK STATIONS GODREJ/BOSQ/WIPRO/FEATHER LITE/ SOLAR DESIGNS CHENNAI OR EQUIVALENT</b>				
	<b>LOW HEIGHT (1200mm) MODULAR DOUBLE SKIN PARTITION:</b>	SFT	2400		
1	Providing and fixing multi panelled tile based double skin modular partition of minimum 60 mm thickness and of minimum 1200 mm height as per the following technical specifications.				
2	The internal frame shall be made of 16 gauge (minimum 1.60 mm thick) MS material with epoxy powder coating of 50 micron thick. Basic frame is of welded type with connectivity between frames is with bolt & nut arrangement. There shall be 2 race ways to draw the electrical, computer, telephone cables etc at skirting and table top levels.				
3	The vertical connecting frames (corner as well as intermediate ones), top & side rails/trims, corner caps shall be made of 16 gauge thick aluminium extruded sections with powder coating of appropriate colour as per Bank's requirement.				
4	The overall thickness of the partition shall be minimum of 70 mm with internal cavity between tiles shall be 45 mm. The tiles shall be made of minimum 9 mm thick both side pre-laminated particle boards of Novaplan/Bhutahan boards/archidlam or equivalent make, with edges lipped with melamine edge banding. The tiles shall have proper clipping arrangement to get fixed in to the MS frame work. Necessary openings in the boards shall be made for fixing the electrical boxes/sockets, telephone socket, LAN/computer information outlets etc.				
5	Only at select places the tile panels shall be finished with fabric of approved colour with basic rate not less than 250 per metre or plain glass of 6mm thickness with necessary channels, clips, instead of laminate finish. The colour combination of modular partition is as decided by the Bank and approval of the shades shall be obtained at the time of finalising the shop drawings of the modular partitions and before placing orders for fabrication. The payment is based on the elevation area of the modular partition erected at site including trims/finished surface sizes.				
6	<b>INDEPENDENT WORK TABLES</b>				
	Providing & fixing new modular Self standing type work tables of following sizes having 750 mm height, using 25 mm thick pre-laminated particle board of Novopan or equivalent make for table top & for all verticals and of approved shade for table top & for all verticals. The front modesty panel shall be also for the full height of 750 mm without any openings at the bottom. Verticals shall be provided with bottom bushes.				
	All the edges shall be lipped with 2 mm thick PVC edge banding of matching colour. Necessary provision for cable/wire manager to be made. The table top shall be fitted to verticals and front facia using knock down fittings. The unit for payment is per table unit. Any variation in size of the table will be paid on proportionate basis taking volume of the table as the parameter.				
i	Officer tables of 1500 mm (L) x 600 mm (W) x 750 mm (H).	NOS	126		
ii	Clerk tables of 1200 mm (L) x 600 mm (W) x 750 mm (H).	NOS	1		
7	<b>METAL BODY MOBILE PEDASTAL UNIT</b>	NOS	127		



Name of Work: PROPOSED INTERIOR WORKS FOR CIRCLE OFFICE AT 2ND FLOOR V2 BUILDING, PROPERTY NO. 98/4, AIRPORT ROAD, HUBBALLI-580030

**BILL OF QUANTITIES**

No.	Description	Unit	Qty	Rate	Amount
	Providing & installing 3 drawer mobile pedestal boxes of minimum size 460mm wide, 500mm deep and 690mm ht. Pedestal unit shall be made out of CRCA Metal of 20 swg thickness with minimum of 50 micron thick approved colour / shade powder coating on both sides. Facia of the Mobile drawer unit shall be made of 18mm thick pre-laminated particle board. Out of the 3 drawers the top first 2 nos. shall be of 100mm deep drawer & the bottom one shall be of filing drawer with single key Central locking mechanism. The mobile unit shall be supported on 4 nos. lockable castor wheels. The central locking mechanism to be provided on the front side. The drawers shall have push pull arrangements with sliding channels on the bottom mounted glides of Ebco or hettich make.				
	The top two drawers shall be of 100 mm height and the bottom drawer shall have minimum 380 mm height with gallery fitting and fileset fitted inside. The front pre-laminated particle boards all edges shall be finished with 2mm thick matching PVC edge banding. The drawers shall have suitable handles for opening & closing.				
8	<b>KEY BOARD DRAWER</b>	NOS	127		
	Providing & fixing EBCO or equivalent make computer Keyboard platform of minimum 500 mm length (without any sharp edges), made of metal or pre-laminated MDF or PVC body with raised arm rest, height adjustment telescopic channels, pull out mouse pad and with soft palm. The tray movement shall be on ball slides. The internal dimension of these trays shall be suitable to accommodate any standard key board. The front edge of the tray is provided with a soft pad, which serves as a wrist rest. The key board shall be firmly fixed to the bottom of the work station's top using anti-rust CP screws, with proper alignment to have smooth push-pull arrangement of key board tray.				
9	<b>CPU TROLLEY</b>	NOS	127		
	Providing & fixing MS body CPU keeping trolley finished with epoxy coating. The trolley shall be mounted on 4 Nos castor wheels for mobility.				
10	<b>WORK STATION SIDE UNIT</b>				
	Fabricating & supplying the following size independent work station's side storage unit / credenza unit with a central horizontal and a central vertical (for lower half height only) using 18mm thick pre-laminated particle board of Novapan or equivalent brand for verticals, bottom and for internal shelves. For rear portion 9mm thick pre-laminated particle board to be used. All the edges shall be finished with 2 mm thick PVC edge banding of matching colour. The top shall be made of 25 mm thick both side pre-laminated particle board finished with 2.00 mm thick PVC edge banding.				
	The unit shall be fitted using groove and knock down fittings. The sliding shutters shall be made of 18mm thick pre-laminated particle board of same shade & brand with edges lipped with 2 mm thick PVC edge band of matching colour. The sliding arrangement shall be made of Ebco or equivalent make sliding door kit, having PVC channels inserted into base and top using 12mm thick groove. The shutters shall be fitted with PVC wheels on top and bottom, handles, locking arrangement and other essential accessories to make it fully functional & lockable.				
i	Unit having size 1050 mm (L) x 500 mm (D) x 750 mm (H) size	NOS	127		
	<b>Total</b>				
(Total in words.....)					

