

CANARA BANK

INVITATION TO TENDER

ONLY FOR EMPANEL CONTRACTORS

OF

CIRCLE OFFICE KOLKATA

CANARABANK (CLASS – C & above) /

E-SYNDICATE (CLASS – IV & above)

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

INSTRUCTION TO BIDERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

CIVIL & INTERIOR FURNISHING WORKS

AT

CANARA BANK – MIRZANAGAR BRANCH,

DIST.: NORTH 24 PRAGANAS, WB

TENDER NO.: 02/21-22/SP

NAME OF THE CONTRACTOR:

.....

ADDRESS:

.....

SEAL & SIGNATURE OF TENDERER

NOTICE INVITING THE TENDER

To,

M/s

Sealed tenders on item rate basis are invited from panel Contractors for **Civil & Furnishing Works at Mirzanagar Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **23-06-2021** till **30-06-2021**.

Earnest Money Deposit : **NIL**

Period of completion : **30 days**

Last date, time and place for Submission of tender : **On or before 3.00pm, 30-06-2021 to The Divisional Manager, Premises & Estate section Canara Bank, Circle Office Kolkata**

Time and date of opening of tender : **3.30 PM on 30-06-2021**

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

DIVISIONAL MANAGER
Premises & Estate Section
Canara Bank, Circle Office
Kolkata

.....

Date: 22-06-2021

SEAL & SIGNATURE OF TENDERER

GENERAL RULES & INSTRUCTIONS TO TENDERERS

Name of the work: Civil & Furnishing Works to be carried out at Mirzanagar Branch, Dt. North 24 Praganas

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

GST WILL BE PAID EXTRA.

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 30 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

TENDERS:

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

SEAL & SIGNATURE OF TENDERER

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

AGREEMENT

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

EARNEST MONEY AND SECURITY DEPOSIT:

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 3% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipments and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, electrical wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

LIQUIDATED DAMAGES:

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.

TIME PERIOD FOR COMPLETION: 30 days from the date of award of work.

SEAL & SIGNATURE OF TENDERER

FINAL PAYMENTS

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

ESCALATION:

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

CONTRACTORS EMPLOYEES:

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

PAYMENTS:

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

SEAL & SIGNATURE OF TENDERER

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part there of if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

ARBITRATION:

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or branch of the contract[other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sour arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as a foresaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as a foresaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

SEAL & SIGNATURE OF TENDERER

The arbitrator shall be deemed to have entered on the reference the date he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

Date:

**Signature of the Contractor
With seal and address**

SEAL & SIGNATURE OF TENDERER

LIST OF APPROVED MAKES

1	False Ceiling / Channels	India Gypsum / Armstrong / Saint Gobain
2	Wood Frame Work / Wood Section : All Wood, Must be well seasoned, free from knots, other defects decay and defects due to handling and Transportation. Wherever necessary, provide with anti – termite Treatment.	Malaysian Sal / Kapoor
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Ceader / CP Teak
4	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI / Bison by British Paint
5	Fire Reterdant Paint	Industrial grads of Noble / Viper
6	BWR Ply (IS : 710)	Century / Green Panel/ Sylvan/ Archid
7	Flush Door / BWP Block board (IS : 1659)	Century / Green Panel /Sylvan/ Archid
8	Laminate (1.0 mm thk.) (IS : 2046)	Green lam / Century mica / Sunmica / Archid
9	Door Closure (Heavy Duty)	Godrej / Universal
10	Floor Spring (Heavy Duty)	Godrej / Universal/ Sandhu
11	Door Lock (Dead)	Godrej / Hafele /Hettich / Kich / Doorset / Yale
12	Door Handles	Godrej / Hafele /Hettich / Kich / Doorset
13	Drawer / Storage Handle	Godrej / Hafele /Hettich / Kich / Doorset
14	Drawer / Storage Lock (Multipurpose)	Ebco / Hafele /Hettich /Doorset
15	Night latch	Godrej / 4C Acme
16	Screws	GKW / Nettle fold
17	Hinges	CIEF
18	Sliding Telescopic Drawer Channel	Ebco / Earl Behari / Efficient Gadjets
19	Cable Organiser	Ebco / Innofitt Systems (CM 63.C)
20	Adhesive	Fevicol SH / Fevimate TL
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annums / Window Fashion
23	Glass	Modi /AIS / Saint Gobain
24	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / ICI
25	PVC Flooring	Krishna Vinyl / Armstrong / Birla
26	Texture Paint	Spectrum
27	Glass	Modi / AIS / Saint Gobain
28	European WC / Washbasin	Hindware /Parryware
29	Sanitary Fittings	Jaquar / Essco Delux
30	G.I. Pipe	Tata (Medium)
31	Cement	Ultratech / Laferge / ACC
32	Footmat	Birla 3M / Approved Equivalent
33	Vitrified Tiles	Johnson / Kajaria
34	Ceramic Tiles	Johnson / Kajaria
35	Chairs	Godrej/Featherlite/ Nilkamal
36	All other items not covered above	As per sample approved By Bank/ Consultant

NOTE:

Any brands indicated under the items specifications in the schedule of quantities will prevail over the above indicated makes.

Apart from the above makes, any further equivalent make as approved by the Bank, can also be used with prior permission from the Bank.

SEAL & SIGNATURE OF TENDERER

"Civil works at Canara Bank Mirza Nagar Branch"

TENDER FOR CIVIL WORK

Sl.No	DESCRIPTION	Unit	Qty.	Rate	Amount
1	Dismantling & Rubbish removing work				Rs.
a	Dismantling all types of masonry, cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. In ground floor including roof. Removal of rubbish. earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge. (No additional work)	Cu.M.	58		
b	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, leveling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm.	Cu.M.	115		
2	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 300mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation	Cu.M.	54		
3	Filling in foundation or plinth by silver sand in layers not exceeding 300 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	Cu.M.	58		
4	BRICK WORKS				
a	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. (up to 100mm compacted) including labour, materials etc all complete work. (a) 1:3:6 proportion	Sq.M	195		
5	Controlled Cement concrete 100mm thk with well graded stone chips (20 mm graded nominal size) excluding shuttering and reinforcement with complete design of concrete as per IS : 456 and relevant special publications, submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in charge. Consumption of cement will not be less than 300 Kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test and job mix formula. In ground floor and foundation. [using concrete mixture] thickness of concrete not exiding 100mm. M 20 Grade (i) Pakur Variety	Cu.M.	24.61		
6	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. NOTE: Cement 0.152 cu.m per 100 sq.m.	Sq.M	208		
TOTAL (PART "A")					



PART "B"

TENDER FOR INTERIOR FURNISHING WORKS AT CANARA BANK MIRZANAGAR BRANCH

PART "B"						
TENDER FOR INTERIOR FURNISHING WORKS AT CANARA BANK MIRZANAGAR BRANCH						
A	FURNISHING WORK					
S. No.	Description	Quantity	Unit	Rate (In Rs.)	Amount (In Rs.)	
1	PARTITIONS					
a	Low height Partition Providing & fixing of LOW HEIGHT PARTITION (HT. 4'-6") made of 2" x 2" 1st quality Partal wood section at 2'0" c/c both ways 6mm commercial ply of <u>CENTURY / SYLVAN/GREEN/ARCHID</u> Make on both faces finished with 1mm thick laminate of <u>CENTURY/ SUNMICA GREENLAM/ARCHID</u> Make of approved shade. Till the height of 3'-3" and 1'-3"(10mm thk.)glass on top complete with teak beading, The spirit polishing teak sections of approved shade as per drawing Complete in all respects to the complete satisfaction of the Architect.	165	sq. ft.			
b	MANAGER CABIN, TABLE SIDE PARTITION AND CASH CABIN PARTITION WITH DOOR Providing & fixing of PARTITION (HT. 8'-0") (partly glazed (6mm glass) as per design), made of 2" x 2" 1st quality Partal wood frame are 2'-0" c/c both ways 6mm commercial ply of <u>CENTURY / SYLVAN/GREEN/ARCHID</u> Make on both faces finished with 1mm thick laminate of <u>CENTURY/ SUNMICA/ GREENLAM /ARCHID</u> Make, shade as approved. The work includes, spirit polishing of shade on woodwork and steam beach beading etc. Including doors but excluding cost of door closers mortise locks. Complete in all respects to the complete satisfaction of the Architect./Engineer.	350	sq. ft.			
c	Full height Partition Providing & fixing of FULL HEIGHT PARTITION (HT.10'-0") made of 2" x 2" 1st quality Partal wood section at 2'0" c/c both ways 6mm commercial ply of <u>CENTURY / SYLVAN/ ARCHID</u> Make on both faces finished with 1mm thick laminate of <u>CENTURY/ GREENLAM/ARCHID</u> Make of approved shade and shade as approved minimum 10 mm thick glass (4'x3') with itching as required on glazed portion. The spirit polishing teak sections of approved shade as per drawing Complete in all respects to the complete satisfaction of the Architect. Including doors and accesories but excluding cost of door closure.	770	sq. ft.			
(i)	Hydraulic Door closer.(Make Godrej/Universal)	8	no.			
(ii)	Mortise locks (with handles.(Make Godrej)	8	no.			
(iii)	Floor springs for main Entrance Door.(Make Godrej / Universal / Sandhu)	1	no.			
(iv)	Night Latch lock (Make Godgrej) for cash cabin	2	no.			
3	ENTRANCE DOOR					
a	Main Entrance Door 3'-7" x 7'-6" (All aluminium sections powder-coated).glass for doors: 12mm thick one way vision Toughened glass with etching of logo & Aluminium sections for door shutter :3 1/4"x 1 3/4" x 2mm thick & 18" SS handle, lock & Tower bolts etc. complete in all respects including powder coating. (Make: Hindalco / Jindal)	40	sq. ft.			
4	CASH COUNTERS AND TABLES					

	a	Providing and fixing of tables and the total height of 2'-6" as per detailed drawing, cash counter height should be standard as per bank' specification. made up of 19mm commercial board of <u>CENTURY / SYLVAN/GREEN/ARCHID</u> approved Make and finished with 1 mm thick laminate of make, and shade as approved, as per detailed drawing. (with 10mm thick glass on table top) Table shall be provided with drawers sliding on telescopic channels (<u>Ebco/ Godrej make</u>) and one cabinet with proper locking arrangements and keyboard with telescopic channels (<u>Ebco/ Godrej make</u>) . cash counter front glass will be 12mm toughened glass fixed with "D" bracked. Tabletop shall be finished with 1.0mm thick laminate of approved shade & quality. The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, spirit polishing of steam beach/ white cedar beading etc. and The inner exposed surfaces to be painted over one coat of primer and enamel paint of approved shade. complete in all respects to the entire satisfaction of the Architect/Bank.				
	(i)	Manager Table size: 6'-0" x3'0"x 2'-6" (Must be kept loose without fixing to the wall)	1	no.		
	(ii)	Table size: 5'-0" x2'6"x 2'-6" (Must be kept loose without fixing to the wall)	3	no.		
	(iii)	Bank front counter	28	Rft.		
	(iv)	Supplying, fitting and fixing of Cash Counter Cabin with 65 mm. thk double skin laminated glazed partition at 2 sides & back, with 6 mm ply (both side), 1mm thk laminate of approved make & shade & 6 mm. thk. glass including door frame & 35 mm. thk. flush shutter . At front, the total ht. will be 1800 mm., upto 1150 mm. with working counter and rest with 12 mm thk glass with necessary slit & hole for operation. Counter to be completed with drawer unit, keyboard and foot rest, cpu trolley as per architects dwg. The internal size of Cash Counter is 1500 x 2100 x 1950 (h) mm., complete as per design & direction.	2	no.		
	b	SIDE CREDENZAS (Must be kept loose without fixing to the wall) Providing and fixing SIDE CREDENZAS of size 2'-6" to 3'-0" x 1'-6" x 2'-6" made of 19mm commercial board <u>CENTURY / SYLVAN/GREEN/ARCHID</u> finished with 1 mm thick laminate of approved Make and shade on top, sides and front having two drawers and cabinet below complete with all accessories like locks, handles etc. Teak wood beading on all exposed edges with spirit polish.	2	no.		
5		MISCELLANEOUS FURNITURE				
	a	LOW/FULL HEIGHT STORAGE CABINETS Providing & fixing STORAGE CABINETS of 2'-6" ht and 1'-6" deep as per layout plan made up of 19mm commercial board of <u>CENTURY / SYLVAN/GREEN/ARCHID</u> Make and finished with 1mm thick laminate of <u>CENTURY/ SUNMICA/ GREENLAM/ARCHID</u> Make, shade as approved and per detailed drawing. With 2-3 shelves made up of 19mm thick commercial board, in side to be painted over a coat of primer and enamel paint of approved Make and color The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc complete in all respects to the complete satisfaction of the Architect.	150	stf.		

	b	SUGGESTION BOX/WRITING LEDGE/VOUCHER STAND Providing and fixing VOUCHER STAND, including Clearing & Suggestion Box, cheque drop box, writing top at 3'9" height with space for vouchers and 3'x2' soft board-as per specifications laid down in the detailed drawing and as per Bank specifications.	1	no.		
	c	COLUMN/WALL PANNELING (ONLY IN COLUMNS OF BANKING HALL) Providing and fixing of COLUMN PANNELING (9'-0" Ht.) as per design, consisting of 6mm thick commercial ply CENTURY / SYLVAN/GREEN/ARCHID Make fixed on wall with 2" x 2" 1st quality Partal wood framing at 2'-0" C/c both ways. The above shall be laminated with 1mm thick mica CENTURY/ SUNMICA/ GREENLAM Make, The work includes sprit polishing of wood beading, complete in all respects as per detailed drawings to the complete satisfaction of the Architect.	100	sft		
	d	Providing & fixing Notice Board as per bank specofication	1	no.		
	e	Providing & fixing ELECTRICAL PANEL BOXING of 8'-6" ht and depth as per size of the electrical panel, layout plan made up of 19mm commercial board of CENTURY / SYLVAN/GREEN/ARCHID Make and finished with 1mm thick laminate of CENTURY/ SUNMICA/ GREENLAM Make, shade as approved , in side to be painted over a coat of primer and enamel paint of approved Make and color. A fix glass window should also be given to show the indicator LEDS of the panel inside. The work also includes supplying, fixing of hinges, magnetic catchers, handles, Steam Beach lipping, Ventilator Grill etc complete in all respects to the complete satisfaction of the Architect.	1	no.		
6		Providing and fixing 1.5MM thick Steel sheet door with iron (L) TYPE MS frame with necessary fittings complete as per architect insctruction.	1	no.		
7	a	Vertical Blinds				
		Providing and fixing of vertival blinds of bank's approved colour and sprcification.	162	Sft.		
8	a	PAINTING				
		Providing and applying Acrylic emulsion paints after removing the damaged plaster , replastering with 12mm thk cement mortar finished with putty to make the necessary smoothnes , repairing all damages . Then two coats of Primer of approved make to be applied finished with two or more coats of acrylic emulsion paints .The work to be completed as per approval and satisfaction of the Site in charge.	3350	Sft		
	b	SYNTHETIC ENAMEL PAINT : FOR WINDOW GRILL, ROLLING SHUTTER & COLLAPSEABLE GATE etc.	250	Sft		
		TOTAL AMOUNT (B)				

Total Quoted amount For Part "A" -(Civil Work)	
Total Quoted amount For Part "B" -(Furnishing Work)	
Total (Part A + Part B)	

